



County of Santa Cruz

PLANNING DEPARTMENT

701 OCEAN STREET, 4TH FLOOR, SANTA CRUZ, CA 95060
(831) 454-2580 FAX: (831) 454-2131 TDD: (831) 454-2123

KATHLEEN MOLLOY PREVISICH, PLANNING DIRECTOR

www.sccoplanning.com

NOTICE OF INTENT TO ADOPT A MITIGATED NEGATIVE DECLARATION

NOTICE OF PUBLIC REVIEW AND COMMENT PERIOD

Pursuant to the California Environmental Quality Act, the following project has been reviewed by the County Environmental Coordinator to determine if it has a potential to create significant impacts to the environment and, if so, how such impacts could be solved. A Negative Declaration is prepared in cases where the project is determined not to have any significant environmental impacts. Either a Mitigated Negative Declaration or Environmental Impact Report (EIR) is prepared for projects that may result in a significant impact to the environment.

Public review periods are provided for these Environmental Determinations according to the requirements of the County Environmental Review Guidelines. The environmental document is available for review at the County Planning Department located at 701 Ocean Street, in Santa Cruz. You may also view the environmental document on the web at www.sccoplanning.com under the Planning Department menu. If you have questions or comments about this Notice of Intent, please contact Matt Johnston of the Environmental Review staff at (831) 454-3201

The County of Santa Cruz does not discriminate on the basis of disability, and no person shall, by reason of a disability, be denied the benefits of its services, programs or activities. If you require special assistance in order to review this information, please contact Bernice Shawver at (831) 454-3137 (TDD number (831) 454-2123 or (831) 763-8123) to make arrangements.

PROJECT: COUNTY ROUNTREE REHABILITATION AND RE-ENTRY FACILITY

APP #: 151210

APN(S): 052-531-03

PROJECT DESCRIPTION: Proposal to demolish approximately 5,692 square feet of an existing County jail building, to construct additions totaling approximately 14,629 square feet to include a new 7,647 square foot inmate residential wing, new 2,891 square foot visitation building, 2,700 administration addition, 1,391 square foot storage addition, and to remodel approximately 14,256 square feet of existing inmate residential area for a new program training area and 200 square feet of the medium security facility. The project includes grading of approximately 3,800 cubic yards of cut and 4,800 cubic yards of fill, installation of new perimeter security fence, loop road, storm water improvements, outdoor recreation, expanded service yard and inmate intact sally ports, removal of 28 existing trees, planting of 28 replacement trees, and site landscaping. Requires an Amendment to Commercial Development Permit/Coastal Development Permit 90-0603, Soils Report and Arborist Report Review.

The proposed project is located west of the City of Watsonville at 100 Rountree Lane near Harkins Slough Road within the San Andreas Planning Area in the unincorporated County of Santa Cruz

PROJECT LOCATION: The project is located west of the City of Watsonville at 100 Rountree Lane near Harkins Slough Road within the San Andreas Planning Area in the unincorporated County of Santa Cruz.

EXISTING ZONE DISTRICT: PF (Public Facility)

APPLICANT: COUNTY OF SANTA CRUZ, SHERIFF'S OFFICE, C/O BETSEY LYNBERG

OWNER: COUNTY OF SANTA CRUZ SHERIFF'S OFFICE

PROJECT PLANNER: Sheila McDaniel, (831) 454-2255

EMAIL: Sheila.McDaniel@santacruzcounty.us

ACTION: Mitigated Negative Declaration

REVIEW PERIOD: November 10, 2015 through December 10, 2015

This project will be considered at a public hearing by the Planning Commission. The date, time and location have not yet been set. When scheduling does occur, these items will be included in all public hearing notices for the project.



COUNTY OF SANTA CRUZ

PLANNING DEPARTMENT

701 OCEAN STREET, 4TH FLOOR, SANTA CRUZ, CA 95060
(831) 454-2580 FAX: (831) 454-2131 TDD: (831) 454-2123
KATHLEEN MOLLOY PREVISICH, PLANNING DIRECTOR
<http://www.sccoplanning.com/>

MITIGATED NEGATIVE DECLARATION

Project: County Rountree Rehabilitation and Re-Entry Facility

APN(S): 052-531-03

Application #: 151210

Project Description: Proposal to demolish approximately 5,692 square feet of an existing County jail building, to construct additions totaling approximately 14,629 square feet to include a new 7,647 square foot inmate residential wing, new 2,891 square foot visitation building, 2,700 administration addition, 1,391 square foot storage addition, and to remodel approximately 14,256 square feet of existing inmate residential area to a new program training area and 200 square feet to the medium security facility. The project includes grading of approximately 3,800 cubic yards of cut and 4,800 cubic yards of fill, installation of new perimeter security fence, storm water improvements, outdoor recreation, expanded service yard and inmate intact sally ports, removal of 28 existing trees, planting of 28 replacement trees, and site landscaping. Requires an Amendment to Commercial Development Permit/Coastal Development Permit 90-0603, Soils Report and Arborist Report Review.

Project Location: The proposed project is located west of the City of Watsonville at 100 Rountree Lane near Harkins Slough Road within the San Andreas Planning Area in the unincorporated County of Santa Cruz.

Owner: County of Santa Cruz Sheriff's Office

Applicant: County of Santa Cruz Sheriff's Office, C/O Betsey Lynberg

Staff Planner: Sheila McDaniel

Email: Sheila.McDaniel@Santacruzcounty.us

This project will be considered by the Planning Commission at a public hearing. The time, date and location have not been set. When scheduling does occur, these items will be included in all public hearing notices for the project.

California Environmental Quality Act Mitigated Negative Declaration Findings:


Find, that this Mitigated Negative Declaration reflects the decision-making body's independent judgment and analysis, and; that the decision-making body has reviewed and considered the information contained in this Mitigated Negative Declaration and the comments received during the public review period; and, that revisions in the project plans or proposals made by or agreed to by the project applicant would avoid the effects or mitigate the effects to a point where clearly no significant effects would occur; and, on the basis of the whole record before the decision-making body (including this Mitigated Negative Declaration) that there is no substantial evidence that the project as revised will have a significant effect on the environment. The expected environmental impacts of the project are documented in the attached Initial Study on file with the County of Santa Cruz Planning Department located at 701 Ocean Street, 4th Floor, Santa Cruz, California.

Review Period Ends: 12/10/15

Note: This Document is considered Draft until it is Adopted by the Appropriate County of Santa Cruz Decision-Making Body

Date: 11/9/15


MATT JOHNSTON, Environmental Coordinator
(831) 454-3201



County of Santa Cruz

PLANNING DEPARTMENT

701 OCEAN STREET, 4TH FLOOR, SANTA CRUZ, CA 95060
(831) 454-2580 FAX: (831) 454-2131 TDD: (831) 454-2123

KATHLEEN MOLLOY PREVISICH, PLANNING DIRECTOR

www.sccoplanning.com

CALIFORNIA ENVIRONMENTAL QUALITY ACT (CEQA) INITIAL STUDY/ENVIRONMENTAL CHECKLIST

Date: November 2, 2015

Application Number: 151210

County Rountree

Project Name: Rehabilitation and Re-
Entry Facility

Staff Planner: Sheila McDaniel

I. OVERVIEW AND ENVIRONMENTAL DETERMINATION

County of Santa Cruz

APPLICANT: Sheriff's Office, C/O Betsey
Lynberg

APN(s): 052-531-03

OWNER: County of Santa Cruz
Sheriff's Office

SUPERVISORAL DISTRICT: 2

PROJECT LOCATION: The proposed project is located west of the City of Watsonville at 100 Rountree Lane near Harkins Slough Road within the San Andreas Planning Area in the unincorporated County of Santa Cruz (Figure 1). The County of Santa Cruz is bounded on the north by San Mateo County, on the south by Monterey and San Benito counties, on the east by Santa Clara County, and on the south and west by the Monterey Bay and the Pacific Ocean.

ENVIRONMENTAL SETTING AND SURROUNDING LAND USES:

Natural Environment

Santa Cruz County is uniquely situated along the northern end of Monterey Bay approximately 55 miles south of the City of San Francisco along the Central Coast. The Pacific Ocean and Monterey Bay to the west and south, the mountains inland, and the prime agricultural lands along both the northern and southern coast of the county create limitations on the style and amount of building that can take place. Simultaneously, these natural features create an environment that attracts both visitors and new residents every year. The natural landscape provides the basic features that set Santa Cruz apart from the surrounding counties and require specific accommodations to ensure building is done in a safe, responsible and environmentally respectful manner.

The California Coastal Zone affects nearly one third of the land in the urbanized area of the unincorporated County with special restrictions, regulations, and processing procedures required for development within that area. Steep hillsides require extensive review and

engineering to ensure that slopes remain stable, buildings are safe, and water quality is not impacted by increased erosion. The farmland in Santa Cruz County is among the best in the world, and the agriculture industry is a primary economic generator for the County. Preserving this industry in the face of population growth requires that soils best suited to commercial agriculture remain active in crop production rather than converting to other land uses.

PROJECT BACKGROUND:

The County Rountree Correctional facility contains an existing 19,948 square foot minimum security facility for 162 inmates constructed in the 1970's and a 22,765 square foot medium security facility for 96 inmates constructed in the early 1990's. The medium security facility permit included a certified environmental impact report addressing the septic, water, traffic, drainage and water quality, and geology and soils impacts, etc., for the entire correctional facility and occupancy for 258 inmates and staff associated with the facility.

The County of Santa Cruz Sheriff's Office has received SB 1022 Adult Local Criminal Justice Facilities Program funding for the proposed Rountree renovation. The funding from the state will provide for the renovation and construction of additional space primarily at the minimum security facility to provide adequate space for housing, treatment, and rehabilitation programs and services, as well as construction of administration and visitation buildings, and minor renovations and additions to the medium security facility. Previously the County of Santa Cruz found this project to be exempt from CEQA under a Class 2 Categorical exemption; however, the County of Santa Cruz has a specific ordinance that requires an initial study for projects that include more than 1,000 cubic yards of grading. As plans were developed it was determined that the grading amounts would exceed 1,000 cubic yards and that the exemption could not be applied to this proposed project.

The County of Santa Cruz Sheriff's Office is also pursuing funding for a women's facility at the Rountree site. As a separate, stand alone project the County determined that project would also be exempt under a Class 2 Categorical Exemption, filed with the Clerk of the Board on May 27, 2015.

SUMMARY PROJECT DESCRIPTION: Proposal to demolish approximately 5,692 square feet of an existing County jail building, to construct additions totaling approximately 14,629 square feet to include a new 7,647 square foot inmate residential wing, new 2,891 square foot visitation building, 2,700 administration addition, 1,391 square foot storage addition, and to remodel approximately 14,256 square feet of existing inmate residential area to a new program training area and 200 square feet to the medium security facility. The project includes grading of approximately 3,800 cubic yards of cut and 4,800 cubic yards of fill, installation of new perimeter security fence, storm water improvements, outdoor recreation, expanded service yard and inmate intact sally ports, removal of 28 existing trees, planting of 28 replacement trees, and site landscaping. Requires an Amendment to Commercial

Development Permit/Coastal Development Permit 90-0603, Soils Report and Arborist Report Review.

Detailed Project Description:

The County Sheriff proposes to design and construct renovations to and expansions of the existing County Jail at Rountree Lane. Overall, construction would result in approximately 28,885 square feet minimum security housing, visiting, administrative, intake/release, and facility support space, and the renovations would repurpose approximately 14,256 square feet of the minimum security facility into program and support space.

The facility contains a 22,765 square foot medium security building for 96 inmates and a former 19,948 minimum security facility (also known as the x-wing building) for 162 inmates. The existing occupancy of the minimum security facility is proposed to be reduced from 162 to 64 inmates resulting in a reduction in currently permitted occupancy. However, the originally permitted occupancy, though not utilized by this project, would be retained as a previous permit entitlement.

No change in occupancy is proposed at the medium security facility.

The jail renovation and expansion would be constructed primarily of steel, masonry, and concrete for long-term durability.

Minimum Security Housing Addition

Selective demolition of approximately 5,692 square feet of the south wing of the existing 19,948 square foot minimum security building would be completed to allow construction of the new approximately 7,647 square foot housing addition. Total building area following the project work would be approximately 21,903 square feet. Overall, the minimum security facility building would be expanded by approximately 1,955 square feet.

The new housing addition would be constructed as an open span building addition and provide approximately 64 minimum security beds in a two story mezzanine style structure. Each individual inmate sleeping area would be provided with a bed, a desk, and storage area as well as low privacy walls. An officer workstation, video visitation stations, and dayroom are proposed in the central portion of the housing area.

Remaining Minimum Security Renovation

The proposed renovations would repurpose approximately 14,256 square feet of the remaining and existing minimum security building into program and support space for inmates. This renovated area would include vocational/educational program rooms, computer lab, interview and counseling room, group rooms, indoor and outdoor recreational space, administrative support space, restrooms, expanded laundry facilities as well as storage and mechanical rooms. Programs may include vocational and training classes such as academic education, substance abuse help, job training, family reunification, and other types of program functions.

Outdoor recreation would include a basketball court, walking path with exercise station, garden area and site landscaping.

Visitation Building

Facility expansion would include the proposed 2,891 square foot visitation building located in the existing minimum security building patio area now. This building would provide an improved environment for family contact visitation, non-contact visitation rooms, screening room, and support space, such as an interview room, restrooms, mechanical and electrical rooms, etc.

Proposed Administration Building Expansion

An approximately 2,700 addition is proposed on the west side of the existing administration building at the front of the medium security facility. This building addition includes minimum security visitor waiting room, medium security visitor waiting room, conference/training room, safety cell and offices. The new addition also includes a visitor sally port for secure entry, screening and visiting rooms, video visitation stations, waiting, a secure cell, and administrative support space.

Medium Security Facility Improvements/other

The project includes an approximately 1,391 square foot addition for storage space and a 200 square foot renovation for freezer at the medium security facility. Total medium security building area following the project work would be approximately 26,856 square feet. Overall, the medium security facility building would be expanded by approximately 8,182 square feet, including the administration expansion and storage addition.

The project includes installation of secure perimeter fencing, approximately 14 feet in height, and a loop road for site and fire access, and improvements to the existing sally ports for ease of transfer of inmates.

The project would also install upgraded on-site utility systems including but not limited to water, septic sewer, electrical, plumbing, mechanical, heating ventilation and air conditioning, telecommunications, security, fire protection and storm water systems; and all necessary appurtenances. A delivery vehicle sally port would be constructed and an existing parking lot would be refurbished. The project would include seismic upgrades to existing facilities and install perimeter fencing.

ENVIRONMENTAL FACTORS POTENTIALLY AFFECTED: *All of the following potential environmental impacts are evaluated in this Initial Study. Categories that are marked have been analyzed in greater detail based on project specific information.*

- | | |
|---|--|
| <input checked="" type="checkbox"/> Aesthetics and Visual Resources | <input type="checkbox"/> Land Use and Planning |
| <input type="checkbox"/> Agriculture and Forestry Resources | <input type="checkbox"/> Mineral Resources |
| <input type="checkbox"/> Air Quality | <input checked="" type="checkbox"/> Noise |

ENVIRONMENTAL FACTORS POTENTIALLY AFFECTED: All of the following potential environmental impacts are evaluated in this Initial Study. Categories that are marked have been analyzed in greater detail based on project specific information.

- | | |
|--|---|
| <input checked="" type="checkbox"/> Biological Resources | <input type="checkbox"/> Population and Housing |
| <input checked="" type="checkbox"/> Cultural Resources | <input type="checkbox"/> Public Services |
| <input type="checkbox"/> Geology and Soils | <input type="checkbox"/> Recreation |
| <input type="checkbox"/> Greenhouse Gas Emissions | <input type="checkbox"/> Transportation/Traffic |
| <input type="checkbox"/> Hazards and Hazardous Materials | <input type="checkbox"/> Utilities and Service Systems |
| <input checked="" type="checkbox"/> Hydrology/Water Supply/Water Quality | <input type="checkbox"/> Mandatory Findings of Significance |

DISCRETIONARY APPROVAL(S) BEING CONSIDERED:

- | | |
|--|--|
| <input type="checkbox"/> General Plan Amendment | <input checked="" type="checkbox"/> Coastal Development Permit |
| <input type="checkbox"/> Land Division | <input checked="" type="checkbox"/> Grading Permit |
| <input type="checkbox"/> Rezoning | <input type="checkbox"/> Riparian Exception |
| <input checked="" type="checkbox"/> Development Permit | <input type="checkbox"/> LAFCO Annexation |
| <input type="checkbox"/> Sewer Connection Permit | <input type="checkbox"/> Other: |

OTHER PUBLIC AGENCIES WHOSE APPROVAL IS REQUIRED (e.g., permits, financing approval, or participation agreement):

<u>Permit Type/Action</u>	<u>Agency</u>
Construction Permit	Regional Water Quality Control Board

DETERMINATION:

On the basis of this initial evaluation:


- I find that the proposed project COULD NOT have a significant effect on the environment, and a NEGATIVE DECLARATION will be prepared.
- I find that although the proposed project could have a significant effect on the environment, there will not be a significant effect in this case because revisions in the project have been made or agreed to by the project proponent. A MITIGATED NEGATIVE DECLARATION will be prepared.
- I find that the proposed project MAY have a significant effect on the environment, and an ENVIRONMENTAL IMPACT REPORT is required.
- I find that the proposed project MAY have a "potentially significant impact" or "potentially significant unless mitigated" impact on the environment, but at least one effect 1) has been adequately analyzed in an earlier document pursuant to applicable legal standards, and 2) has been addressed by mitigation measures

based on the earlier analysis as described on attached sheets. An ENVIRONMENTAL IMPACT REPORT is required, but it must analyze only the effects that remain to be addressed.


- I find that although the proposed project could have a significant effect on the environment, because all potentially significant effects (a) have been analyzed adequately in an earlier EIR or NEGATIVE DECLARATION pursuant to applicable standards, and (b) have been avoided or mitigated pursuant to that earlier EIR or NEGATIVE DECLARATION, including revisions or mitigation measures that are imposed upon the proposed project, nothing further is required.



Matt Johnston, Environmental Coordinator



Date





This page intentionally left blank.



This page intentionally left blank.

II. BACKGROUND INFORMATION

EXISTING SITE CONDITIONS:

Parcel Size (acres): 93.6 acres
 Existing Land Use: Public Facility/Institutional Designation
 Vegetation: Developed/Landscaped
 Slope in area affected by project: 0 - 30% 31 - 100% N/A
 Nearby Watercourse: Harkins Slough, Gallighan Slough, Perennial Streams
 Distance To: Approximately 500 feet from nearest proposed improvements

ENVIRONMENTAL RESOURCES AND CONSTRAINTS:

Water Supply Watershed:	No	Fault Zone:	N/A
Groundwater Recharge:	Yes, Portion	Scenic Corridor:	Yes
Timber or Mineral:	No	Historic:	N/A
Agricultural Resource:	No	Archaeology:	Yes, portion
Biologically Sensitive Habitat:	Yes, nearby stream area	Noise Constraint:	No
Fire Hazard:	No	Electric Power Lines:	South edge of facility
Floodplain:	No	Solar Access:	Yes
Erosion:	No	Solar Orientation:	Yes
Landslide:	No	Hazardous Materials:	No
Liquefaction:	Yes	Other:	

SERVICES:

Fire Protection:	County Fire	Drainage District:	Zone 4
School District:	Pajaro Valley Unified	Project Access:	Rountree Lane
Sewage Disposal:	Septic	Water Supply:	Well

PLANNING POLICIES:

Zone District: PF (Public Facility)	Special Designation: O (Other Public Facility),] L (Landfill)
General Plan: P (Public Facility)	
Urban Services Line:	<input type="checkbox"/> Inside <input checked="" type="checkbox"/> Outside
Coastal Zone:	<input checked="" type="checkbox"/> Inside <input type="checkbox"/> Outside

III. ENVIRONMENTAL REVIEW CHECKLIST

A. AESTHETICS AND VISUAL RESOURCES

Would the project:

1. Have a substantial adverse effect on a scenic vista?

Discussion:

A portion of the perimeter of the subject property, at southern boundary and northern tip, is designated scenic resource, including the Highway One, San Andreas Road, and Beach Drive. The subject property is not visible from the Highway One Scenic Corridor given that higher topographic contours, located between Highway One and the subject property, preclude any views of the subject property from Highway One. The same is true of higher topographic contours between the subject property and San Andreas Scenic Road and Beach Drive Scenic Road precluding views from San Andreas Road and Beach Drive.

The portion of the site proposed for development is not mapped scenic resource and only views of the project affected by the project are those from private property. County visual resource protection regulations only apply to public view sheds. No visual impacts would occur as a result of the proposed improvements.

2. Substantially damage scenic resources, including, but not limited to, trees, rock outcroppings, and historic buildings within a state scenic highway?

Discussion: Although a portion of the subject property, located at the southern boundary and at the northern tip, is designated scenic resource, the portion of the site proposed for development is not visible from State Highway One given that higher topographic contours, located between Highway One and the subject property, preclude any views of the subject property from Highway One.

3. Substantially degrade the existing visual character or quality of the site and its surroundings?

Discussion: The existing visual setting is comprised of the County Correctional Facility, residential development to the south of the correctional facility, the Buena Vista Landfill to the northeast and northwest and agricultural land to the north. Proposed improvements are proposed within the correctional facility site. The proposed project will not change visual character of the site or surroundings as a result of facility addition and renovations.

4. Create a new source of substantial light or glare which would adversely affect day

or nighttime views in the area?

Discussion:

The project currently includes existing exterior site and building lighting. The project would contribute an incremental amount of night lighting to the visual environment as a result of the proposed lighting on the exterior of the building and along site fencing. However, preliminary lighting plans include lighting directed toward the site with downcast and shielded lights intended to reduce this potential impact to a less than significant level.

B. AGRICULTURE AND FORESTRY RESOURCES

In determining whether impacts to agricultural resources are significant environmental effects, lead agencies may refer to the California Agricultural Land Evaluation and Site Assessment Model (1997) prepared by the California Department of Conservation as an optional model to use in assessing impacts on agriculture and farmland. In determining whether impacts to forest resources, including timberland, are significant environmental effects, lead agencies may refer to information compiled by the California Department of Forestry and Fire Protection regarding the state's inventory of forest land, including the Forest and Range Assessment Project and the Forest Legacy Assessment Project; and forest carbon measurement methodology provided in Forest Protocols adopted by the California Air Resources Board. Would the project:

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 1. Convert Prime Farmland, Unique Farmland, or Farmland of Statewide Importance (Farmland), as shown on the maps prepared pursuant to the Farmland Mapping and Monitoring Program of the California Resources Agency, to non-agricultural use? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The project site does not contain any lands designated as Prime Farmland, Unique Farmland, or Farmland of Statewide Importance as shown on the maps prepared pursuant to the Farmland Mapping and Monitoring Program of the California Resources Agency. In addition, the project does not contain Farmland of Local Importance. Therefore, no Prime Farmland, Unique Farmland, Farmland of Statewide or Farmland of Local Importance would be converted to a non-agricultural use. No impact would occur from project implementation.

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 2. Conflict with existing zoning for agricultural use, or a Williamson Act contract? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The project site is zoned PF (Public Facility), which is not considered to be an agricultural zone. Additionally, the project site's land is not under a Williamson Act Contract. Therefore, the project does not conflict with existing zoning for agricultural use,

or a Williamson Act Contract. No impact is anticipated.

The subject property is located adjacent to parcels containing mapped type 3 agricultural resource designation. However, the proposed improvements are located beyond 200 feet of agricultural resources. No impact to adjoining agricultural resources is anticipated.

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| <p>3. Conflict with existing zoning for, or cause rezoning of, forest land (as defined in Public Resources Code Section 12220(g)), timberland (as defined by Public Resources Code Section 4526), or timberland zoned Timberland Production (as defined by Government Code Section 51104(g))?</p> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The project is not located near land designated as Timber Resource. Therefore, the project would not affect the resource or access to harvest the resource in the future. The timber resource may only be harvested in accordance with California Department of Forestry timber harvest rules and regulations.

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| <p>4. Result in the loss of forest land or conversion of forest land to non-forest use?</p> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: No forest land occurs on the project site or in the immediate vicinity. See discussion under B-3 above. No impact is anticipated.

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| <p>5. Involve other changes in the existing environment which, due to their location or nature, could result in conversion of Farmland, to non-agricultural use or conversion of forest land to non-forest use?</p> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The project site and surrounding area within a radius of 200 feet does not contain any lands designated as Prime Farmland, Unique Farmland, Farmland of Statewide Importance or Farmland of Local Importance as shown on the maps prepared pursuant to the Farmland Mapping and Monitoring Program of the California Resources Agency. Therefore, no Prime Farmland, Unique Farmland, Farmland of Statewide, or Farmland of Local Importance would be converted to a non-agricultural use. In addition, the project site contains no forest land, and no forest land occurs within 200 feet of the proposed project site. Therefore, no impacts are anticipated.

C. AIR QUALITY

The significance criteria established by the Monterey Bay Unified Air Pollution Control District (MBUAPCD) has been relied upon to make the following determinations. Would the project:

1. Conflict with or obstruct implementation of the applicable air quality plan?

Discussion: The project would not conflict with or obstruct any long-range air quality plans of the Monterey Bay Unified Air Pollution Control District (MBUAPCD). Because general construction activity related emissions (i.e., temporary sources) are accounted for in the emission inventories included in the plans, impacts to air quality plan objectives are less than significant. See C-2 below.

General estimated basin-wide construction-related emissions are included in the MBUAPCD emission inventory (which, in part, form the basis for the air quality plans cited below) and are not expected to prevent long-term attainment or maintenance of the ozone and particulate matter standards within the North Central Coast Air Basin (NCCAB). Therefore, temporary construction impacts related to air quality plans for these pollutants from the proposed project would be less than significant, and no mitigation would be required, since they are presently estimated and accounted for in the District’s emission inventory, as described below. No stationary sources would be constructed that would be long-term permanent sources of emissions.

2. Violate any air quality standard or contribute substantially to an existing or projected air quality violation?

Discussion:

The North Central Coast Air Basin (NCCAB) does not meet state standards for ozone and particulate matter (PM₁₀) (MBUAPCD, 2013a). These pollutants are both emitted during construction activities.

Ozone is the main pollutant of concern for the NCCAB. The primary sources of ROG within the air basin are on- and off-road motor vehicles, petroleum production and marketing, solvent evaporation, and prescribed burning. The primary sources of NOx are on- and off-road motor vehicles, stationary source fuel combustion, and industrial processes. In 2010, daily emissions of ROGs were estimated at 63 tons per day. Of this, area-wide sources represented 49 percent, mobile sources represented 36 percent, and stationary sources represented 15 percent. Daily emissions of NOx were estimated at 54 tons per day with 69 percent from mobile sources, 22 percent from stationary sources, and 9 percent from area-wide sources. In addition, the region is “NOx sensitive,” meaning that ozone formation due to local emissions is more limited by the availability of NOx as opposed to the

availability of ROGs (MBUAPCD, 2013b).

PM₁₀ is the other major pollutant of concern for the NCCAB. In the NCCAB, highest particulate levels and most frequent violations occur in the coastal corridor. In this area, fugitive dust from various geological and man-made sources combines to exceed the standard. Nearly three quarters of all NCCAB exceedances occur at these coastal sites where sea salt is often the main factor causing exceedance (MBUAPCD, 2005). In 2005 daily emissions of PM₁₀ were estimated at 102 tons per day. Of this, entrained road dust represented 35 percent of all PM₁₀ emission, windblown dust 20 percent, agricultural tilling operations 15 percent, waste burning 17 percent, construction 4 percent, and mobile sources, industrial processes, and other sources made up 9 percent (MBUAPCD, 2008).

Emissions from construction activities represent temporary impacts that are typically short in duration, depending on the size, phasing, and type of project. Air quality impacts can nevertheless be acute during construction periods, resulting in significant localized impacts to air quality. Table 1 summarizes the threshold of significance for construction activities.

Activity	Potential Threshold*
Construction site with minimal earthmoving	8.1 acres per day
Construction site with earthmoving (grading, excavation)	2.2 acres per day

*Based on Midwest Research Institute, Improvement of Specific Emission Factors (1995). Assumes 21.75 working weekdays per month and daily watering of site.

Note: Construction projects below the screening level thresholds shown above are assumed to be below the **82 lb/day threshold of significance**, while projects with activity levels higher than those above may have a significant impact on air quality. Additional mitigation and analysis of the project impact may be necessary for those construction activities.

Source: Monterey Bay Unified Air Pollution Control District, 2008.

Impacts

As required by the MBUAPCD, construction activities (e.g., excavation, grading, on-site vehicles) which directly generate 82 pounds per day or more of PM₁₀ would have a significant impact on local air quality when they are located nearby and upwind of sensitive receptors such as the community of Watsonville. Construction projects below the screening level thresholds shown in Table 1 are assumed to be below the 82 lb/day threshold of significance, while projects with activity levels higher than those thresholds may have a significant impact on air quality. The proposed project would require minimal grading. Although the project would produce PM₁₀, it would be far below the 82 pounds per day threshold. This would result in less than significant impacts on air quality from the generation of PM₁₀.

Construction projects using typical construction equipment such as dump trucks, scrapers, bulldozers, compactors and front-end loaders that temporarily emit precursors of ozone [i.e., volatile organic compounds (VOC) or oxides of nitrogen (NO_x)], are accommodated in

the emission inventories of state- and federally-required air plans and would not have a significant impact on the attainment and maintenance of ozone AAQS (MBUAPCD 2008).

Although not a mitigation measure per se (i.e., required by law), California ultralow sulfur diesel fuel with a maximum sulfur content of 15 ppm by weight will be used in all diesel-powered equipment, which minimizes sulfur dioxide and particulate matter.

The following Best Management Practices (BMPs) and Best Available Control Technology (BACT) would be implemented during all site excavation and grading.

Best Management Practices

The project impacts would be reduced to a less than significant level with implementation of the required MBUAPCD emission control measures, i.e., diesel engine and fugitive dust controls.

Contracted Diesel Control Measures: In addition to the use of Tiered engines and California ultralow sulfur diesel fuel, the following requirements will be incorporated into contract specifications:

- To minimize potential diesel odor impacts on nearby receptors (pursuant to MBUAPCD Rule 402, Nuisances), construction equipment will be properly tuned. A schedule of tune-ups will be developed and performed for all equipment operating within the project area. A written log of required tune-ups will be maintained and a copy of the log will be submitted to the County of Santa Cruz Department of Public Works (DPW) Planning Director for review every 2,000 service hours.
- Fixed temporary sources of air emissions (such as portable pumps, compressors, generators, etc.) will be electrically powered unless the contractor submits documentation and receives written approval from the County of Santa Cruz DPW that the use of such equipment is not practical, feasible, or available (generally contingent upon power line proximity, capacity, and accessibility). California ultralow sulfur diesel fuel with maximum sulfur content of 15 ppm by weight (ppmw S), or an approved alternative fuel, will be used for on-site fixed equipment not using line power.
- To minimize diesel emission impacts, construction contracts will require off-road compression ignition equipment operators to reduce unnecessary idling with a 2-minute time limit, subject to monitoring and written documentation.
- On-road material hauling vehicles will shut off engines while queuing for loading and unloading for time periods longer than 2 minutes, subject to monitoring and written documentation.
- Off-road diesel equipment will be fitted with verified diesel emission control systems (e.g., diesel oxidation catalysts) to the extent reasonably and

economically feasible.

- Utilize alternative fuel equipment (i.e., compressed or liquefied natural gas, biodiesel, electric) to the extent reasonably and economically feasible.

Feasibility will be determined consistent with Best Available Control Technology (BACT) general criteria: 1) achieved in practice; 2) contained in adopted control measures; 3) technologically feasible; and 4) cost-effective.

Diesel Particulate Matter Emissions Control Measures: In addition, the project will implement the following measures to reduce particulate matter emissions from diesel exhaust:

- Grid power will be used instead of diesel generators where it is feasible to connect to grid power (generally contingent upon power line proximity, capacity, and accessibility).
- The project specifications will include 13 CCR Sections 2480 and 2485, which limit the idling of all diesel-fueled commercial vehicles (weighing over 10,000 pounds, both California- or non-California-based trucks) to 30 seconds at a school or 5 minutes at any location. In addition, the use of diesel auxiliary power systems and main engines will be limited to 5 minutes when within 100 feet of homes or schools while the driver is resting.
- The project specifications will include 17 CCR Section 93115, Airborne Toxic Control Measure for Stationary Compression Ignition Engines, which specifies fuel and fuel additive requirements; emission standards for operation of any stationary, diesel-fueled, compression-ignition engines; and operation restrictions within 500 feet of school grounds when school is in session.
- A schedule of low-emissions tune-ups will be developed and such tune-ups will be performed on all equipment, particularly for haul and delivery trucks.
- Low-sulfur (≤ 15 ppmw S) fuels will be used in all stationary and mobile equipment.

Dust Control Measures: The following controls will be implemented at the construction and staging sites as applicable:

- Water all active construction areas at least twice daily as necessary and indicated by soil and air conditions.
- Cover all trucks hauling soil, sand, and other loose materials or require all trucks to maintain at least 2 feet of freeboard.
- Pave, apply water three times daily, or apply (nontoxic) soil stabilizers on all unpaved access roads, parking areas and staging areas at construction sites.
- Sweep daily (with water sweepers) all paved access roads, parking areas and staging areas at construction sites.

- Sweep streets daily (with water sweepers) if visible soil material is carried onto adjacent public streets.
- All disturbed areas, including storage piles, which are not being actively utilized for construction purposes, will be effectively stabilized of dust emissions using water, chemical stabilizer/suppressant, covered with a tarp or other suitable cover or vegetative ground cover.
- All on-site unpaved roads and off-site unpaved access roads will be effectively stabilized of dust emissions using water or chemical stabilizer/suppressant.
- All land clearing, grubbing, scraping, excavation, land leveling, grading, cut & fill, and demolition activities will be effectively controlled of fugitive dust emissions utilizing application of water or by presoaking.
- When materials are transported off site, all material will be covered, or effectively wetted to limit visible dust emissions, and at least 6 inches of freeboard space from the top of the container will be maintained.
- All operations will limit or expeditiously remove the accumulation of mud or dirt from adjacent public streets at the end of each workday. (The use of dry rotary brushes is expressly prohibited except where preceded or accompanied by sufficient wetting to limit the visible dust emissions. Use of blower devices is expressly forbidden.)
- Following the addition of materials to, or the removal of materials from, the surface of outdoor storage piles, said piles will be effectively stabilized of fugitive dust emissions utilizing sufficient water or chemical stabilizer/suppressant.
- Within urban areas, trackout will be immediately removed when it extends 50 or more feet from the site and at the end of each workday.
- Any site with 150 or more vehicle trips per day will prevent carryout and trackout.
- Hydroseed or apply (nontoxic) soil stabilizers to inactive construction areas (previously graded areas inactive for 10 days or more).
- Enclose, cover, water twice daily, or apply (nontoxic) soil binders to exposed stockpiles (dirt, sand, etc.).
- Limit traffic speeds on unpaved roads to 15 miles per hour.
- Install sandbags or other erosion control measures to prevent silt runoff to public roadways from sites with a slope greater than 1 percent.
- Replant vegetation in disturbed areas as quickly as possible.
- Install wheel washers for all exiting trucks, or wash off all trucks and equipment leaving the site.
- Install wind breaks at windward side(s) of construction areas.
- Suspend excavation and grading activity when winds (instantaneous gusts) exceed 20 miles per hour.

- Limit the area subject to excavation, grading, and other construction activity at any one time.

Implementation of the above BMPs and BACT would ensure that emissions of diesel particulate matter (DPM) and fugitive dust from project excavation and grading would be consistent with the MBUAPCD emissions inventories. Impacts would be less than significant.

- | | | | | |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 3. <i>Result in a cumulatively considerable net increase of any criteria pollutant for which the project region is non-attainment under an applicable federal or state ambient air quality standard (including releasing emissions which exceed quantitative thresholds for ozone precursors)?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion: Project construction would have a limited and temporary potential to contribute to existing violations of California air quality standards for ozone and PM₁₀ primarily through diesel engine exhaust and fugitive dust. However, the Santa Cruz monitoring station has not had any recent violations of federal or state air quality standards mainly through dispersion of construction-related emission sources. BMPs and BACT described above under C-2 would ensure emissions remain below a level of significance. Therefore, the proposed project would not result in a cumulatively considerable net increase in criteria pollutants. The impact on ambient air quality would be less than significant.

- | | | | | |
|---|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 4. <i>Expose sensitive receptors to substantial pollutant concentrations?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|---|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion:

Diesel exhaust contains substances (DPM, toxic air contaminants [TACs], mobile source air toxics [MSATs]) that are suspected carcinogens, along with pulmonary irritants and hazardous compounds, which may affect sensitive receptors such as young children, senior citizens, or those susceptible to respiratory disease. Where construction activity occurs in proximity to long-term sensitive receptors, a potential could exist for unhealthful exposure of those receptors to diesel exhaust, including residential receptors.

Impacts

The proposed project is located in the community of Watsonville and sensitive receptors would be as close as 500 feet from the project area. Due to the intermittent and short-term temporary nature of construction activities (i.e., occurring over a one week period), emissions of DPM, TACs, or MSATs would not be sufficient to pose a significant risk to sensitive receptors from construction equipment operations during the course of the project

with implementation of the following BMPs and BACT.

Best Management Practices

MBUAPCD control measures for diesel exhaust would be implemented as described in Measures AQ-1 and AQ-2. The project would not be expected to expose sensitive receptors to substantial pollutant concentrations. Impacts would be less than significant with the incorporation of mitigation.

5. *Create objectionable odors affecting a substantial number of people?*

Discussion: California ultralow sulfur diesel fuel with a maximum sulfur content of 15 ppm by weight would be used in all diesel-powered equipment, which minimizes emissions of sulfurous gases (sulfur dioxide, hydrogen sulfide, carbon disulfide, and carbonyl sulfide). Therefore, no objectionable odors are anticipated from construction activities associated with the proposed project, and no mitigation measures would be required. The proposed project would not create objectionable odors affecting a substantial number of people; therefore, impacts are expected to be less than significant.

D. BIOLOGICAL RESOURCES

Would the project:

1. *Have a substantial adverse effect, either directly or through habitat modifications, on any species identified as a candidate, sensitive, or special status species in local or regional plans, policies, or regulations, or by the California Department of Fish and Wildlife, or U.S. Fish and Wildlife Service?*

Discussion: The property is mapped for Riparian Woodlands and Biotic Resources associated with the Galligan Slough and Harkins Slough, approximately 300 to 700 feet from the proposed project construction area. The property is not mapped for sensitive habitat in areas proposed for development. According to the California Natural Diversity Data Base (CNDDB), maintained by the California Department of Fish and Wildlife, there are no known special status plant or animal species within the construction site vicinity, and there were no special status species or ruderal grassland species observed in the project area by the Environmental Coordinator.

The lack of suitable habitat and the disturbed nature of the site make it unlikely that any special status plant or animal species occur in the area.

2. *Have a substantial adverse effect on any riparian habitat or sensitive natural*

community identified in local or regional plans, policies, regulations (e.g., wetland, native grassland, special forests, intertidal zone, etc.) or by the California Department of Fish and Wildlife or U.S. Fish and Wildlife Service?

Discussion:

Riparian woodland occurs along the banks of the Galligan Slough and Harkins Slough, approximately 300 to 700 feet from the proposed project construction area. The sloughs are dominated by Coastal and Valley Freshwater Marsh species and Riparian woodland along the higher edge of the banks. Riparian woodland is considered a sensitive natural community by the California Department of Fish and Wildlife (CDFW), and is regulated under the California Fish and Game Code Section 1600 regarding lake and streambed alteration agreements. The riparian woodland in the site area falls within the CDFW stream zone, which extends laterally to the outer edge of riparian vegetation.

The proposed project would not directly impact the riparian woodland as a result of the significant distance between the project improvements and the edge of the riparian woodland. Potential indirect impacts to riparian woodland include site runoff and are addressed by standard best management practices included on the project plans to ensure water quality is maintained and the quality of the riparian woodland is not impacted. As a result, the proposed project will not result in significant impacts to the riparian woodland.

- | | | | | |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 3. <i>Have a substantial adverse effect on federally protected wetlands as defined by Section 404 of the Clean Water Act (including, but not limited to marsh, vernal pool, coastal, etc.) through direct removal, filling, hydrological interruption, or other means?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion: Galligan Slough and Harkin Slough are mapped or designated federally protected wetlands on or adjacent to the project site. The proposed project would not directly impact the wetland as a result of the significant distance, approximately 300 to 700 feet, between the project improvements and the edge of the wetlands. Potential indirect impacts to wetlands include potential site runoff and are addressed by standard best management practices on the project plans to ensure water quality is maintained and the quality of the wetlands are not impacted. As a result, the proposed project will not result in significant impacts to the wetlands.

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 4. <i>Interfere substantially with the movement of any native resident or migratory fish or</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|

wildlife species or migratory wildlife corridors, or impede the use of native wildlife nursery sites?

Discussion: The proposed project does not involve any activities that would interfere with the movements or migrations of fish or wildlife, or impede use of a known wildlife nursery site.

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 5. Conflict with any local policies or ordinances protecting biological resources (such as the Sensitive Habitat Ordinance, Riparian and Wetland Protection Ordinance, and the Significant Tree Protection Ordinance)? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The project would not conflict with any local policies or ordinances.

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 6. Conflict with the provisions of an adopted Habitat Conservation Plan, Natural Community Conservation Plan, or other approved local, regional, or state habitat conservation plan? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The proposed project would not conflict with the provisions of any adopted Habitat Conservation Plan Natural Community Conservation Plan, or other approved local, regional, or state habitat conservation plan. Therefore, no impact would occur.

- | | | | | |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 7. Produce nighttime lighting that would substantially illuminate wildlife habitats? | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion: All construction would be completed during daylight hours. No nighttime lighting impacts from project implementation would occur.

The development area is adjacent to a riparian corridor; however this corridor is approximately 300 to 700 feet away from the project area. Nonetheless, wildlife associated with this habitat could be adversely affected by a new or additional source of light that is not adequately deflected or minimized. The project currently includes existing exterior site and building lighting. The project would contribute an incremental amount of night lighting to the visual environmental as a result of the proposed lighting on the exterior of the building and along site fencing. However, preliminary lighting plans include lighting directed toward the site with downcast and shielded lights intended to reduce any potential impact to a less than significant level.

E. CULTURAL RESOURCES

Would the project:

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 1. Cause a substantial adverse change in | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

the significance of a historical resource as defined in CEQA Guidelines Section 15064.5?

Discussion: The existing structure(s) on the property is/are not designated as a historic resource on any federal, state or local inventory. As a result, no impacts to historical resources would occur from project implementation.

- | | | | | |
|---|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 2. <i>Cause a substantial adverse change in the significance of an archaeological resource pursuant to CEQA Guidelines Section 15064.5?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|---|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion: Although archaeological resources are mapped on the southern tip of the subject property, no archeological resources have been identified in the project construction area. Pursuant to County Code Section 16.40.040, if at any time in the preparation for or process of excavating or otherwise disturbing the ground, any human remains of any age, or any artifact or other evidence of a Native American cultural site which reasonably appears to exceed 100 years of age are discovered, the responsible persons shall immediately cease and desist from all further site excavation and comply with the notification procedures given in County Code Chapter 16.40.040.

Impacts are expected to be less than significant.

- | | | | | |
|---|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 3. <i>Disturb any human remains, including those interred outside of formal cemeteries?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|---|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion: Impacts are expected to be less than significant. However, pursuant to Section 16.40.040 of the Santa Cruz County Code, if at any time during site preparation, excavation, or other ground disturbance associated with this project, human remains are discovered, the responsible persons shall immediately cease and desist from all further site excavation and notify the sheriff-coroner and the Planning Director. If the coroner determines that the remains are not of recent origin, a full archeological report shall be prepared and representatives of the local Native California Indian group shall be contacted. Disturbance shall not resume until the significance of the archeological resource is determined and appropriate mitigations to preserve the resource on the site are established.

- | | | | | |
|---|--------------------------|--------------------------|-------------------------------------|-------------------------------------|
| 4. <i>Would the project cause a substantial adverse change in the significance of a tribal cultural resource as defined in Public Resources Code 21074?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> |
|---|--------------------------|--------------------------|-------------------------------------|-------------------------------------|

Discussion: See discussion under E-2. Impacts would be less than significant.

Potentially Significant Impact	Less than Significant with Mitigation Incorporated	Less than Significant Impact	No Impact
--------------------------------	--	------------------------------	-----------

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 5. Directly or indirectly destroy a unique paleontological resource or site or unique geologic feature? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: No unique paleontological resources or unique geologic features are known to occur in the vicinity of the proposed project. No impacts are anticipated.

F. GEOLOGY AND SOILS

Would the project:

- | | | | | |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 1. Expose people or structures to potential substantial adverse effects, including the risk of loss, injury, or death involving: | | | | |
| A. Rupture of a known earthquake fault, as delineated on the most recent Alquist-Priolo Earthquake Fault Zoning Map issued by the State Geologist for the area or based on other substantial evidence of a known fault? Refer to Division of Mines and Geology Special Publication 42. | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| B. Strong seismic ground shaking? | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| C. Seismic-related ground failure, including liquefaction? | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| D. Landslides? | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |

Discussion (A through D): The project site is located outside of the limits of the State Alquist-Priolo Special Studies Zone (County of Santa Cruz GIS Mapping, California Division of Mines and Geology, 2001). However, the project site is located approximately 3 miles northeast of the Zayante fault zone and 7 miles northeast of the San Andreas fault zone. While the San Andreas fault is larger and considered more active, each fault is capable of generating moderate to severe ground shaking from a major earthquake. Consequently, large earthquakes can be expected in the future. The October 17, 1989 Loma Prieta earthquake (magnitude 7.1) was the second largest earthquake in central California history.

All of Santa Cruz County is subject to some hazard from earthquakes. However, the project site is not located within or adjacent to a county or state mapped fault zone. A geotechnical investigation for the proposed project is required to be reviewed and accepted prior to

project approval. Recommendations of the geotechnical report are required to become conditions of project approval. Therefore, the project will not result in significant impacts.

- | | | | | |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 2. <i>Be located on a geologic unit or soil that is unstable, or that would become unstable as a result of the project, and potentially result in on- or off-site landslide, lateral spreading, subsidence, liquefaction, or collapse?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion:

A geotechnical investigation for the proposed project is required to be reviewed and accepted prior to project approval. Recommendations of the geotechnical report are required to become conditions of project approval. Therefore, the project will not result in significant impacts.

- | | | | | |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 3. <i>Develop land with a slope exceeding 30%?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion: There are slopes between 15% to 30% slope in the project construction area. However, no improvements are proposed on slopes in excess of 30%.

- | | | | | |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 4. <i>Result in substantial soil erosion or the loss of topsoil?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion: Some potential for erosion exists during the construction phase of the project, however, this potential is minimal because the area proposed for development is generally flat and standard erosion controls are a required condition of the project. Prior to approval of a grading or building permit, the project must have an approved Erosion Control Plan (*Section 16.22.060 of the County Code*), which would specify detailed erosion and sedimentation control measures. The plan would include provisions for disturbed areas to be planted with ground cover and to be maintained to minimize surface erosion. Impacts from soil erosion or loss of topsoil would be considered less than significant.

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 5. <i>Be located on expansive soil, as defined in Section 1802.3.2 of the California Building Code (2007), creating substantial risks to life or property?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The project site is mapped for Elkhorn sandy loam, a deep, well-drained soil type that is not typically expansive.

- | | | | | |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 6. <i>Have soils incapable of adequately supporting the use of septic tanks, leach</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|

fields, or alternative waste water disposal systems where sewers are not available for the disposal of waste water?

Discussion: The existing project provides two on-site sewage disposal systems, one for the medium security facility located adjacent to the outdoor area of the minimum security facility and one septic system for the minimum security facility located adjacent to the medium security facility. The proposed project is not proposing to expand the permitted occupancy of the minimum security facility; rather, the proposed use for the rehabilitation project reduces the number of beds from 162 to 64 beds. Thus, expansion of the minimum security septic system is not proposed.

County Environmental Health Services has determined that site conditions are appropriate to support the project provided that applicant complete a routine inspection of the sand filter-septic system by a third-party service provider with a standard monitoring report submitted to Environmental Health to verify the existing system is functioning adequately prior to building permit issuance.

Whitson Engineers provided a memo addressing inspection of the septic system lines and leach fields by Mr Rooter indicating that the septic system is adequate, provided that one of the leach fields be cleaned by "hydroscrubbing in conjunction with treatment with natural enzymes. Additional maintenance recommended by the General Services Agency, who is responsible for maintenance of the system, recommends replacement of the diversion valve and replacement of the effluent pump and pump controller.

Environmental Health staff has also required pumping of the system as it has not been routinely pumped within the last 3 years, with sewage pumping reports forwarded to Environmental Health staff for review. Project conditions will ensure that the current system will continue to function properly.

7. *Result in coastal cliff erosion?*

Discussion: The proposed project is not located in the vicinity of a coastal cliff or bluff; and therefore, would not contribute to coastal cliff erosion. No impact is anticipated.

G. GREENHOUSE GAS EMISSIONS

Would the project:

1. *Generate greenhouse gas emissions, either directly or indirectly, that may have a significant impact on the environment?*

Discussion: The proposed project, like all development, would be responsible for an incremental increase in green house gas emissions by usage of fossil fuels during the site grading and construction. Santa Cruz County has recently adopted a Climate Action

Potentially Significant Impact	Less than Significant with Mitigation Incorporated	Less than Significant Impact	No Impact
--------------------------------	--	------------------------------	-----------

Strategy (CAS) intended to establish specific emission reduction goals and necessary actions to reduce greenhouse gas levels to pre-1990 levels as required under AB 32 legislation. The strategy intends to reduce greenhouse gas emissions and energy consumption by implementing measures such as reducing vehicle miles traveled through the County and regional long range planning efforts and increasing energy efficiency in new and existing buildings and facilities. All project construction equipment would be required to comply with the Regional Air Quality Control Board emissions requirements for construction equipment. As a result, impacts associated with the temporary increase in green house gas emissions are expected to be less than significant.

2. Conflict with an applicable plan, policy or regulation adopted for the purpose of reducing the emissions of greenhouse gases?

Discussion: See the discussion under G-1 above. No significant impacts are anticipated.

H. HAZARDS AND HAZARDOUS MATERIALS

Would the project:

1. Create a significant hazard to the public or the environment as a result of the routine transport, use or disposal of hazardous materials?

Discussion: The facility has a current Hazard Materials Permit from the Environmental Health Services agency; no change in use of hazardous materials is proposed. An asbestos and lead report was produced evaluating the potential for asbestos and lead to be disturbed as a result of the renovation. The report determined that both lead and asbestos are present in low amounts and may be disturbed during the renovation process. In order to reduce impacts from lead and asbestos exposure to less than significant, the following mitigation shall be implemented:

Mitigation Hz 1 - The Project applicant shall be required to retain an EPA-Certified Asbestos Professional and EPA Lead-Safe Certified contractor to prepare an Asbestos/Lead Paint Management Plan that includes lead and asbestos inspection notes and sampling results, as well as a Respiratory Protection Program, Medical Surveillance Requirements, an Injury and Illness Program, asbestos-containing building materials disposal requirements, and a Periodic [Asbestos] Surveillance Schedule. All asbestos-containing building materials and lead identified in the Asbestos/Lead Paint Management Plan shall be removed and disposed of by an EPA-Certified Asbestos Professional and EPA Lead-Safe Certified contractor, as appropriate, in accordance with all state and federal regulations.

2. Create a significant hazard to the public or the environment through reasonably foreseeable upset and accident conditions

involving the release of hazardous materials into the environment?

Discussion: Please see discussion under H-1 above. Project impacts would be considered less than significant.

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 3. <i>Emit hazardous emissions or handle hazardous or acutely hazardous materials, substances, or waste within one-quarter mile of an existing or proposed school?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The project is not located within proximity of a school. No impacts are anticipated.

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 4. <i>Be located on a site which is included on a list of hazardous materials sites compiled pursuant to Government Code Section 65962.5 and, as a result, would it create a significant hazard to the public or the environment?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The project site is not included on the 8/3/2015 list of hazardous sites in Santa Cruz County compiled pursuant to Government Code Section 65962.5. No impacts are anticipated from project implementation.

- | | | | | |
|---|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 5. <i>For a project located within an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport or public use airport, would the project result in a safety hazard for people residing or working in the project area?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|---|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion: The project site is located within approximately 1.2 miles of the Watsonville airport and located along the edge of the outer extent of the airport approach zone, but not located within the restricted approach zones (Clear or A or B zone) that preclude or limit residential development density. Furthermore, the occupancy of the facility (number of inmates and staff) currently permitted at the correctional facility is not intended to be increased as a result of the proposed facility remodel. Therefore, it is not expected that the proposed project would result in a significant safety hazard for inmates or staff in the project area.

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 6. <i>For a project within the vicinity of a private airstrip, would the project result in a safety hazard for people residing or working in the project area?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The proposed project is not located in the vicinity of a private airstrip.

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 7. <i>Impair implementation of or physically interfere with an adopted emergency response plan or emergency evacuation plan?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The proposed project would not conflict with implementation of the County of Santa Cruz Local Hazard Mitigation Plan 2010-2015 (County of Santa Cruz, 2010). Therefore, no impacts to an adopted emergency response plan or evacuation Plan would occur from project implementation.

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 8. <i>Expose people or structures to a significant risk of loss, injury or death involving wildland fires, including where wildlands are adjacent to urbanized areas or where residences are intermixed with wildlands?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The proposed project is not located in a Fire Hazard Area. However, the project design incorporates all applicable fire safety code requirements and includes fire protection devices as required by the local fire agency and State Fire Marshall. Impacts would be less than significant.

I. HYDROLOGY, WATER SUPPLY, AND WATER QUALITY

Would the project:

- | | | | | |
|--|--------------------------|-------------------------------------|--------------------------|--------------------------|
| 1. <i>Violate any water quality standards or waste discharge requirements?</i> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
|--|--------------------------|-------------------------------------|--------------------------|--------------------------|

Discussion:

A portion of the project site drainage system outlets on a slope above a series of water treatment ponds that function as a part of the wastewater treatment for the adjacent farm worker housing facility. The ponds drain directly into Gallighan Slough and a concrete ditch is located above the ponds to divert storm water around them. Preliminary analysis has shown that the existing drainage from the Rountree facility may exceed the capacity of the diversion ditch in less than a 25 year storm event.

Mitigation Dr 1: In order to ensure that storm water from the Rountree facility does not exceed the capacity of the ditch and flood the ponds into Gallighan Slough, the applicant will develop a storm water management plan to be incorporated into the final drainage design. The storm water management plan will determine the ditch capacity and limit the amount of runoff at the existing outlet above the ponds such that the 25 year event will not exceed the diversion ditch capacity. The remaining drainage will be detained on site, percolated where feasible, and disbursed onto the slope west of the pond. The storm water

management plan components (detention, retention and metered dispersion) will be reviewed and approved by the drainage staff of the Department of Public Works prior to consideration by the decision-making body.

- | | | | | | |
|----|---|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 2. | <i>Substantially deplete groundwater supplies or interfere substantially with groundwater recharge such that there would be a net deficit in aquifer volume or a lowering of the local groundwater table level (e.g., the production rate of pre-existing nearby wells would drop to a level which would not support existing land uses or planned uses for which permits have been granted)?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|----|---|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion: The project would rely on an existing private well for water supply. Prior environmental review has determined the well has adequate supply for the capacity of the facility; therefore no impacts will occur as a result of this project.

- | | | | | | |
|----|--|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 3. | <i>Substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river, in a manner which would result in substantial erosion or siltation on- or off-site?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|----|--|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion:

The proposed project is located adjacent to Gallighan Slough, and has the potential to generate water quality impacts during and post construction. However, the proposed project would be consistent with County Code Section 7.79.070, which states, "No person shall make any unpermitted alterations to drainage patterns or modifications to the storm drain system or any channel that is part of receiving waters of the county. No person shall deposit fill, debris, or other material in the storm drain system, a drainage channel, or on the banks of a drainage channel where it might enter the storm drain system or receiving waters and divert or impede flow." It is required that prior to public hearing an erosion control plan would be required per Section 16.22.060 of the County Code. The attached plan would undergo revisions to meet Public Works Design Criteria. The Department of Public Works Drainage Section staff would approve the proposed drainage plan revisions. Impacts would be less than significant.

The following water quality protection and erosion and sediment control best management practices (BMPs) would be implemented, based on standard County requirements, to minimize construction-related contaminants and mobilization of sediment to Gallighan

Slough.

The BMPs will be selected to achieve maximum sediment removal and represent the best available technology that is economically achievable and are subject to review and approval by the County. The County will perform routine inspections of the construction area to verify the BMPs are properly implemented and maintained. The County will notify contractors immediately if there is a noncompliance issue and will require compliance.

The BMPs will include, but are not limited to, the following.

- All earthwork or foundation activities will occur in the dry season (generally between June 1 and October 15).
- Equipment used in and around drainages and wetlands will be in good working order and free of dripping or leaking engine fluids. All vehicle maintenance will be performed at least 300 feet from all drainages and wetlands. Any necessary equipment washing will be carried out where the water cannot flow into drainages or wetlands.
- Any surplus concrete rubble, asphalt, or other rubble from construction will be taken to a local landfill.
- An erosion and sediment control plan will be prepared and implemented for the proposed project. It will include the following provisions and protocols. The Storm Water Pollution Prevention Plan (SWPPP) for the project will detail the applications and type of measures and the allowable exposure of unprotected soils.
 - Discharge from dewatering operations, if needed, and runoff from disturbed areas will be made to conform to the water quality requirements of the waste discharge permit issued by the RWQCB.
 - Temporary erosion control measures, such as sandbagged silt fences, will be applied throughout construction of the proposed project and will be removed after the working area is stabilized or as directed by the engineer. Soil exposure will be minimized through use of temporary BMPs, groundcover, and stabilization measures. Exposed dust-producing surfaces will be sprinkled daily, if necessary, until wet; this measure will be controlled to avoid producing runoff. Paved streets will be swept daily following construction activities.
 - The contractor will conduct periodic maintenance of erosion and sediment control measures.
 - An appropriate seed mix of native species will be planted on disturbed areas upon completion of construction.
 - Cover or apply nontoxic soil stabilizers to inactive construction areas (previously

graded areas inactive for 10 days or more) that could contribute sediment to waterways.

- Enclose and cover exposed stockpiles of dirt or other loose, granular construction materials that could contribute sediment to waterways. Material stockpiles will be located in non-traffic areas only. Side slopes will not be steeper than 2:1. All stockpile areas will be surrounded by a filter fabric fence and interceptor dike.
- Contain soil and filter runoff from disturbed areas by berms, vegetated filters, silt fencing, straw wattle, plastic sheeting, catch basins, or other means necessary to prevent the escape of sediment from the disturbed area.
- Use other temporary erosion control measures (such as silt fences, staked straw bales/wattles, silt/sediment basins and traps, check dams, geofabric, sandbag dikes, and temporary re-vegetation or other ground cover) to control erosion from disturbed areas as necessary.
- Avoid earth or organic material from being deposited or placed where it may be directly carried into the channel.

Implementation of the above BMPs would ensure that water quality impacts to the Gallighan Slough are less than significant.

- | | | | | |
|---|--------------------------|-------------------------------------|--------------------------|--------------------------|
| 4. <i>Substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river, or substantially increase the rate or amount of surface runoff in a manner which would result in flooding, on- or off-site?</i> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
|---|--------------------------|-------------------------------------|--------------------------|--------------------------|

Discussion: A See I1.

- | | | | | |
|--|--------------------------|-------------------------------------|--------------------------|--------------------------|
| 5. <i>Create or contribute runoff water which would exceed the capacity of existing or planned storm water drainage systems, or provide substantial additional sources of polluted runoff?</i> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
|--|--------------------------|-------------------------------------|--------------------------|--------------------------|

Discussion: Please see discussion under I-4 above.

- | | | | | |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 6. <i>Otherwise substantially degrade water quality?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion: Please see discussion under I-1 above. Impacts would be considered less than significant with the implementation of BMPs.

Potentially Significant Impact	Less than Significant with Mitigation Incorporated	Less than Significant Impact	No Impact
--------------------------------	--	------------------------------	-----------

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 7. Place housing within a 100-year flood hazard area as mapped on a federal Flood Hazard Boundary or Flood Insurance Rate Map or other flood hazard delineation map? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: According to the Federal Emergency Management Agency (FEMA) National Flood Insurance Rate Map, dated May 16, 2012, no housing or any other development lies within a 100-year flood hazard area. Impacts from project implementation are expected to be less than significant.

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 8. Place within a 100-year flood hazard area structures which would impede or redirect flood flows? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: According to the Federal Emergency Management Agency (FEMA) National Flood Insurance Rate Map, dated May 16, 2012, no portion of the project site lies within a 100-year flood hazard area. Therefore, the proposed project would not impede or redirect flood flows. No impact would occur.

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 9. Expose people or structures to a significant risk of loss, injury or death involving flooding, including flooding as a result of the failure of a levee or dam? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The proposed project would not increase the risk of flooding and would not lead to the failure of a levee or dam. No impact would occur.

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 10. Inundation by seiche, tsunami, or mudflow? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The project location is on a knoll above the junction of two slough systems that ultimately feed into the Pajaro River near the mouth of the river. In the case of a tsunami or seiche, tidal waters would inundate the flat farmland of the Pajaro Valley before rising 100 feet to the level of the existing facility. No source exists in the vicinity of the project to create a damaging mudflow; therefore there would be no impact.

J. LAND USE AND PLANNING

Would the project:

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 1. Physically divide an established community? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The proposed project does not include any element that would physically

divide an established community. No impact would occur.

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 2. Conflict with any applicable land use plan, policy, or regulation of an agency with jurisdiction over the project (including, but not limited to the general plan, specific plan, local coastal program, or zoning ordinance) adopted for the purpose of avoiding or mitigating an environmental effect? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The proposed project does not conflict with any regulations or policies adopted for the purpose of avoiding or mitigating an environmental effect. No impacts are anticipated.

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 3. Conflict with any applicable habitat conservation plan or natural community conservation plan? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The proposed project would not conflict with any applicable habitat conservation plan or natural community conservation plan. No impact would occur.

K. MINERAL RESOURCES

Would the project:

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 1. Result in the loss of availability of a known mineral resource that would be of value to the region and the residents of the state? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The site does not contain any known mineral resources that would be of value to the region and the residents of the state. Therefore, no impact is anticipated from project implementation.

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 2. Result in the loss of availability of a locally-important mineral resource recovery site delineated on a local general plan, specific plan or other land use plan? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The project site is zoned Public Facility, which is not considered to be an Extractive Use Zone (M-3) nor does it have a Land Use Designation with a Quarry Designation Overlay (Q) (County of Santa Cruz 1994). Therefore, no potentially significant loss of availability of a known mineral resource of locally important mineral resource recovery (extraction) site delineated on a local general plan, specific plan or other land use plan would occur as a result of this project.

L. NOISE

Would the project result in:

- | | | | | |
|---|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 1. Exposure of persons to or generation of noise levels in excess of standards established in the local general plan or noise ordinance, or applicable standards of other agencies? | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|---|--------------------------|--------------------------|-------------------------------------|--------------------------|

The Rountree Facility is in a rural location, adjacent to a landfill, with farm worker housing located on the same parcel, 500 feet from the limits of disturbance. Noise-related impacts that result from this project will be limited to normal workday hours and will be similar in nature to the operational noises of the adjacent landfill and delivery trucks to the Rountree facility. The construction-related noise will be temporary in nature and is considered a less than significant impact.

- | | | | | |
|---|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 2. Exposure of persons to or generation of excessive groundborne vibration or groundborne noise levels? | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|---|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion: See L.1. above

- | | | | | |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 3. A substantial permanent increase in ambient noise levels in the project vicinity above levels existing without the project? | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion: See L.1. above

- | | | | | |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 4. A substantial temporary or periodic increase in ambient noise levels in the project vicinity above levels existing without the project? | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion: See L.1. above

- | | | | | |
|---|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 5. For a project located within an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport or public use airport, would the project expose people residing or working in the project area to excessive noise levels? | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|---|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion: The proposed project is within two miles of a public airport. The Watsonville Airport Noise Contour figure from the City of Watsonville shows the Rountree facility well outside of the 55 decibel area. The impact of noise from the airport on the people working in and around the Rountree facility is less than significant.

Potentially Significant Impact	Less than Significant with Mitigation Incorporated	Less than Significant Impact	No Impact
--------------------------------	--	------------------------------	-----------

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 6. For a project within the vicinity of a private airstrip, would the project expose people residing or working in the project area to excessive noise levels? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The proposed project is not within two miles of a private airstrip. Therefore, the proposed project would not expose people residing or working in the project area. No impact is anticipated.

M. POPULATION AND HOUSING

Would the project:

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 1. Induce substantial population growth in an area, either directly (for example, by proposing new homes and businesses) or indirectly (for example, through extension of roads or other infrastructure)? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The proposed project is designed at the density and intensity of development allowed by the existing use permit for the parcel. Additionally, the project does not involve extensions of utilities (e.g., water, sewer, or new road systems) into areas previously not served. Consequently, it is not expected to have a significant growth-inducing effect. Impacts would be less than significant.

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 2. Displace substantial numbers of existing housing, necessitating the construction of replacement housing elsewhere? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The proposed project would not displace any existing housing. No impact would occur.

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 3. Displace substantial numbers of people, necessitating the construction of replacement housing elsewhere? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The proposed project would not displace a substantial number of people since the project is intended to remodel and existing detention facility. No impact would occur.

N. PUBLIC SERVICES

Would the project:

- | | | | | |
|---|--|--|--|--|
| 1. Would the project result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, need for new or physically altered governmental facilities, the construction of which could cause | | | | |
|---|--|--|--|--|

significant environmental impacts, in order to maintain acceptable service ratios, response times, or other performance objectives for any of the public services:

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| a. Fire protection? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| b. Police protection? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| c. Schools? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| d. Parks? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| e. Other public facilities; including the maintenance of roads? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |

Discussion (a through e): The Rountree Facility is permitted for up to 258 inmates; the proposed project will not increase the capacity of the facility and will have no effects on the demand for public services.

O. RECREATION

Would the project:

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 1. Would the project increase the use of existing neighborhood and regional parks or other recreational facilities such that substantial physical deterioration of the facility would occur or be accelerated? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The proposed project would not substantially increase the use of existing neighborhood and regional parks or other recreational facilities. Impacts would be considered less than significant.

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 2. Does the project include recreational facilities or require the construction or expansion of recreational facilities which might have an adverse physical effect on the environment? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The proposed project does not propose the expansion or construction of additional recreational facilities. No impact would occur.

P. TRANSPORTATION/TRAFFIC

Would the project:

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 1. Conflict with an applicable plan, ordinance or policy establishing measures of effectiveness for the performance of the circulation system, taking into account all | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

modes of transportation including mass transit and non-motorized travel and relevant components of the circulation system, including but not limited to intersections, streets, highways and freeways, pedestrian and bicycle paths, and mass transit?

Discussion: The facility and infrastructure were designed and permitted for a capacity and level of service greater than the proposed project would result in, therefore no transportation-related impacts are expected.

- | | | | | | |
|----|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 2. | <i>Conflict with an applicable congestion management program, including, but not limited to level of service standards and travel demand measures, or other standards established by the county congestion management agency for designated roads or highways?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|----|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: In 2000, at the request of the Santa Cruz County Regional Transportation Commission (SCCRTC), the County of Santa Cruz and other local jurisdictions exercised the option to be exempt from preparation and implementation of a Congestion Management Plan (CMP) per Assembly Bill 2419. As a result, the County of Santa Cruz no longer has a Congestion Management Agency or CMP. The CMP statutes were initially established to create a tool for managing and reducing congestion; however, revisions to those statutes progressively eroded the effectiveness of the CMP. There is also duplication between the CMP and other transportation documents such as the Regional Transportation Plan (RTP) and the Regional Transportation Improvement Program (RTIP). In addition, the goals of the CMP may be carried out through the Regional Transportation Improvement Program and the Regional Transportation Plan. Any functions of the CMP which are useful, desirable and do not already exist in other documents may be incorporated into those documents.

The proposed project would not conflict with either the goals and/or policies of the RTP or with monitoring the delivery of state and federally-funded projects outlined in the RTIP. No impact would occur.

- | | | | | | |
|----|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 3. | <i>Result in a change in air traffic patterns, including either an increase in traffic levels or a change in location that results in substantial safety risks?</i> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|----|---|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: No change in air traffic patterns would result from project implementation.

Therefore, no impact is anticipated.

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 4. Substantially increase hazards due to a design feature (e.g., sharp curves or dangerous intersections) or incompatible uses (e.g., farm equipment)? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The proposed project consists of a remodel of an existing facility. No increase in hazards would occur from project design or from incompatible uses. No impact would occur from project implementation.

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 5. Result in inadequate emergency access? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The project's road access meets County standards and has been approved by the local fire agency or California Department of Forestry, as appropriate.

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| 6. Conflict with adopted policies, plans, or programs regarding public transit, bicycle, or pedestrian facilities, or otherwise decrease the performance or safety of such facilities? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|

Discussion: The proposed project design would comply with current road requirements to prevent potential hazards to motorists, bicyclists, and/or pedestrians. No impact would occur.

Q. UTILITIES AND SERVICE SYSTEMS

Would the project:

- | | | | | |
|---|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 1. Exceed wastewater treatment requirements of the applicable Regional Water Quality Control Board? | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|---|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion: The proposed project's wastewater flows would not violate any wastewater treatment standards. No significant impacts would occur from project implementation.

- | | | | | |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|
| 2. Require or result in the construction of new water or wastewater treatment facilities or expansion of existing facilities, the construction of which could cause significant environmental effects? | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
|--|--------------------------|--------------------------|-------------------------------------|--------------------------|

Discussion: The project would rely on an individual well for water supply. Public water delivery facilities would not have to be expanded. Impacts from project construction would be less than significant.

The project would be served by an existing on-site sewage disposal system, which would be

Potentially Significant Impact	Less than Significant with Mitigation Incorporated	Less than Significant Impact	No Impact
--------------------------------	--	------------------------------	-----------

adequate to accommodate the demands of the project. Impacts would be considered less than significant. Conditions of approval by the Health Services Department require maintenance of the septic system to ensure that environmental health effects do not occur.

3. *Require or result in the construction of new storm water drainage facilities or expansion of existing facilities, the construction of which could cause significant environmental effects?*

Discussion: A portion of the project site drainage system outlets on a slope above a series of water treatment ponds that function as a part of the wastewater treatment for the adjacent farm worker housing facility. The ponds drain directly into Gallighan Slough and a concrete ditch is located above the ponds to divert storm water around them. Analysis has shown that the existing drainage from the Rountree facility exceeds the capacity of the diversion ditch in storms between a 25 design year event. See I.4. for mitigation.

4. *Have sufficient water supplies available to serve the project from existing entitlements and resources, or are new or expanded entitlements needed?*

Discussion: The Rountree facility currently draws water from a private well that has the ability to serve the facility at full capacity. No new water entitlements are required.

5. *Result in determination by the wastewater treatment provider which serves or may serve the project that it has adequate capacity to serve the project's projected demand in addition to the provider's existing commitments?*

Discussion: Please see discussion under Q-2 above. No impact would occur from project implementation.

6. *Be served by a landfill with sufficient permitted capacity to accommodate the project's solid waste disposal needs?*

Discussion: The proposed would not generate solid waste during the operational phase of the project. However, construction debris would be generated during demolition and construction, much of which would be recycled. No impact is anticipated.

7. *Comply with federal, state, and local statutes and regulations related to solid*

waste?

Discussion: The project would comply with all federal, state, and local statutes and regulations related to solid waste disposal. No impact would occur.

R. MANDATORY FINDINGS OF SIGNIFICANCE

1. Does the project have the potential to degrade the quality of the environment, substantially reduce the habitat of a fish or wildlife species, cause a fish or wildlife population to drop below self-sustaining levels, threaten to eliminate a plant or animal community, reduce the number or restrict the range of a rare or endangered plant or animal community, reduce the number or restrict the range of a rare or endangered plant or animal or eliminate important examples of the major periods of California history or prehistory?

Discussion: The potential to degrade the quality of the environment, substantially reduce the habitat of a fish or wildlife species, cause a fish or wildlife population to drop below self-sustaining levels, threaten to eliminate a plant or animal community, reduce the number or restrict the range of a rare or endangered plant or animal or eliminate important examples of the major periods of California history or prehistory were considered in the response to each question in Section III (A through Q) of this Initial Study. Resources that have been evaluated as significant would be potentially impacted by the project, particularly riparian habitat. However, mitigation has been included that clearly reduces these effects to a level below significance. This mitigation includes lighting constraints and storm water management. As a result of this evaluation, there is no substantial evidence that, after mitigation, significant effects associated with this project would result. Therefore, this project has been determined not to meet this Mandatory Finding of Significance.

2. Does the project have impacts that are individually limited, but cumulatively considerable? ("cumulatively considerable" means that the incremental effects of a project are considerable when viewed in connection with the effects of past projects, the effects of other current projects, and the effects of probable future projects)?

Discussion: In addition to project specific impacts, this evaluation considered the projects

potential for incremental effects that are cumulatively considerable. As a result of this evaluation, there is no substantial evidence that there are cumulative effects associated with this project. Therefore, this project has been determined not to meet this Mandatory Finding of Significance.

3. Does the project have environmental effects which will cause substantial adverse effects on human beings, either directly or indirectly?

Discussion: In the evaluation of environmental impacts in this Initial Study, the potential for adverse direct or indirect impacts to human beings were considered in the response to specific questions in Section III (A through Q). As a result of this evaluation, there were determined to be potentially significant effects to human beings related to the following: Hazardous materials. However, mitigation has been included that clearly reduces these effects to a level below significance. As a result of this evaluation, there is no substantial evidence that, after mitigation, there are adverse effects to human beings associated with this project. Therefore, this project has been determined not to meet this Mandatory Finding of Significance.

IV. REFERENCES USED IN THE COMPLETION OF THIS INITIAL STUDY

California Department of Conservation. 1980

Farmland Mapping and Monitoring Program Soil Candidate Listing for Prime Farmland and Farmland of Statewide Importance Santa Cruz County U.S. Department of Agriculture, Natural Resources Conservation Service, soil surveys for Santa Cruz County, California, August 1980.

County of Santa Cruz, 2013

County of Santa Cruz Climate Action Strategy. Approved by the Board of Supervisors on February 26, 2013.

County of Santa Cruz, 2010

County of Santa Cruz Local Hazard Mitigation Plan 2010-2015. Prepared by the County of Santa Cruz Office of Emergency Services.

County of Santa Cruz, 1994

1994 General Plan and Local Coastal Program for the County of Santa Cruz, California. Adopted by the Board of Supervisors on May 24, 1994, and certified by the California Coastal Commission on December 15, 1994.

MBUAPCD, 2008

Monterey Bay Unified Air Pollution Control District (MBUAPCD), CEQA Air Quality Guidelines. Prepared by the MBUAPCD, Adopted October 1995, Revised: February 1997, August 1998, December 1999, September 2000, September 2002, June 2004 and February 2008.

MBUAPCD, 2013a

Monterey Bay Unified Air Pollution Control District, NCCAB (NCCAB) Area Designations and Attainment Status – January 2013. Available online at [http://www.mbuapcd.org/mbuapcd/pdf/Planning/Attainment Status January 2013 2.pdf](http://www.mbuapcd.org/mbuapcd/pdf/Planning/Attainment%20Status%20January%202013%202.pdf)

MBUAPCD, 2013b

Triennial Plan Revision 2009-2011. Monterey Bay Air Pollution Control District. Adopted April 17, 2013.



This page intentionally left blank.

Attachment 1

Negative Declaration Mitigations

NAME: County Rountree Rehabilitation and Re-Entry Facility
APPLICATION: 151210
A.P.N: 052-531-03

NEGATIVE DECLARATION MITIGATIONS

- A. The potential for hazardous materials (asbestos and lead) to impact workers during the demolition phase will be mitigated through the implementation of an Asbestos/Lead Paint Management Plan that includes lead and asbestos inspection notes and sampling results, as well as a Respiratory Protection Program, Medical Surveillance Requirements, an Injury and Illness Program, asbestos-containing building materials disposal requirements, and a Periodic [Asbestos] Surveillance Schedule. All asbestos-containing building materials and lead identified in the Asbestos/Lead Paint Management Plan shall be removed and disposed of by an EPA-Certified Asbestos Professional and EPA Lead-Safe Certified contractor, as appropriate, in accordance with all state and federal regulations.
- B. In order to ensure that storm water from the Rountree facility does not exceed the capacity of the ditch and flood the ponds into Gallighan Slough, the applicant will develop a storm water management plan to be incorporated into the final drainage design. The storm water management plan will determine the ditch capacity and limit the amount of runoff at the existing outlet above the ponds such that the 25 year event will not exceed the diversion ditch capacity. The remaining drainage will be detained on site, percolated where feasible, and disbursed onto the slope west of the pond. The storm water management plan components (detention, retention and metered dispersion) will be reviewed and approved by the drainage staff of the Department of Public Works prior to consideration by the decision-making body.
- C. In order to mitigate impacts of nighttime lighting on the riparian habitat, prior to issuance of a building permit, a lighting plan must be approved by the Planning Department that includes the following measures:
1. All exterior lighting shall be directed away from the riparian corridor and adjacent properties.
 2. Light sources must be shielded by landscaping, fixture design or other physical means.



This page intentionally left blank.

Attachment 2

Supporting Documents



CGL COMPANIES
2405 NATOMAS PARK DR., SUITE 300
SACRAMENTO, CA 95833



WHITSON ENGINEERS
1000 UNIVERSITY AVENUE, SUITE 100
SACRAMENTO, CA 95833



COASTAL DEVELOPMENT PERMIT AMENDMENT

PROJECT NUMBER	0200000000
PROJECT NAME	SANTA CRUZ COUNTY ROUNDTREE REHABILITATION AND RE-ENTRY FACILITY
PROJECT LOCATION	100 ROUNDTREE LANE WASTONVILLE, CA
DATE	APRIL 08/2016
SCALE	C0.2

SANTA CRUZ COUNTY ROUNDTREE REHABILITATION AND RE-ENTRY FACILITY


100 ROUNDTREE LANE WASTONVILLE, CA

CIVIL SITE DETAILS


PROJECT NUMBER: 0200000000
PROJECT NAME: SANTA CRUZ COUNTY ROUNDTREE REHABILITATION AND RE-ENTRY FACILITY
PROJECT LOCATION: 100 ROUNDTREE LANE WASTONVILLE, CA
DATE: APRIL 08/2016
SCALE: C0.2




NOT FOR CONSTRUCTION




1 BIOFILTRATION BMP DETAIL
NO SCALE




2 BIOFILTRATION BMP: INLET CONDITION DETAIL
NO SCALE




3 BMP OUTLET STRUCTURE DETAIL
NO SCALE



4 FIRE DEPARTMENT CONNECTION
NO SCALE



5 SEWER/STORM DRAIN CLEAN OUT
NO SCALE



CGL COMPANIES
2485 NATOMAS PARK DR., SUITE 300
SACRAMENTO, CA 95833

WHITSON ENGINEERS
1000 P. P. FERRER BLVD.
SACRAMENTO, CA 95833



COASTAL DEVELOPMENT PERMIT AMENDMENT


SANTA CRUZ COUNTY ROUNDTREE REHABILITATION AND RE-ENTRY FACILITY

100 ROUNDTREE LANE WASTONVILLE, CA

SCHEMATIC GRADING, DRAINAGE & UTILITY PLAN

PROJECT NUMBER: 40222
DATE: 7/12/2015

C1.1



GRADING KEY NOTES

- 1. NEW PAVEMENT
- 2. NEW SIDEWALK
- 3. NEW CONCRETE CURBS AND GUTTER
- 4. RELOCATE OR REPLACE EXISTING SMH
- 5. NEW FENCE: SEE ARCHITECTURAL PLANS
- 6. NEW RETAINING CONCRETE WALLING TRACK
- 7. NEW BRASS SHARED OPTIC FIBER ACCESS DRAINAGE
- 8. NEW CAST IRON VALVE
- 9. NEW CAST IRON VALVE
- 10. CONNECT TO EXISTING 12" WATER LINE
- 11. NEW DEPARTMENT CONNECTION
- 12. SEE DETAIL 'S' ON SHEET D-2
- 13. NEW BRASS SHARED OPTIC FIBER ACCESS DRAINAGE
- 14. SEE ARCHITECTURAL PLANS FOR CONNECTION
- 15. NEW BRASS SHARED OPTIC FIBER ACCESS DRAINAGE
- 16. NEW BRASS SHARED OPTIC FIBER ACCESS DRAINAGE
- 17. FORMS CONCRETE PAVEMENT
- 18. CONNET STORMWATER TO EXISTING STORMWATER
- 19. CONNET STORMWATER TO EXISTING STORMWATER
- 20. POSSIBLE LOCATION OF EXISTING IN-USE AND RECYCLING AREA: SEE ARCHITECTURAL PLANS

NOTE: EXISTING BRICK REMOVED AS SHOWN ON THE PROJECT, AS DIRECTED BY THE OWNER.

ENTIREMENT AND LOCALIZED AREAS SEE PRELIMINARY FINISH CALCULATIONS FOR THE ENTIRE PROJECT.

APPROXIMATE LIMITS OF DISTURBANCE, TYP.


PROPERTY BOUNDARY (CONTRACT LEASE AREA)

PROPERTY BOUNDARY (CONTRACT LEASE AREA)


PROPERTY BOUNDARY (CONTRACT LEASE AREA)

ABBREVIATIONS
 MDC MASONRY CONCRETE
 APPR APPROVAL
 CATV CABLE TELEVISION
 CTR CONTROL POINT
 ELEV ELEVATION
 ELEC ELECTRICAL
 EL ELEVATION
 G.M. GAS METER
 G.P. GATE VALVE
 H.V. HIGH VOLTAGE
 I.P. INVERT
 M.U. METER
 M.V. METER VALVE
 M.W. METER WALKER
 M.P. METER POINT
 M.V. METER VALVE
 M.W. METER WALKER
 M.P. METER POINT

LEGEND
 ELEV. BOUNDARY CONTOUR
 SUBJECT PROPERTY LINE
 RIGHT OF WAY
 ADJACENT PROPERTY LINE
 EASEMENT LINE
 CONTROL POINT
 BENCHMARK
 FOUND IRON PIPE, TAGGED AS NOTED
 SPOT GRADE
 TREE
 FENCE
 SIGN
 OVERHEAD UTILITY LINES
 UNDERGROUND ELECTRIC LINE
 UTILITY POLE SPARKING HOES AND GUY WIRE
 LIGHT ELECTRODER
 GAS LINE
 GAS VALVE
 STORM DRAIN LINE
 STORM DRAIN INLET
 SANITARY SEWER LINE (GRAVITY)
 SANITARY SEWER MANHOLE



NOTES:
 1. THIS MAP REPRESENTS A TOPOGRAPHIC SURVEY PERFORMED BY WHITSON ENGINEERS IN DECEMBER OF 2014.
 2. THIS MAP DOES NOT SHOW EXISTING OR PROPOSED UTILITY LINES OR CONDUIT EASEMENTS, ZONING OR REGULATORY INFORMATION OR ANY OTHER REFS AND SPECIFICALLY REQUESTED BY THE CLIENT.
 3. THIS MAP DOES NOT SHOW EXISTING OR PROPOSED UTILITY LINES OR CONDUIT EASEMENTS, ZONING OR REGULATORY INFORMATION OR ANY OTHER REFS AND SPECIFICALLY REQUESTED BY THE CLIENT.
 4. DISTANCES AND DIMENSIONS SHOWN ARE EXPRESSED IN FEET AND DECIMALS THEREOF, UNLESS OTHERWISE NOTED.
 5. PROJECT BENCHMARK: A SPIKE IN ASPHALT IN AERIAL PHOTO AT THE INTERSECTION OF TERRA ALTA DR. AND BOONVILLE LANE W. OF SANTA CRUZ, CALIFORNIA. ELEVATION = 1524.11 FEET (409.14 METERS). A GUY WIRE AND WALKER IN ASPHALT LOCATED ON THE NORTHERLY SIDE OF A 15 FEET SOUTHLY OF A FIRE HYDRANT. ELEVATION = 1523.17 FEET.
 6. UNDERGROUND UTILITIES, IF SHOWN, ARE BASED ON FIELD LOCATION INFORMATION PROVIDED BY THE UNDERGROUND UTILITY LOCATION COMPANY AND A CONDUIT EASEMENT. UNDERGROUND UTILITIES PROVIDED BY THE OWNER, EXACT LOCATIONS AND DEPTHS SHOULD BE DETERMINED PRIOR TO CONSTRUCTION.
 7. DIAMETERS OF TREES ARE SHOWN IN INCHES. TREES SMALLER THAN 6" WERE NOT NECESSARILY LOCATED AS PART OF THIS SURVEY.




APPROX. LOCATION FOR WIRE LINE
COULD NOT FIELD LOCATED
WTR. LINE SURFACE FEATURES

POLE ENCUMBER
2000-04-15


EXTREME LIMITS OF
ROUNTREE LANE
FOR TOPOGRAHY &
BOUNDARY MAP BY DEWITT &
DATED 3-23-1990


CONC.
CONC. INSET TOP (1)
CONC. INSET TOP (1)
CONC. INSET TOP (1)
CONC. INSET TOP (1)






**SANTA CRUZ COUNTY SHERIFF'S OFFICE ROUNDTREE REHABILITATION
AND RE-ENTRY FACILITY RENOVATION**






1 X-BUILDING - SOUTHEAST 1





2 MEDIUM SECURITY BUILDING - NORTH 1




SANTA CRUZ COUNTY SHERIFF'S OFFICE ROUNDTREE REHABILITATION AND RE-ENTRY FACILITY RENOVATION











TYPICAL SECURITY FENCE



SANTA CRUZ COUNTY SHERIFF'S OFFICE ROUNDTREE REHABILITATION AND RE-ENTRY FACILITY RENOVATION



SANTA CRUZ COUNTY SHERIFF'S OFFICE ROUNDTREE REHABILITATION AND RE-ENTRY FACILITY RENOVATION



SANTA CRUZ COUNTY SHERIFF'S OFFICE ROUNDTREE REHABILITATION AND RE-ENTRY FACILITY RENOVATION

**A SURVEY OF THE SIGNIFICANT TREES THAT WILL BE IMPACTED BY THE PROPOSED
RENOVATION AND EXPANSION OF THE SANTA CRUZ COUNTY ROUNDTREE FACILITY
AT 90 ROUNDTREE LANE - WATSONVILLE**

Prepared at the request of:
Rodney Trujillo – Registered Civil Engineer
Whitson Engineers
2425 Porter Street, Suite 2
Soquel, CA 95073
rtrujillo@whitsonengineers.com

Site visit by:
Nigel Belton – ISA Certified Arborist WE-0410A
June 26, 2015

Job – SC Roundtree – 6-15

TABLE OF CONTENTS:

Background ----- 1
Assignment ----- 1
Summary ----- 2
Limiting Conditions ----- 3
Discussion Regarding Proposed Improvements ----- 3
General Recommendations Concerning Tree Preservation and Protection ----- 4
- Tree Protection Zone Fencing ----- 4
- Utility, Sewer and Drainage Trenching Requirements ----- 4
- Irrigation and Mulching guidelines ----- 5
- Pruning and support cable installation guidelines ----- 5
Observations and Recommendations pertaining to Individual Trees ----- 5
Inspection Schedule ----- 28

**A SURVEY OF THE SIGNIFICANT TREES THAT WILL BE IMPACTED BY THE PROPOSED RENOVATION AND EXPANSION OF THE SANTA CRUZ COUNTY ROUNDTREE FACILITY AT 90 ROUNDTREE LANE WATSONVILLE
Site visit by Nigel Belton, ISA Certified Arborist WE-0410A – June 26, 2015**

**A SURVEY OF THE SIGNIFICANT TREES THAT WILL BE IMPACTED BY THE PROPOSED
RENOVATION AND EXPANSION OF THE SANTA CRUZ COUNTY ROUNDTREE FACILITY
AT 90 ROUNDTREE LANE WATSONVILLE**

Background:

Rodney Trujillo of Whitson Engineers contacted me regarding the provision of a survey and an arborist's report concerning the significant trees located at the Santa Cruz County Roundtree Rehabilitation and Re-entry Facility located at 90 Roundtree Lane, Watsonville. The County plans to expand and renovate this facility which will have an impact on many existing trees.

I met on site with Lieutenant Paul Ramos of the Santa Cruz County Sherriff's Office and Constance Conroy, Project Manager, County of Santa Cruz Department of Public Works to discuss the scope of the improvement work and potential impacts on the significant trees. Lieutenant Ramos instructed me that in addition to those trees that will have to be removed because of their proximity to the new structures and infrastructure, all of the larger trees situated in close proximity to the new security fence location will also have to be removed.

Assignment:

This assignment entails the provision of a tree survey and a preliminary arborist's report concerning 75 trees over 6 inches in diameter measured at 54 inches above grade (diameter at breast height or DBH). The tree survey identifies individual trees with numbered tags affixed to their trunks. The tag numbers correspond with the numbers utilized in the tree survey chart, the arborist's report and an accompanying tree survey map.

The tree survey chart documents tree dimensions and conditions. It identifies those trees that must be removed because of their condition ratings and /or locations within the proximity of proposed construction work.

This preliminary arborist's report provides recommendations pertaining to design considerations in order to minimize root loss and damage within the critical root zones of affected trees. The report also includes tree protection strategies that must be implemented during the construction phase of this project. These recommendations include tree protection zone fencing requirements and root preservation strategies.

The arborist's report also includes recommendations concerning the maintenance of the health, structural integrity and safety of individual trees that are designated for preservation.

Summary:

Seventy five trees with trunk diameters over six inches measured at breast height were surveyed on the Roundtree Facility Site. Fifty three of these trees are situated within closer proximity to the proposed remodeling and expansion work and as such are included in the recommendations of this report. The 22 London Plane Sycamores situated in the landscape next to the frontage of Roundtree lane are setback well away from proposed construction activities and have all been recommended for preservation.

A total of 43 trees on this site are recommended for preservation and protection during the construction period.

The critical root zones of all trees designated for preservation must be protected from damage with Tree Protection Zone Fences. These fences must be installed before demolition work proceeds and remain in place throughout the entire construction period (the TPZ fence locations are shown on the attached Tree Location Map). The TPZ fences must not be dismantled or moved without the consent of the project arborist. Care must also be taken whenever any construction work or trenching for new drains or utilities will encroach within critical root zone areas (These areas are generally defined as being within tree canopy driplines). The project arborist must inspect and supervise all work in critical root zone areas.

The Coast Redwood Trees on this site are exhibiting symptoms of drought stress and should be irrigated as prescribed in the report if water is available for this purpose. These trees should be mulched with woodchips to conserve soil moisture and improve their growing conditions.

The three large Nichols Eucalyptus Trees recommended for preservation require pruning work and the installation of support cables as specified in the report. These actions are recommended to improve the structural integrity and safety of these trees.

The project arborist must visit the site and provide supervision as specified in the inspection schedule.

At total of 28 eight trees are recommended for removal.

Fourteen of these trees have been designated for removal because of their locations in close proximity to areas of construction or within construction footprints.

Seven of these trees are designated for removal because of their close proximity to the proposed security fence.

Seven trees have been recommended for removal because of poor condition ratings (poor health or structural concerns).

The status of Four London Planes Sycamore Trees located on the west side of the facility is yet to be determined.

These trees may have to be removed if it is determined that they are too close to the proposed security fence location and the corner of the minimum security building.

Limiting Conditions:

This is a preliminary report based on information regarding the proposed improvements provided to me at this time.

The inspection of these trees was made from the ground only. No trees were climbed to examine above ground structures nor were any trees examined below the soil grade to examine their root structures. Inspections of tree structures were limited to visual examinations only.

Note that recommendations regarding pruning work and the installation of tree support systems are intended to reduce the chance of tree failures but must never be considered as being guarantees against such events. Trees can and sometimes do fail despite these procedures being implemented.

Discussion Regarding the Proposed Improvements:

The proposed improvements for the rehabilitation facility will entail the construction and expansion of buildings on the north side of the existing structures and the expansion of the service yard on the east side.

These improvements include the construction of a new administration addition to the medium security building and a new visitation building adjacent to the minimum security building. The construction of these buildings will impact a number of significant trees (trees with trunks over six inches diameter at breast height) that are either located within or near to their footprints (about 14 trees).

The expansion of the service yard on the east side of the facility will require the removal of six Coast Redwood Trees.

The installation of a new security fence on the north and west sides of the facility will require the removal of all significant trees located within close proximity to the inside of this structure for security reasons.

The 22 London Plane Sycamore Trees located in the two areas of turf next to Roundtree Lane should not be impacted because the footprints of the adjacent parking and driveway infrastructure will remain the same.

A SURVEY OF THE SIGNIFICANT TREES THAT WILL BE IMPACTED BY THE PROPOSED RENOVATION AND EXPANSION OF THE SANTA CRUZ COUNTY ROUNDTREE FACILITY AT 90 ROUNDTREE LANE WATSONVILLE

Site visit by Nigel Belton, ISA Certified Arborist WE-0410A – June 26, 2015

General Recommendations Concerning Tree Protection and Preservation:

1 - Tree Protection Zone Fence Specifications:

Tree Protection Zone (TPZ) fencing must be installed as specified in this report and shown on the attached Tree Location Map. The TPZ fencing must be inspected and documented by the project arborist before any demolition, grading and site work can proceed. These protective fences must not be removed (or moved) during the construction period without the consent of the project arborist. No equipment or vehicles can enter the TPZ at any time, nor can grading work or utility trenching occur within these protected areas without the direct supervision of the project arborist. No construction materials or construction waste may be stored or dumped within the defined TPZ areas. Laminated Tree Protection Zone notices that provide descriptions of these protections and restrictions must be attached to these fences at 10 foot intervals.

TPZ fences must consist of five foot tall (or higher) steel chain-link fencing attached to steel pipes driven 24 inches into the ground where in close proximity to the construction areas (concerning Trees #1 through #53).

TPZ fencing can consist of plastic snow fencing attached to steel standards concerning the protection of the 22 London Plane Trees located in the two turf areas next to Roundtree Lane.

2 – Utility, Sewer Line and Drainage Trenching Requirements:

Note that all new underground utilities, drains, sewer lines and septic systems must be routed around the outside of the canopy drip lines of protected trees where possible in order to protect these Critical Root Zone areas from damage. In the event that utilities and drains must be routed under tree canopies they must be setback as far as possible from tree trunks to reduce the potential for root loss and damage.

In the event that trenching work for utilities (including sanitary sewer lines, water, electrical, gas, telephone and cable services) or storm drains and irrigation lines must encroach within the defined Tree Protection Zones, the project arborist must provide guidance and site supervision regarding appropriate root protection and preservation strategies in order to minimize root loss and disturbance.

Root protection strategies may entail either tunneling the under significant roots (roots between 1.5 and 2 inches diameter contingent on their locations) to insert these services underneath them or root pruning work, contingent on the proximity of these services to the trunks of the affected trees. Root pruning work entails the use of a sharp saw to cleanly cut significant sized roots (roots over 1.5 inches diameter) at the edge of the excavation in order to avoid tearing damage (a sawzall is recommended for this work).

In some cases an initial soil cut must be made in the service trench at between 12 and 16 inches outside of the final edge of excavation line in order to locate any significant roots. These larger roots must then be hand dug back to the final excavation line and pruned with a saw before the trenching work is completed.

3 – Irrigation and Mulching to Improve Tree Health and Conserve Soil Moisture:

The provision of supplemental irrigation to drought stressed trees is recommended only if enough water is available for this purpose. In the event that enough water is available for this purpose, it should be applied to the soil surface at a rate of 10 gallons per inch of trunk diameter measured at 54 inches above grade (DBH measurement). The water should be delivered through irrigation tubing (such as Netafim product) or by means of soaker hoses every three weeks until the onset of adequate rainfall patterns.

The installation of wood chip mulches (bark products are not recommended) should serve to conserve soil moisture and improve soil health over time. The mulches should be applied at a depth of three to four inches and cover the soil surface within and beyond canopy drip lines where space allows. These mulches should be setback at least nine inches from tree trunks as a general rule.

4 – Tree Pruning and Support Cable Installation Work:

All tree pruning and support system installation work must be performed by a State Licensed tree service provider in accordance with ISA Pruning Standards and ANSI A300 Best Management Practices. This work must be performed under the supervision of an ISA Certified Arborist.

Support cables should be inspected every two years to ensure that they are in good condition.

Observations and Recommendations Pertaining to Individual Trees:

Tree's #1, #2 & #3 – Three Coast Redwood (*Sequoia sempervirens*):

These large trees have 41, 43 & 37 inch, 38 inch and 38 inch DBH trunk measurements, respectively.

These tree are located in the landscape adjacent to the north side of the medium security building. The trees are growing in unirrigated turf which is in poor condition.

These trees exhibit fair to good condition ratings despite having some symptoms of initial drought stress. Tree #1 has a co-dominant structure (3 similar sized trunks) but appears to be structurally sound. I noted the presence of large exposed roots on the soil surface under the canopies of these trees.



1 - The preliminary grading and drainage plan prepared by Whitson Engineers shows three areas of concern within the proximity of these trees. These issues concern include the following features.

(1) - A proposed pathway which will be in very close proximity to the trunk of Tree #3.

I recommend that the new pathway is re-routed to be set back as far as possible from the trunks of these trees. One option will be to route the path next to the curb line of the adjacent parking stalls and then have it turn 90 degrees to access the front entrance of the building. The installation of a simple split-rail fence may be one way to discourage people from taking a short cut under these trees. The new path should be constructed on as close to existing grade as possible to avoid cutting too many roots within the critical root zones of these trees. This should entail the installation of a reinforced concrete pathway that does not rely on base material for its structural integrity.

(2) - The bio swale/retention system shown in close proximity to Tree's #2 & #3.

The bio swale location must be moved further west to be situated beyond the canopy dripline of Tree #3. Tree's #4, #5 & #6 (three Douglas Firs) are recommended for removal and their location appears to be a good option for the new bio swale.

(3) - The concrete pad between the new pathway and the building.

The pad that connects the front of the building to the new pathway on the plan must be constructed of reinforced concrete installed on grade to avoid excessive root loss.

2 - Install Tree Protection Zone Fencing as shown on the Tree Location Map before any demolition and construction equipment comes on site.

3 - The three Coast Redwood Trees are vulnerable to drought stress at this time.

I recommend that these trees are irrigated (as prescribed in the notes on page 5) if enough water is available for this purpose. I understand that this prescription will entail the application of a lot of water so it should be understood that this is a general guideline. The actual volume of water used can be lower than initially calculated if necessary. I also recommend that the soil under the canopy of these trees is covered by a wood chip mulch to conserve soil moisture and improve soil health.

Tree's #4, #5 & #6 – Three Douglas Firs (*Pseudotsuga menziesii*):

These trees have 16 inch, 11 inch and 21 inch DBH measurements, respectively.



A SURVEY OF THE SIGNIFICANT TREES THAT WILL BE IMPACTED BY THE PROPOSED RENOVATION AND EXPANSION OF THE SANTA CRUZ COUNTY ROUNDTREE FACILITY AT 90 ROUNDTREE LANE WATSONVILLE

Site visit by Nigel Belton, ISA Certified Arborist WE-0410A – June 26, 2015

Page 7

The three Douglas firs have poor condition ratings due to the effects of the drought. The foliage of these trees is thin and of poor color. The new seasons shoot growth in the branch tips is poor when compared to healthy trees of the same species.

I recommend that the Douglas Firs are removed because they are in poor health and have become unattractive due to drought stress. These firs should be replaced with more drought tolerant trees.

Tree's #7 and #8 – Two Liquidambar Trees (*Liquidambar styraciflua*):

Both of these trees exhibit good health but have very poor structures due to their co-dominant growth patterns. The trees have multiple stems emanating from common trunks near ground level and as such are vulnerable to structural failures.



The footprint of the new administration addition will encroach within the location of Tree #7 and will be setback about three feet away from the trunk of Tree #8.

Both of these trees must be removed because of their locations relative to footprint of the new administration building.

A SURVEY OF THE SIGNIFICANT TREES THAT WILL BE IMPACTED BY THE PROPOSED RENOVATION AND EXPANSION OF THE SANTA CRUZ COUNTY ROUNDTREE FACILITY AT 90 ROUNDTREE LANE WATSONVILLE

Site visit by Nigel Belton, ISA Certified Arborist WE-0410A – June 26, 2015

Tree #9 – 33 inch DBH Nichols Eucalyptus (*Eucalyptus nicholii*):

The trunk of this tree will be located about 12 feet inside the location of the new security fence shown on the improvement plans.




The tree exhibits good health and has a fair structure rating.

I recommend that this tree is removed because of its proximity to the inside of the new security fence.

Tree #10 – 47 inch DBH Nichols Eucalyptus:

This tree exhibits good health and has a fair structure rating. The base of the trunk of this tree will be situated about two feet outside of the new security fence location. I noted two large buttress roots growing on the soil surface for some distance from the trunk.



I recommend that this tree is removed due to its close proximity to the proposed security fence which will be built on a concrete footing. The footing location will encroach through both of these supportive roots which are too high above existing grade to allow for the utilization of a grade beam on piers as an alternative design to preserve this tree.

Tree #11 – 11 inch DBH Nichols Eucalyptus:

This tree exhibits poor health and has a fair structure rating. The tree is unattractive in appearance and is being suppressed by the larger adjacent trees.



I recommend that this tree is removed because of its poor condition and appearance.

Tree #12 – 21 & 14 inch DBH Nichols Eucalyptus:

This tree exhibits good health but has a very poor co-dominant structure.



The trunk divides into two co-dominant stems at about three feet above grade. The largest stem leans heavily westward over the proposed landscape area next to the new visitation center. The majority of the limb structure is concentrated at the ends of both stems.

I recommend that this tree is removed because of its poor structural condition rating. The tree is vulnerable to failure in the area of attachment between the two stems. This condition cannot be effectively mitigated through pruning work without ruining the appearance of this tree or by instillation of a support cable.

Tree #13 – 33 inch DBH Nichols Eucalyptus:

This large tree exhibits good health and has a fair to poor structure rating. I noted that the trunk of this tree divides into two co-dominant stems at approximately nine feet above grade. The area of attachment between these stems is narrow and relatively poor. The north facing scaffold limb (attached at about five feet above grade) is poorly attached to the trunk and appears to be heavy and over-extended. The limb structure within the balance of the upper canopy appears to be relatively light and structurally sound.



I recommend that this tree is preserved and pruned and cabled to improve its structure and safety.

1 - Prune to remove any larger dead wood over ½ inch diameter and reduce weight in the end of the north facing scaffold limb. This limb could also be removed completely.

2 - Install five support cables high in the canopy of this tree in such a way as to create two triangulations of cable between the four main stems. Utilize 5/8 through rods with threaded amon eyes as attachment points for 5/16 EHS Grade cable and thimbles. Inspect the tree and the cable hardware every two years.

3 - Install Tree Protection Zone Fencing as shown on the Tree Location Map before any demolition and construction equipment comes on site.

Tree #14 – 8 & 5 inch DBH Nichols Eucalyptus:

A small tree located next to the entrance driveway.

I recommend that this tree is preserved.

1 - Install Tree Protection Zone Fencing as shown on the Tree Location Map before any demolition and construction equipment comes on site.

Tree #15 – 7/8/10 inch DBH Nichols Eucalyptus:

This tree exhibits very poor health and has a poor structure rating.



I recommend that this tree is removed because of its poor condition ratings.

Tree #16 – 18 & 13 inch DBH Nichols Eucalyptus:

This tree exhibits good health but has a very poor structure rating. The tree leans heavily towards the west and over the proposed visitation building site.



I recommend that this tree is removed because of its very poor structure rating and encroachment over the footprint of the proposed building.

Tree #17 – 51 inch DBH Nichols Eucalyptus:

This large specimen exhibits good health and has a fair to poor structure at this time. The tree has a co-dominant structure at about five feet above grade. The south facing co-dominant stem leans heavily to the southeast.



I recommend that this tree is preserved and maintained to improve its structural integrity and safety.

1 - Prune this tree to remove larger dead wood and reduce weight in limb ends (end weight reduction).

2 - Install one cable set between the two co-dominant stems utilizing 5/8 inch or ¾ inch diameter through rods with amon eyes and 5/16 inch diameter EHS Grade cable.

3 - Install Tree Protection Zone Fencing as shown on the Tree Location Map before any demolition and construction equipment comes on site.

Tree #18 – 50 & 22 inch DBH Nichols Eucalyptus:

This large tree exhibits good health and a fair to poor structure rating. The tree has four co-dominant stems attached to a common trunk at between four and six feet above grade.



I recommend that this tree is preserved and maintained to improve its structural integrity and safety.

- 1 - Prune this tree to remove larger dead wood and reduce end weight.**
- 2 - Install three cable sets in between the three most vertical stems utilizing 5/8 or 3/4 inch diameter through rods and amon eyes with 5/16 inch EHS Grade cable (triangulate the cables). Install one direct cable to the north facing stem utilizing the same hardware.**
- 3 - Install Tree Protection Zone Fencing as shown on the Tree Location Map before any demolition and construction equipment comes on site.**

Tree #19 – 8/5/14 inch DBH Bottle Brush (*Callistemon viminalis*):

This weeping Bottlebrush will be located within the proposed security fence.

I recommend that this tree is removed because of concerns about its location and visibility.

Tree #20 – 6/5/4 inch DBH Bottle Brush:

This tree is the taller of the two Bottle Brush trees. It is in good condition and is an attractive specimen.




I recommend that if at all possible this tree is preserved because it is an attractive tree.

1 – I recommend that the canopy of this tree is raised high enough to provide an acceptable amount of visibility and line of sight regarding security concerns.

2 - Install Tree Protection Zone Fencing as shown on the Tree Location Map before any demolition and construction equipment comes on site.

Tree #21 – 17 inch DBH London Plane Sycamore (*Platanus x Acerifolia*):

This tree exhibits good health and has a fair structure rating. The trunk of this tree will be setback about seven feet from the foundation footprint of the new visitation structure.



1 - I recommend that this tree is considered for preservation in the event that any required over excavation for the foundation does not encroach within six feet of the trunk. Otherwise the tree should be removed.

2 - Install Tree Protection Zone Fencing as shown on the Tree Location Map before any demolition and construction equipment comes on site (setback four feet from the edge of the foundation line).

3 – A root protection buffer may be required in the area between the foundation and the fence.

Tree's #22 through #27 – Six London Plane Sycamores:

17, 16, 16, 18, 16 & 23 inch DBH, respectively.

These trees are located within the footprint of the proposed visitation center.



Remove all of these trees because of their location within the building footprint.

Tree #28 – 16 inch DBH Liquidambar Tree:

This tree has a relatively good condition rating and is located about eight feet inside the proposed security fence location.



Remove this tree because of its proximity to the new security fence location.

Tree #29 – 11 inch DBH Liquidambar Tree:

This tree has a good condition rating and is located next to the outside of the proposed security fence.

Remove this tree because of its location next to the security fence footprint.

Tree's #30 through #33 – Four London Plane Sycamores:

9, 12, 13 & 18 inch DBH measurements, respectively. These trees located on the west side of the facility exhibit good health and fair structures having been pollarded.

Three of these trees may have to be removed because of their proximity to the new security fence location (Tree's #30 through #32). In the event that they can be retained, they will serve to provide shade and beauty to this area.


I recommend that all of these considerations are evaluated carefully before a final decision is made. The fourth tree (Tree #33) is located near the corner of the building and is set well back from the proposed fence site. This tree could be retained if there are no compelling reasons for it to be removed as it does not appear to be in the way of any improvements.



1 – In the event that any of these trees are to be preserved, install Tree Protection Zone Fencing as shown on the Tree Location Map before any demolition and construction equipment comes on site.

Tree #34 – 8 inch DBH Liquidambar Tree:


This tree is located near the apex of the northwest and southwest wings of the minimum security building. It has a very poor structure having lost its most dominant co-dominant stem in a previous storm event. The trunk of this tree is setback about three and a half feet from the adjacent asphalt parking surface.



This tree must be removed because of its compromised structure and location near the parking area which will be vulnerable to root damage over time.

Tree #35 – 7 inch DBH Liquidambar Tree:

This tree is located within three and a half feet of the asphalt parking area in the apex of northwest and southwest wings of the minimum security building.




Remove this tree because of the high probability of significant infrastructure damage from root growth over time. This species is noted for its destructive root growth pattern.

Tree's #36 through #40 – Five Coast Redwood Trees:

These trees have 11, 14, 19, 18 & 20 inch DBH measurements, respectively.

The trees are located within the footprint of the proposed expanded service yard area on the east side of the facility. The Coast Redwood trees exhibit fair to poor health due to the effects of the drought.

These trees are recommended for removal because of their location within the area of proposed improvement work.



Tree #41 – 13 inch DBH Coast Redwood:

This tree exhibits fair to poor health due to the effects of the drought and will be located about seven feet back from the expanded service yard area.

This tree is recommended for removal because of its proximity to the proposed service yard area.

Tree's #42 & #43 – Two Coast Redwoods:

These trees have 11 & 23 inch DBH measurements, respectfully.

These trees exhibit fair to poor health due to the effects of the drought.

I recommend that these trees are preserved.

1 - Mulch and irrigate these trees if additional water is available for this purpose (see the notes on irrigation and mulching on page 5).

2 – Install Tree Protection Zone Fencing as shown on the Tree Location Map.

Tree's #44 & #45 – Two Coast Redwood Trees:

These trees have 21 and 32 inch DBH measurements, respectively and are located in the landscaped area that protrudes into the parking area to the north of the service yard. The trees exhibit fair health due to drought stress.



These trees will be encroached upon by the proposed expansion of the asphalt driveway surface and a new pathway.

I recommend the removal of both trees because of their locations within close proximity to proposed infrastructure changes.

Tree #46 – 20 inch DBH Coast Redwood:

This tree is also located in the landscape area that protrudes into the parking lot. The tree exhibits fair health due to drought stress and has a notable trunk distortion.

I recommend that this tree is preserved despite its odd trunk development which does not appear to be of concern at this time.

1 - Mulch and irrigate this tree if additional water is available for this purpose (see the notes on irrigation and mulching on page 5).

2 – Install Tree Protection Zone Fencing as shown on the Tree Location Map.

Tree's #47 through #53 – Seven Coast Redwood Trees:

These trees have 13, 20, 19, 19, 17, 18 & 15/8 inch DBH measurements, respectfully.

All of these trees are located within the boundary fence adjoining the eastern parking area. The trees are in fair condition due to the effects of the drought.



I recommend that all of these trees are preserved.


1 - Mulch and irrigate these trees if additional water is available for this purpose (see the notes on irrigation and mulching on page 5).

2 – Install Tree Protection Zone Fencing as shown on the Tree Location Map.

Tree's #54 through 75 – Twenty two London Plane Sycamores:

I estimate that the average trunk measurements for these trees approximate 14 inches diameter.

These trees are located in the two areas of turf located next to the frontage of Roundtree Lane and have not been tagged numerically as they are situated well away from proposed construction activity. The trees exhibit good health and have fair to good structure ratings.



I recommend that these trees are protected by two lines of plastic snow fencing installed next to the curbs as shown on the Tree Location Map.

Inspection Schedule:

This development site must be inspected by the project arborist before and during the construction period at the following times:

- 1 – Meet with the tree removal and pruning contractor to identify trees designated for removal and discuss the scope of pruning and cable installation work.**
- 2 – Inspect this site when the Tree Protection Zone (TPZ) fences have been installed after the tree removal and pruning work has been completed and before any demolition, grading and construction work proceeds.**
- 3 – Inspect the site any time utility, sewer line or drainage trenches encroach under the drip lines of protected trees. Provide guidance and supervision regarding root protection procedures.**
- 4 – Inspect this site when excavation work for the construction of new building foundations, infrastructure and bio- retention areas encroach within the canopy drip lines of protected trees.**

Please do not hesitate to contact me if you have any questions.

Respectfully submitted

Nigel Belton

Attachments:

- Assumptions and Limiting Conditions
- Tree Survey Chart
- Tree Location map
- ISA Pruning Standards
- Sample Tree Protection Zone notice

TREE SURVEY CHART
 ROUND TREE REHABILITATION CENTER
 90 ROUNDTREE LANE - WATSONVILLE

<i>SHEET 1.</i>									
#	TREE NAME	TRUNK DIAMETER @ 54" ABOVE GRADE - (DBH)	ESTIMATED HEIGHT	ESTIMATED SPREAD	HEALTH	STRUCTURE	SUITABLE FOR PRESERVATION	RECOMMENDED FOR REMOVAL	COMMENTS
1	Coast Redwood (<i>Sequoia sempervirens</i>)	41/43 /37	60	30	3	3	X		Three trunks (co-dominant structure). Signs of initial drought stress.
2	Coast Redwood	3/8	55	25	3	2	X		Signs of initial drought stress.
3	Coast Redwood	38	50	20	2	3	X		Signs of initial drought stress.
4	Douglas Fir (<i>Pseudotsuga menziesii</i>)	16	5	20	4	3		X	Very drought stressed.
5	Douglas Fir	11	40	15	4	3		X	Very drought stressed.
6	Douglas Fir	21	60	20	4	3		X	Very drought stressed.
7	Liquidambar (<i>Liquidambar styraciflua</i>)	10/11/ 11/15	60	30	2	4		X	Located near to the footprint of the proposed administration building. Poor co-dominant structure.
8	Liquidambar	14/11/ 17	60	25	2	4		X	Located within the proposed construction footprint.
9	Nichols Eucalyptus (<i>Eucalyptus nicholii</i>)	33	80	35	2	3		X	Remove because of location inside proposed security fence.
10	Nichols Eucalyptus	47	90	55	1	3		X	Remove because of location next to proposed security fence.
11	Nichols Eucalyptus	11	80	15	4	3		X	Very poor health.
12	Nichols Eucalyptus	21/14	70	45	2	4		X	Very poor structure.
13	Nichols Eucalyptus	33	90	50	1	3	X		Recommended for pruning and support cable installation work.
14	Nichols Eucalyptus	8/5	15	15	3	2	X		A small specimen that can be retained.
15	Nichols Eucalyptus	7/8/10	25	20	4	4		X	Located within the proposed security fence footprint.
16	Nichols Eucalyptus	18/13	70	30	1	4		X	Very poor structure.

TREE SURVEY CHART
 ROUND TREE REHABILITATION CENTER
 90 ROUNDTREE LANE - WATSONVILLE

#	TREE NAME	TRUNK DIAMETER @ 54" ABOVE GRADE - (DBH)	ESTIMATED HEIGHT	ESTIMATED SPREAD	HEALTH	STRUCTURE	SUITABLE FOR PRESERVATION	RECOMMENDED FOR REMOVAL	COMMENTS
17	Nichols Eucalyptus	51	80	50	1	3	X		Recommended for pruning and support cable installation work.
18	Nichols Eucalyptus	50/22	90	35	1	3	X		Recommended for pruning and support cable installation.
19	Bottle Brush (<i>Callistemon ssp</i>)	8/5/4	15	15	1	3		X	Located near the proposed security fence.
20	Bottle Brush	6/5/4	15	15	1	3	X		Setback some distance from the proposed security fence.
21	London Plane Tree <i>Platanus x acerifolia</i>	17	15	15	1	3	X		Preserve if not too significantly impacted by proposed construction.
22	London Plane Tree	17	15	15	1	3		X	Located within the footprint of the proposed visitation center.
23	London Plane Tree	16	15	15	1	3		X	Located within the footprint of the proposed visitation center.
24	London Plane Tree	16	15	15	1	3		X	Located within the footprint of the proposed visitation center.
25	London Plane Tree	18	15	15	1	3		X	Located within the footprint of the proposed visitation center.
26	London Plane Tree	16	20	15	1	3		X	Located within the footprint of the proposed visitation center.
27	London Plane Tree	23	20	15	1	3		X	Located within the footprint of the proposed visitation center.
28	Liquidambar	16	30	25	1	3		X	Located near the proposed security fence.
29	Liquidambar	11	25	25	1	3		X	Located near the proposed security fence.
30	London Plane Tree	9	25	20	1	3		?	Located near the proposed security fence. Possible candidate for preservation.

TREE SURVEY CHART
 ROUND TREE REHABILITATION CENTER
 90 ROUNDTREE LANE - WATSONVILLE

<i>SHEET 3.</i>									
#	TREE NAME	TRUNK DIAMETER @ 54" ABOVE GRADE - (DBH)	ESTIMATED HEIGHT	ESTIMATED SPREAD	HEALTH	STRUCTURE	SUITABLE FOR PRESERVATION	RECOMMENDED FOR REMOVAL	COMMENTS
31	London Plane Tree	12	25	20	2	3		?	Located near the proposed security fence. Possible candidate for preservation.
32	London Plane Tree	13	20	20	2	3		?	Located near the proposed security fence. Possible candidate for preservation.
33	London Plane Tree	18	15	15	2	3		?	Located near the corner of the building. Possible candidate for preservation.
34	Liquidambar	8	15	10	1	4		X	Badly damaged tree.
35	Liquidambar	7	20	20	1	3		X	Located near the asphalt parking area. Potential root damage in the future.
36	Coast Redwood	11	15	15	3	2		X	Located within the footprint of the proposed service area expansion.
37	Coast Redwood	14	20	20	3	2		X	Located within the footprint of the proposed service area expansion.
38	Coast Redwood	19	30	25	3	2		X	Located within the footprint of the proposed service area expansion.
39	Coast Redwood	18	30	25	3	2		X	Located within the footprint of the proposed service area expansion.
40	Coast Redwood	20	30	20	3	2		X	Located within the footprint of the proposed service area expansion.
41	Coast Redwood	13	30	15	3	2		X	Located within close proximity to the proposed service area expansion.
42	Coast Redwood	11	25	15	3	2	X		Symptoms of drought stress.
43	Coast Redwood	23	35	15	3	2	X		Symptoms of drought stress.
44	Coast Redwood	21	40	20	3	2		X	Symptoms of drought stress. Located in proposed construction footprint.
45	Coast Redwood	32	30	20	3	2		X	Symptoms of drought stress. Located in proposed construction footprint.

TREE SURVEY CHART
 ROUND TREE REHABILITATION CENTER
 90 ROUNDTREE LANE - WATSONVILLE

<i>SHEET 4.</i>									
#	TREE NAME	TRUNK DIAMETER @ 54" ABOVE GRADE -- (DBH)	ESTIMATED HEIGHT	ESTIMATED SPREAD	HEALTH	STRUCTURE	SUITABLE FOR PRESERVATION	RECOMMENDED FOR REMOVAL	COMMENTS
46	Coast Redwood	20	20	20	3	2	X		Symptoms of drought stress. Located in parking lot area.
47	Coast Redwood	13	30	25	3	2	X		Symptoms of drought stress.
48	Coast Redwood	20	40	25	3	2	X		Symptoms of drought stress.
49	Coast Redwood	19	35	25	3	2	X		Symptoms of drought stress.
50	Coast Redwood	19	30	25	3	2	X		Symptoms of drought stress.
51	Coast Redwood	17	30	25	3	2	X		Symptoms of drought stress.
52	Coast Redwood	18	30	25	3	2	X		Symptoms of drought stress.
53	Coast Redwood	15/8	30	20	3	2	X		Symptoms of drought stress.
Tree's #54 To #75	22 London Plane Sycamore Trees	14	20	15	2	3	X		These trees are located in the landscape on the north side of the parking areas. The trees have not been tagged being situated well away from the proposed construction activities. Note that the dimensions and conditions shown represent average ratings for all of these trees.

- Note - Health and Structure Ratings - 1 = Best rating - 5 = Worst rating:

Nigel Boston
 Consulting Architect
 PO Box 1154
 San Jose, CA 95131
 (415) 435-1270
 info@nigelboston.com


DATE PREPARED:
 JUNE 29, 2015

DESIGNED BY:
 ANDREW H. WESTON, REGISTERED ENGINEER
 ANDREW H. WESTON
 11357 E. 14TH AVE., SUITE 2
 DENVER, CO 80231
 (303) 429-8800
 aweston@westonhulland.com

TITLE:
 TREE LOCATION MAP
 Santa Cruz County Roadside Facility
 99 Roadside Lane - Watsonville

THIS LABEL IS INTENDED TO BE PRINTED ON A PLAIN WHITE BACKGROUND. THIS LABEL IS INTENDED TO BE PRINTED AT A SIZE THAT WILL BE READILY READ BY THE USER. THIS LABEL IS INTENDED TO BE PRINTED ON A PLAIN WHITE BACKGROUND.

APPROXIMATE TREE PROTECTION FENCE LOCATION
 APPROXIMATE TREE PROTECTION FENCE LOCATION
 APPROXIMATE TREE PROTECTION FENCE LOCATION



REVISIONS

NO.	DATE	DESCRIPTION

DRAWN BY: [Blank]
CHECKED BY: [Blank]
DATE: [Blank]
SCALE: [Blank]

PROJECT: [Blank]

DATE OF CONTRACT: [Blank]

WATSONVILLE JAIL
 SANTA CRUZ COUNTY
 CALIFORNIA

EXISTING TOPOGRAPHY

9959 Blue Lakeshore Lane - Suite 105 - Monterey, CA 93940
 (831) 649-2225 • Fax (831) 373-9985
WHITSON ENGINEERS
 CIVIL ENGINEERS - LAND SURVEYING - PROJECT MANAGEMENT

ABBREVIATIONS

AC	ASPHALT CONCRETE	MAS	MAGNETIC MSL
APR	APPROXIMATE	SSD	SEWER
CE	CONCRETE	SS	SEWER SERVICE CLEANOUT
CE	CONCRETE	S	SANITARY SEWER
CE	CONCRETE	SP	SANITARY SEWER PIPE PALET
CE	CONCRETE	T	TYPICAL HOLD
CE	CONCRETE	U	UNDERGROUND
CE	CONCRETE	US	UNDERGROUND
CE	CONCRETE	UN	UNKNOWN
CE	CONCRETE	UN	UNKNOWN
CE	CONCRETE	UN	UNKNOWN
CE	CONCRETE	UN	UNKNOWN
CE	CONCRETE	UN	UNKNOWN
CE	CONCRETE	UN	UNKNOWN
CE	CONCRETE	UN	UNKNOWN
CE	CONCRETE	UN	UNKNOWN
CE	CONCRETE	UN	UNKNOWN
CE	CONCRETE	UN	UNKNOWN

LEGEND

- EX. GROUND CONTOUR (1:100)
- SUBJECT PROPERTY LINE
- ADJACENT PROPERTY LINE
- RIGHT OF WAY
- EASEMENT LINE
- CONTROL POINT
- BENCHMARK
- FOUND IRON PIPE, TAGGED AS NOTED
- SPOT GRADE (ELEVATION)
- TREE
- FENCE
- SIOR
- OVERHEAD UTILITY LINE(S)
- UNDERGROUND ELECTRIC LINE AND GUY WIRE
- UTILITY POLE SHOWING ARMS
- LIGHT ELECTRODE
- GAS VALVE
- STONE DRAIN LINE
- STONE DRAIN INLET
- SANITARY SEWER LINE (GRAVITY)
- SANITARY SEWER MANHOLE
- UNDERGROUND TELEPHONE LINE
- CELESTIAL
- SEPTIC TANK
- WATER TANK
- WATER VALVE
- POST INDICATOR VALE
- FIRE HYDRANT
- HOSE RBN
- BACKFLOW PREVENTION DEVICE
- UTILITY MANT
- CONCRETE
- BRICK PAVN
- BALDING
- PAVER PATN

NOTES

- THIS MAP REPRESENTS A TOPOGRAPHIC SURVEY PROVIDED BY WHITSON ENGINEERS IN EXERCISE OF PART OF THE DUTIES AND OBLIGATIONS OF A REGISTERED PROFESSIONAL ENGINEER. THIS MAP DOES NOT SHOW SOILS OR RELATED INFORMATION, AND ANY OTHER INFORMATION NOT SHOWN ON THIS MAP IS NOT TO BE RELIED UPON.
- EXISTING TREE LOCATIONS ARE IDENTIFIED BY NUMBERS 1 THROUGH 60. ALL TOLERANCES ARE AS SHOWN ON THIS MAP. TOLERANCES ARE SHOWN AS PART OF THIS SURVEY.
- EXISTING TREE PROTECTION FENCE LOCATIONS ARE SHOWN AS PART OF THIS SURVEY.
- EXISTING TREE PROTECTION FENCE LOCATIONS ARE SHOWN AS PART OF THIS SURVEY.
- EXISTING TREE PROTECTION FENCE LOCATIONS ARE SHOWN AS PART OF THIS SURVEY.
- EXISTING TREE PROTECTION FENCE LOCATIONS ARE SHOWN AS PART OF THIS SURVEY.
- EXISTING TREE PROTECTION FENCE LOCATIONS ARE SHOWN AS PART OF THIS SURVEY.

SCALES: 1" = 40'
 1" = 80'
 1" = 160'

PLAN

CITY OF WATSONVILLE
 2088-01-25

HDP SERVICES
 LEASING AREA

20" WIDE
 NEW EASEMENT

REVISIONS

NO.	DATE	DESCRIPTION

DATE OF CONTRACT: [Blank]
SCALE: [Blank]

PROJECT: [Blank]

DATE: [Blank]

SCALE: [Blank]

DATE: [Blank]

SCALE: [Blank]

DATE: [Blank]

Assumptions and limiting Conditions

1. Any legal description given by the appraiser/consultant is assumed to be correct. No responsibility is assumed for matters legal in character nor is any opinion rendered as to the quality of any title.
2. The appraiser /consultant can neither guarantee nor be responsible for accuracy of information provided by others.
3. The appraiser/consultant shall not be required to give testimony or to attend court by reason of this appraisal unless subsequent written arrangements are made, including payment of an additional fee for services.
4. Loss or removal of any part of this report invalidates the entire appraisal/evaluation.
5. Possession of this report or a copy thereof does not imply right of publication or use for any purpose by any other than the person(s) to whom it is addressed without written consent of the appraiser/consultant.
6. This report and the values expressed herein represent the opinion of the appraiser/consultant, and the appraiser's/consultant's fee is in no way contingent upon the reporting of a specified value nor upon any finding to be reported.
7. Sketches, diagrams, graphs, photos, etc in this report, being intended as visual aids, are not necessarily to scale and should not be construed as engineering reports or surveys.
8. This report has been made in conformity with acceptable appraisal/evaluation/diagnostic reporting techniques and procedures, as recommended by the International Society of Arboriculture.
9. When applying any pesticide, fungicide, or herbicide, always follow label instructions.
10. No tree described in this report was climbed, unless otherwise stated. We cannot take responsibility for any defects which only could have been discovered by climbing. A full root collar inspection, consisting of excavating the soil around the tree to uncover the root collar and major buttress roots was not performed, unless otherwise stated. We cannot take responsibility for any root defects which could only have been discovered by such an inspection.

Consulting Arborist Disclosure Statement

Arborists are tree specialists who use their education, knowledge, training, and experience to examine trees, recommend measures to enhance the beauty and health of trees, and attempt to reduce risk of living near trees. Clients may choose to accept or disregard the recommendations of the arborist, or to seek additional advice.

Arborists cannot detect every condition that could possibly lead to the structural failure of a tree. Trees are living organisms that fail in ways we do not fully understand. Conditions are often hidden within the trees and below ground. Arborists cannot guarantee that a tree will be healthy or safe under all circumstances, or for a specified period of time. Likewise, remedial treatments, like medicine, cannot be guaranteed.

Trees can be managed, but they cannot be controlled. To live near trees is to accept some degree of risk. The only way to eliminate all risk associated with trees is to eliminate all trees.

Nigel Belton
ISA Certified Arborist – WE 410A

Written by: WC ISA Certification Committee
Ed Perry, Editor
John C. Britton, Chairman
Ed Brennan
Denice Froehlich
Richard W. Harris
Steve Holcomb
John M. Phillips
Fred Roth

These Standards address pruning in terms of tree growth and response. They are not intended as a training manual for pruning or climbing techniques. Tree pruning is often dangerous, with unseen hazards. Proper training in safe work practices and supervision is required for tree climbing. It is the tree worker's responsibility to exercise adequate precautions for safety. All tree maintenance must be performed in compliance with ANSI Z133.1, 1988 Safety Standards.

© 1988 Adopted by the Western Chapter ISA Executive Committee on May 18, 1988.

- C. When removing a live branch, pruning cuts should be made in branch tissue just outside the branch bark ridge and collar, which are trunk tissue. *(Figure 1)* If no collar is visible, the angle of the cut should approximate the angle formed by the branch bark ridge and the trunk. *(Figure 2)*
- D. When removing a dead branch, the final cut should be made outside the collar of live callus tissue. If the collar has grown out along the branch stub, only the dead stub should be removed, the live collar should remain intact, and uninjured. *(Figure 3)*
- E. When reducing the length of a branch or the height of a leader, the final cut should be made just beyond (without violating) the branch bark ridge of the branch being cut to. The cut should approximately bisect the angle formed by the branch bark ridge and an imaginary line perpendicular to the trunk or branch cut. *(Figure 4)*
- F. A goal of structural pruning is to maintain the size of lateral branches to less than three-fourths the diameter of the parent branch or trunk. If the branch is codominant or close to the size of the parent branch, thin the branch's foliage by 15% to 25%, particularly near the terminal. Thin the parent branch less, if at all. This will allow the parent branch to grow at a faster rate, will reduce the weight of the lateral branch, slow its total growth, and develop a stronger branch attachment. If this does not appear appropriate, the branch should be completely removed or shortened to a large lateral. *(Figure 5)*
- G. On large-growing trees, except whorl-branching conifers, branches that are more than one-third the diameter of the trunk should be spaced along the trunk at least 18 inches apart, on center. If this is not possible because of the present size of the tree, such branches should have their foliage thinned 15% to 25%, particularly near their terminals. *(Figure 6)*
- H. Pruning cuts should be clean and smooth with the bark at the edge of the cut firmly attached to the wood.
- I. Large or heavy branches that cannot be thrown clear, should be lowered on ropes to prevent injury to the tree or other property.
- J. Wound dressings and tree paints have not been shown to be effective in preventing or reducing decay. They are therefore not recommended for routine use when pruning.





FIGURE 4. In removing the end of a limb to a large lateral branch, the final cut is made along a line that bisects the angle between the branch bark ridge and a line perpendicular to the limb being removed. Angle AB is equal to Angle BC.

FIGURE 5. A tree with limbs tending to be equal-sized, or codominant. Limbs marked B are greater than $\frac{3}{4}$ the size of the parent limb A. Thin the foliage of branch B more than branch A to slow its growth and develop a stronger branch attachment.



FIGURE 6. Major branches should be well spaced both along and around the stem.



II. Types of Pruning — Mature Trees (*continued*)

E. CROWN RAISING

Crown raising removes the lower branches of a tree in order to provide clearance for buildings, vehicles, pedestrians, and vistas. It is important that a tree have at least one-half of its foliage on branches that originate in the lower two-thirds of its crown to ensure a well-formed, tapered structure and to uniformly distribute stress within a tree.

When pruning for view, it is preferable to develop "windows" through the foliage of the tree, rather than to severely raise or reduce the crown.

III. Size of Pruning Cuts

Each of the Pruning Techniques (Section I) and Types of Pruning (Section II) can be done to different levels of detail or refinement. The removal of many small branches rather than a few large branches will require more time, but will produce a less-pruned appearance, will force fewer watersprouts and will help to maintain the vitality and structure of the tree. Designating the maximum size (base diameter) that any occasional undesirable branch may be left within the tree crown, such as $\frac{1}{2}$ ", 1' or 2' branch diameter, will establish the degree of pruning desired.

IV. Climbing Techniques

- A. Climbing and pruning practices should not injure the tree except for the pruning cuts.
- B. Climbing spurs or gaffs should not be used when pruning a tree, unless the branches are more than throw-line distance apart. In such cases, the spurs should be removed once the climber is tied in.
- C. Spurs may be used to reach an injured climber and when removing a tree.
- D. Rope injury to thin barked trees from loading out heavy limbs should be avoided by installing a block in the tree to carry the load. This technique may also be used to reduce injury to a crotch from the climber's line.

Assumptions and limiting Conditions

1. Any legal description given by the appraiser/consultant is assumed to be correct. No responsibility is assumed for matters legal in character nor is any opinion rendered as to the quality of any title.
2. The appraiser /consultant can neither guarantee nor be responsible for accuracy of information provided by others.
3. The appraiser/consultant shall not be required to give testimony or to attend court by reason of this appraisal unless subsequent written arrangements are made, including payment of an additional fee for services.
4. Loss or removal of any part of this report invalidates the entire appraisal/evaluation.
5. Possession of this report or a copy thereof does not imply right of publication or use for any purpose by any other than the person(s) to whom it is addressed without written consent of the appraiser/consultant.
6. This report and the values expressed herein represent the opinion of the appraiser/consultant, and the appraiser's/consultant's fee is in no way contingent upon the reporting of a specified value nor upon any finding to be reported.
7. Sketches, diagrams, graphs, photos, etc in this report, being intended as visual aids, are not necessarily to scale and should not be construed as engineering reports or surveys.
8. This report has been made in conformity with acceptable appraisal/evaluation/diagnostic reporting techniques and procedures, as recommended by the International Society of Arboriculture.
9. When applying any pesticide, fungicide, or herbicide, always follow label instructions.
10. No tree described in this report was climbed, unless otherwise stated. We cannot take responsibility for any defects which only could have been discovered by climbing. A full root collar inspection, consisting of excavating the soil around the tree to uncover the root collar and major buttress roots was not performed, unless otherwise stated. We cannot take responsibility for any root defects which could only have been discovered by such an inspection.

Consulting Arborist Disclosure Statement

Arborists are tree specialists who use their education, knowledge, training, and experience to examine trees, recommend measures to enhance the beauty and health of trees, and attempt to reduce risk of living near trees. Clients may choose to accept or disregard the recommendations of the arborist, or to seek additional advice.

Arborists cannot detect every condition that could possibly lead to the structural failure of a tree. Trees are living organisms that fail in ways we do not fully understand. Conditions are often hidden within the trees and below ground. Arborists cannot guarantee that a tree will be healthy or safe under all circumstances, or for a specified period of time. Likewise, remedial treatments, like medicine, cannot be guaranteed.

Trees can be managed, but they cannot be controlled. To live near trees is to accept some degree of risk. The only way to eliminate all risk associated with trees is to eliminate all trees.

Nigel Belton
ISA Certified Arborist – WE 410A

- C. When removing a live branch, pruning cuts should be made in branch tissue just outside the branch bark ridge and collar, which are trunk tissue. *(Figure 1)* If no collar is visible, the angle of the cut should approximate the angle formed by the branch bark ridge and the trunk. *(Figure 2)*
- D. When removing a dead branch, the final cut should be made outside the collar of live callus tissue. If the collar has grown out along the branch stub, only the dead stub should be removed, the live collar should remain intact, and uninjured. *(Figure 3)*
- E. When reducing the length of a branch or the height of a leader, the final cut should be made just beyond (without violating) the branch bark ridge of the branch being cut to. The cut should approximately bisect the angle formed by the branch bark ridge and an imaginary line perpendicular to the trunk or branch cut. *(Figure 4)*
- F. A goal of structural pruning is to maintain the size of lateral branches to less than three-fourths the diameter of the parent branch or trunk. If the branch is codominant or close to the size of the parent branch, thin the branch's foliage by 15% to 25%, particularly near the terminal. Thin the parent branch less, if at all. This will allow the parent branch to grow at a faster rate, will reduce the weight of the lateral branch, slow its total growth, and develop a stronger branch attachment. If this does not appear appropriate, the branch should be completely removed or shortened to a large lateral. *(Figure 5)*
- G. On large-growing trees, except whorl-branching conifers, branches that are more than one-third the diameter of the trunk should be spaced along the trunk at least 18 inches apart, on center. If this is not possible because of the present size of the tree, such branches should have their foliage thinned 15% to 25%, particularly near their terminals. *(Figure 6)*
- H. Pruning cuts should be clean and smooth with the bark at the edge of the cut firmly attached to the wood.
- I. Large or heavy branches that cannot be thrown clear, should be lowered on ropes to prevent injury to the tree or other property.
- J. Wound dressings and tree paints have not been shown to be effective in preventing or reducing decay. They are therefore not recommended for routine use when pruning.

II. Types of Pruning — Mature Trees (*continued*)

E. CROWN RAISING

Crown raising removes the lower branches of a tree in order to provide clearance for buildings, vehicles, pedestrians, and vistas. It is important that a tree have at least one-half of its foliage on branches that originate in the lower two-thirds of its crown to ensure a well-formed, tapered structure and to uniformly distribute stress within a tree.


When pruning for view, it is preferable to develop "windows" through the foliage of the tree, rather than to severely raise or reduce the crown.

III. Size of Pruning Cuts

Each of the Pruning Techniques (Section I) and Types of Pruning (Section II) can be done to different levels of detail or refinement. The removal of many small branches rather than a few large branches will require more time, but will produce a less-pruned appearance, will force fewer watersprouts and will help to maintain the vitality and structure of the tree. Designating the maximum size (base diameter) that any occasional undesirable branch may be left within the tree crown, such as $\frac{1}{2}$ ', 1' or 2' branch diameter, will establish the degree of pruning desired.

IV. Climbing Techniques

- A. Climbing and pruning practices should not injure the tree except for the pruning cuts.
- B. Climbing spurs or gaffs should not be used when pruning a tree, unless the branches are more than throw-line distance apart. In such cases, the spurs should be removed once the climber is tied in.
- C. Spurs may be used to reach an injured climber and when removing a tree.
- D. Rope injury to thin barked trees from loading out heavy limbs should be avoided by installing a block in the tree to carry the load. This technique may also be used to reduce injury to a crotch from the climber's line.



FENCE LINE 8' EITHER SIDE

Illuminance (Fc)

Average = 1.61

Maximum = 3.7

Minimum = 0.1

Avg/Min Ratio = 16.10


Max/Min Ratio = 37.00

A : Please consider the environment before printing this e-mail

This e-mail, including all information contained therein and any attachments, is intended solely for the person or entity to which it is addressed and may contain confidential and/or privileged material. If you are not an intended recipient, or an agent responsible for delivering it to an intended recipient, you have received this email in error. In such event, please immediately (i) notify the sender by reply email, (ii) do not review, copy, save, forward or print this email or any of its attachments, and (iii) delete and/or destroy this email and its attachments and all copies thereof. Any review, retransmission, dissemination or other use of, or taking of any action in reliance upon, any e-mail sent in error, including all information contained therein and any attachments, by persons or entities other than the intended recipient is prohibited. Please visit our website at www.huntcompanies.com for important information about our privacy policies. For your protection, please do not transmit account information or instructions by e-mail or include account numbers, Social Security numbers, credit card numbers, passwords or other personal information.

High performance and integrated style, all in one luminaire

LED Wall Sconce 161



PHILIPS GARDCO, LED WALL SCONCE 161

The Philips Gardco LED Wall Sconce 161 is an enlarged and enhanced version of the 121, providing performance capability up to that of a 400W metal halide luminaire, while using considerably less energy.

Project: _____
 Location: _____
 Catalog No: _____
 Fixture Type: _____
 Mfg: _____ Qty: _____
 Notes: _____

Ordering guide

example: 161-CWL-2-70LA-6435-CW-UNIV-BRP

Prefix		Distribution	Wattage	LED Type	Voltage	Finish	Options
161-CWL	Sconce 161 LED	2 IES Type 2 distribution	350mA	CW 5700°K	120	BRP Bronze	F¹ Fusing
161-MR	161 with motion response (120V or 277V only)	3 IES Type 3 distribution	70LA-6435 2 LED arrays, 70W	NW 4000°K	208	BLP Black	PCB² Button photocell (not available with 161-DCC)
161-DCC ¹	161 with dual circuit control	4 IES Type 4 distribution	110LA-9635 2 LED arrays, 110W	WW 3000°K	240	NP Natural	DL Diffusing lens
161-DIM	161 with 0-10V dimming controlled by others		530mA		277	WP White	WS Surface mount conduit feed junction box
161-APD	161 with automatic profile dimming (120V thru 277V ONLY)		110LA-6453 2 LED arrays, 110W		347	OC Optional color (specify optional color or RAL ex: OC-LGP or RAL7024)	
161-APD-MRI	161 with automatic profile dimming and motion response override – integrated motion sensor (120V or 277V ONLY)		700mA		480	SC Special color (specify, must supply color chip)	
			170LA-9653 2 LED arrays, 170W		UNIV 120-277V AC		
			150LA-6470 2 LED arrays, 150W		HVU 347-480V AC		
			220LA-9670 2 LED arrays, 220W				

Footnotes:

- ¹ For luminaires with input voltages above 277V (347, 480 or HVU) the 161-DCC is available with 110LA-9635, 170LA-9653 and 220LA-9670 LED wattages only.
- ² Available 120-277V only. Provide specific input voltage.

Accessories (order separately)

- **FS1R-100** – MR hand held programmer (For use with 'MR' motion response when field programming is required). If desired, only one is needed per job.

Features

- Complements the 121 wall sconce
- Perfect companion to Philips Gardco PureForm site and area luminaires
- Type 2, 3, and 4 optical distributions available
- Full cutoff performance minimizes glare and light trespass
- 10kA surge protection provided standard, meeting ANSI C62.41.2

Benefits

- Exceptional performance can reduce pole requirements on a site
- Motion response and control options available for additional energy savings
- Performance equivalent to 400W HID while utilizing less energy

Description

- **Housing:** Die cast housing
- **Finish:** Painted finish only
- **Lens:** Light engines will be sealed IP66 (in downlight application only). Tempered flat glass and diffuse glass lens option
- **Mounting:** Wall mounted only
- **Supply connection:** 90°C supply wire minimum (supplied by others)
- **Driver:** 120-277VAC and 347-480VAC non-class 2, constant current driver 350mA and 530mA, 700mA 0-10VDC dimming
- **Light engine:** LEDgine 32, 48 LEDs. LEDgine optics - acrylic. IES distributions - 2, 3, and 4. 0% uplight (full cut-off).
- **Agency approvals:** UL/CUL listed for wet locations when mounted in the downlight position. All 161 luminaires equipped with NW or CW are DesignLights Consortium[®] qualified.





LED Wall Sconce 161


LED Wattage and Lumen Values

Ordering Code	Average System Watts ¹	LED Current (mA)	LED Quantity - Dual LED Arrays		LED Selection	Luminaire Initial Absolute Lumens		
			Per LED Array	Total LEDs		TYPE 2	TYPE 3	TYPE 4
70LA-6435	74.4	350	32	64	NW	6,815	7,105	6,890
110LA-9635	110.0	350	48	96	NW	10,029	10,469	10,171
110LA-6453	106.8	530	32	64	NW	9,565	9,972	9,670
170LA-9653	158.0	530	48	96	NW	14,061	14,532	14,181
150LA-6470	142.0	700	32	64	NW	11,957	12,466	12,087
220LA-9670	210.0	700	48	96	NW	17,509	18,103	17,822

Dimensions




Approximate luminaire weight – 40lbs (18.15kg)




Mounting plate and bolt pattern

Note: Mounting plate center is located in the center of the luminaire width and 3.5" (8.89cm) above the luminaire bottom (lens down position). Splices must be made in the J-box (by others). Mounting plate must be secured by max. 5/16" (.79cm) diameter bolts (by others) structurally to the wall.


Distribution Options



Type 2



Type 3



Type 4

LED Performance

Predicted Lumen Depreciation Data ¹		
Ambient Temperature °C	Driver mA	L ₇₀ Hours ²
25 °C	350 mA	180,000
	530 mA	150,000
	700 mA	120,000
40 °C	350 mA	170,000
	530 mA	130,000
	700 mA	100,000

Footnotes:


- Wattage may vary by +/- 8% due to LED manufacturer forward volt specification and ambient temperature. Wattage shown is average for 120V through 277V input. Actual wattage may vary by an additional +/- 10% due to actual input voltage.
- Predicted performance derived from LED manufacturer's data and engineering design estimates.
- L₇₀ is the predicted time when LED performance depreciates to 70% of initial lumen output.

Luminaire Configuration Information

- **161-CWL:** 161 LED sconce providing constant wattage and constant light output when power to the luminaire is energized.
- **161-MR:** Luminaires include a passive infrared (PIR) motion sensor, WattStopper® FSP-211 equipped with an FS-L3V lens, capable of detecting motion within 20 feet of the sensor, 180° around the luminaire, when placed at a 20 foot mounting height, and mounted on a wall. Available in 120V or 277V input only. Motion sensor off state power is 0.0 watts.

In Motion Response (MR) luminaires, when no motion is detected for 10 minutes, the Motion Response system reduces the wattage by 90%, to 10% of the normal constant wattage, reducing the light level accordingly. When motion is detected by the PIR, the luminaire returns to full wattage and full light output. Dimming on low is factory set to 10% with duration set at 10 minutes.

The approximate motion sensor coverage pattern is as shown below.



FS1R-100 Wireless Remote Programming Tool:

The FS1R-100 Remote Programming Tool accessory permits adjustment of 161-MR sensor settings, including duration and dimming level on low, without the need to connect any wires to the luminaire.


The FS1R-100 Wireless IR Programming Tool is a handheld tool for setup and testing of WattStopper FSP-211. It provides wireless access to the FSP-211 sensors for setup and parameter changes.

The FS1R-100 display shows menus and prompts to lead you through each process. The navigation pad provides a familiar way to navigate through the customization fields.

Within a certain mounting height of the sensor, the FS1R-100 allows modification of the system without requiring ladders or tools simply with a touch of a few buttons.


The FS1R-100 IR transceiver allows bi-directional communication between the FSP-211 and the FS1R-100 programming tool. Simple menu screens let you see the current status of the system and make changes. It can change FSP-211 sensor parameters such as high/low mode, sensitivity, time delay, cut off and more. With the FS1R-100 you can also establish and store FSP-211 parameter profiles.

The FS1R-100 operates on three standard 1.5V AAA Alkaline batteries or three rechargeable AAA NiMH batteries. The battery status displays in the upper right corner of the display. Three bars next to BAT= indicates a full battery charge. A warning appears on the display when the battery level falls below a minimum acceptable level. To conserve battery power, the FS1R-100 automatically shuts off 10 minutes after the last key press.



You navigate from one field to another using (up) or (down) arrow keys. The active field is indicated by flashing (alternates between yellow text on black background and black text on yellow background).

Once active, use the Select button to move to a menu or function within the active field. Value fields are used to adjust parameter settings. They are shown in "less-than/greater-than" symbols: <value>. Once active, change them using (left) and (right) arrow keys. In general the up key increments and the down key decrements a value. Selections wrap-around if you continue to press the key beyond maximum or minimum values. Moving away from the value field overwrites the original value. The Home button takes you to the main menu. The Back button can be thought of as an undo function. It takes you back one screen. Changes that were in process prior to pressing the key are lost.




More information on the FS1R-100 Remote Programming Tool is available at wattstopper.com.

The FS1R-100 Wireless Remote Programming Tool can be used to adjust sensor settings on 161-MR luminaires ONLY. It cannot be used to adjust sensor settings on the 161-APD-MRI.

- **161-DCC:** 161 LED sconce provided with dual circuiting, permitting separate switching of each LED array. Note, for luminaires with input voltages above 277V (347, 480 or HVU) the 161-DCC is available with 110LA-9635, 170LA-9653 and 220LA-9670 LED wattages only.
- **161-DIM:** 161 LED sconce provided with 0-10V dimming for connection to a control system provided by others.
- **161-APD:** 161 LED sconces with Automatic Profile Dimming, are provided with a programmable driver, programmed to go to 50% power, 50% light output two (2) hours prior to night time mid-point and remain at 50% for six (6) hours after night time mid-point. Mid-point is continuously recalculated by the programmable driver based on the average mid-point of the last two full night cycles. Short duration cycles, and power interruptions are ignored and do not affect the determination of mid-point.

161-APD is available in 120V through 277V input only.

APD Dimming Profile:



Luminaire Configuration Information

- **161 - APD- MRI:** 161 wall sconce with Automatic Profile Dimming and Motion Response Override (with integral motion sensor) combines the benefits of both automatic profile dimming and motion response. The luminaire will dim to 50% power, 50% light output, per the dimming profile shown for the 161-APD. If motion is detected during the time that the luminaire is operating at 50%, the luminaire returns to 100% power and light output. The luminaire remains on high until no motion is detected for the duration period, after which the luminaire returns to low. Duration period is factory set at 10 minutes.
APD-MRI luminaires are available with 120V or 277V input voltages only.
APD-MRI luminaires use the identical motion sensor as MR luminaires.

Additional Specifications

General Description

The Philips Gardco LED Wall Sconce 161 is an enlarged and enhanced version of the 121, providing performance capability up to that of a 400W metal halide luminaire, while using considerably less energy.

Housing

Housing constructed of die-cast aluminum.

IP Rating

LED light engine rated IP66 (in downlight application only).

Optical Systems

IES Type 2, 3 and 4 distributions available. 0% uplight (full cut-off).

Listings


UL/CUL listed for wet locations when mounted in the downlight position. All 161 luminaires equipped with NW or CW are DesignLights Consortium® qualified.

Finish

Each luminaire receives a fade and abrasion resistant, electrostatically applied, thermally cured, triglycidal isocyanurate (TGIC) textured polyester powdercoat finish. Standard colors are as listed. Consult factory for specs on custom colors.

Warranty

161 Luminaires feature a 5 year limited warranty. LED luminaires with LED arrays feature a 5 year limited warranty covering the LED arrays. LED drivers are covered by a 5 year limited warranty. PIR sensors carry a 5 year limited warranty from the sensor manufacturer.




PHILIPS



Site & Area

EcoForm



Project: _____
 Location: _____
 Cat. No. _____
 Type: _____
 Qty: _____
 Notes: _____

EcoForm combines economy with performance in an LED area luminaire. Capable of delivering up to 20,000 lumens or more in a compact, low profile housing, EcoForm offers a new level of customer value. EcoForm features an innovative retrofit arm kit, simplifying site conversions to LED by eliminating the need to drill additional holes in most existing poles. Integral control systems, including motion response and wireless controls are available for further energy savings during off peak hours.

Ordering guide

example: ECF-APD-MRO-1-4-75LA-NW-120-NP-LF

Prefix	Controls	Mounting	Optics	LED Wattage	Color Temp	Voltage	Finish	Options
ECF	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
ECF EcoForm	— Standard luminaire (leave blank) DIM 0-10V Dimming APD ¹ Auto Profile Dimming APD-MRO ² Auto Profile Dimming and Motion Response Override pole mounted motion sensor APD-MRI ^{2,3} APD with Motion Response Override luminaire sensor MRI ^{2,3} Motion Response at 50% low luminaire sensor MR50 ² Motion Response at 50% low, pole mounted sensor Limelight Wireless Controls LLC2 ^{1,5} #2 lens for 8-15' mounted heights LLC3 ^{1,5} #3 lens for 15-25' mounted heights LLC4 ^{1,5} #4 lens for 25-40' mounted heights	1 Standard 2 2@180 2@90 2@90 3 3@90 3@120 3@120 4 4@90 WS Wall mount including surface conduit rear entry permitted MA Mast Arm Fitter (requires 2-3/8" O.D. Mast Arm)	2 Type 2 3 Type 3 4 Type 4 5 Type 5	530 mA 55LA-3253 ¹ 75LA-4853 100LA-6453 700mA 70LA-3270 105LA-4870 135LA-6470 1050mA 105LA-321A ¹ 160LA-481A 215LA-641A	CW Cool White 5,700K 70CRI (nominal) NW Neutral White 4,000K 70CRI (nominal) WW ⁴ Warm White 3,000K 70CRI (nominal)	120 120V 208 208V 240 240V 277 277V 347 347V 480 480V UNV 120-277V 50hz/60hz HVU 347-480V 50hz/60hz	BRP Bronze Paint BLP Black Paint WP White Paint NP Natural Paint OC Optional Color Specify optional color or RAL (ex: OC-LGP or OC-RAL7024) SC Special color Specify, must supply color chip Requires factory quote.	TL Tool-Less entry and driver removal hardware TB ¹ Terminal Block IS ⁵ Internal Shield LF ⁷ Line Fusing LFC ⁷ Line Fusing for Canada PC ^{5,7,8} Receptacle with Photocell (Includes PCR5) PCB ^{5,7,8} Photocell Button PCR5 ^{5,10,11} Photocell Receptacle only with 2 dimming connections PCR7 ^{5,10,11} Photocell Receptacle only with 2 dimming and 2 auxiliary connections RAM Retrofit Arm Mount kit PTF2 ⁹ Pole Top Fitter for 2 1/2" - 3" Tenon PTF3 ⁹ Pole Top Fitter for 3" - 3 1/2" Tenon PTF4 ⁹ Pole Top Fitter for 3 1/2" - 4" Tenon RPA ¹⁰ Round Pole Adapter for 3" - 3 9/16" O.D. BD Bird Deterrent (field installed only)

- Available in 120V-277V Voltages only (UNV, 120, 208, 240 & 277).
- MR50 and APD-MRO luminaires require one motion sensor per pole, ordered separately. See page 2 for Accessories. Available in 120V or 277V only.
- ECF-MRI requires outboarded sensor when used with Terminal Block (TB) Option.
- Contact factory for lead times on warm white.
- LLC2/LLC3/LLC4 Wireless Controls are not configurable with PC/PCB/PCR5/PCR7 Options. See page 7-8 for more info.
- Not configurable with Type 5 (5) Optics.
- Not configurable with 120-277V (UNV) Voltage. Voltage must be specified.
- Not configurable with 480V (480) Voltage.
- Not configurable with 3@120 (3@120) Mounting
- No adaptor required for 4" round poles. RPAs provided with Black Paint standard.
- Works with 3-pin or 5-pin NEMA photocell/dimming device.
- Works with 3-pin or 5-pin NEMA photocell/dimming device and auxiliary connections are not connected (for future use only).
- If ordered with DIM, APD, MRI, MR50, APD-MRI, APD-MRO, dimming will not be connected to NEMA receptacle.

ECF EcoForm

Site & Area

EcoForm Accessories (order separately)

FSIR-100

MR hand held programmer

For use with 'MRI' motion response when field programming is required. If desired, only one is needed per job.

MS-A-120V

120V Input Area Motion Sensor

For MR50 (Motion Response) or APD-MRO (Automatic Profile Dimming with Motion Response Override)


MS-A-277V

277V Input Area Motion Sensor

For MR50 (Motion Response) or APD-MRO (Automatic Profile Dimming with Motion Response Override)

Note: Motion Sensors are ordered separately, with one (1) motion sensor required per pole location for MR50 or APD-MRO luminaires. See Luminaire Configuration Information on page 5 for more details. Area motion sensor color is Arctic White. MRI and APD-MRI luminaires include an integral motion sensor.

EcoForm Drill Template (standard arm mount)




LED Wattage and Lumen Values (standard EcoForm luminaire)

Order Code (standard units)	Array Quantity	Total LEDs	LED Current (mA)	Average System Watts ¹	LED Selection	Initial Lumens ²			
						2 Type 2	3 Type 3	4 Type 4	5 Type 5
55LA-3253	2	32	530	52	NW	5,994 (s)	5,895 (s)	5,823 (s)	5,588 (s)
75LA-4853	3	48	530	77	NW	8,899 (s)	8,753 (s)	8,646 (s)	8,297 (s)
100LA-6453	4	64	530	103	NW	11,896 (s)	11,700	11,558	11,091
70LA-3270	2	32	700	69	NW	7,385 (s)	7,576 (s)	7,293 (s)	7,068 (s)
105LA-4870	3	48	700	104	NW	10,965 (s)	11,249 (s)	10,828 (s)	10,494 (s)
135LA-6470	4	64	700	139	NW	14,657 (s)	15,037	14,475 (s)	14,028
105LA-321A	2	32	1050	107	NW	10,199 (s)	10,458	10,072 (s)	9,767
160LA-481A	3	48	1050	158	NW	15,144 (s)	15,565	14,955 (s)	14,465
215LA-641A	4	64	1050	211	NW	20,243	20,252	19,991	19,880


- System input wattage may vary based on input voltage, by up to +/- 10%, and based on manufacturer forward voltage, by up to +/- 8%.
- Lumen values based on photometric tests performed in compliance with IESNA LM-79.
(s) Data is scaled based on tests of similar, but not identical, luminaires.

Dimensions – Standard EcoForm luminaire

Top View



Side View



End View



EPA (ft²/m²)

Single	Twin (2@180)	3/4@90
0.2 / 0.019	0.5 / 0.046	0.5 / 0.046


Approximate Luminaire Weight:
20 Lbs (9.07 Kg)

ECF EcoForm


Site & Area

Dimensions – EcoForm with Retrofit Arm Mount (RAM)


Top View



Side View



End View




EPA (ft²/m²)

Single	Twin (2@180)	3/4@90
0.3 / 0.028	0.6 / 0.056	0.7 / 0.065


Approximate Luminaire Weight:
21 Lbs (9.53 Kg)

Dimensions – EcoForm with Mast Arm Filter (MA)


Top View



Side View



End View



EPA (ft²/m²)


Single

0.51 / 0.047


Approximate Luminaire Weight:
21.5 Lbs (9.77 Kg)

Dimensions – EcoForm with Wall Mount (WS)


Top View



Side View




End View



Approximate Luminaire Weight:
23.36 Lbs (10.6 Kg)

Dimensions – EcoForm with LimeLight Luminaire mounted controller


Top View



Side View



End View



ECF EcoForm

Site & Area

Luminaire Configuration Information

ECF

Philips Gardco EcoForm LED standard luminaire providing constant wattage and constant light output when power to the luminaire is energized.

ECF-DIM

Philips Gardco EcoForm LED luminaire provided with 0-10V dimming for connection to a control system provided by others.

ECF-APD

Philips Gardco EcoForm LED luminaire with Automatic Profile Dimming. Luminaire is provided with a Philips DynaDimmer module, programmed to go to 50% power, 50% light output two (2) hours prior to night time mid-point and remain at 50% for six (6) hours after night time mid-point. Mid-point is continuously recalculated by the Philips DynaDimmer module based on the average mid-point of the last two full night cycles. Short duration cycles, and power interruptions are ignored and do not affect the determination of mid-point.

ECF-APD is available in 120V-277V input only.

ECF-APD Dimming Profile:


100%	2 hours 50%	6 hours 50%	100%
Power On	Mid Point		Power Off

ECF-MR50

Philips Gardco EcoForm LED luminaire with motion response, providing a 50% power reduction on low and a commensurate reduction in light output. The power and light output reduction is accomplished utilizing the Philips DynaDimmer module, programmed for a constant 50% power. Power supplied by the motion sensor connected to the override line on the DynaDimmer takes the luminaire to high setting, 100% power and light output, when motion is detected. The luminaire remains on high until no motion is detected for the motion sensor duration period, after which the luminaire returns to low. Duration period is factory set at 15 minutes, and is field adjustable from 5 minutes up to 15 minutes.


ECF-MR50 is available in 120V-277V input only to the luminaire. Motion sensors require single voltage 120V or 277V input.

The Area PIR motion sensor is the WattStopper EW-200-120-W (120V Input - MSA-120V) or the WattStopper EW-200-277-W (277V Input - MSA-277V). One motion sensor per pole is required and is ordered separately. Area sensors require single voltage 120V or 277V input.




The area motion detector provides coverage equal to up to 6 times the sensor height above ground, 270° from the front-center of the sensor.

Area PIR Motion Sensor Coverage Pattern:



Motion response requires that the pole include an additional hand hole 15 feet above the pole base, normally oriented 180° to the standard hand hole. For Philips Gardco poles, order the pole with the Motion Sensor Mounting (MSM) option which includes the hand hole and a special hand hole cover plate for the sensor with a 1/2" NPT receptacle centered on the hand hole cover plate into which the motion sensor mounts. Once the motion sensor is connected to the hand hole cover plate, then wiring connections are completed in the pole. The plate (complete with motion sensor attached and wired) is then mounted to the hand hole. If poles are supplied by others, the customer is responsible for providing suitable mounting accommodations for the motion sensor in the pole.

Mounting to a Philips Gardco Pole:



ECF-APD-MRO

Philips Gardco EcoForm LED luminaire with Automatic Profile Dimming, with Motion Response Override. The ECF-APD-MRO combines the benefits of both automatic profile dimming and motion response, using the Philips DynaDimmer module. The luminaire will dim to 50% power, 50% light output, per the dimming profile shown for the ECF-APD. If motion is detected during the time that the luminaire is operating at 50%, the luminaire returns to 100% power and light output. The luminaire remains on high until no motion is detected for the duration period, after which the luminaire returns to low. Duration period is factory set at 15 minutes, and is field adjustable from 5 minutes up to 15 minutes.

Notes:

ECF-APD-MRO is available in 120V through 277V input only to luminaire. The motion sensor requires either 120V or 277V input to the motion sensor.

The ECF-APD-MRO has the same pole requirements and utilizes the same motion sensors as the ECF-MR50. The motion sensor mounts and wires identically as well. The ECF-APD-MRO utilizes the identical dimming profile as shown for the ECF-APD.

By combining the benefits of automatic profile dimming and motion response, the ECF-APD-MRO assures maximum energy savings, and insures that adequate light is present if motion is detected.

All motion sensors utilized consume 0.0 watts in the off state.

Luminaire Configuration Information (Continued)


ECF-MRI

Luminaires with Motion Response include a LED driver and an integral programmable motion sensor. The motion sensor is set to a constant 50%. When motion is detected, the luminaire goes to 100%. The luminaire remains on high until no motion is detected for the motion sensor duration period, after which the luminaire returns to low. Duration period is factory set at 5 minutes. Available with 120V or 277V only.


Luminaires include a passive infrared (PIR) motion sensor, WattStopper® FSP-211 equipped with an FSP-L3 lens, capable of detecting motion within 20 feet of the sensor, 180° around the luminaire, when placed at a 20 foot mounting height, or mounted on a wall. Available in 120V or 277V input only. Motion sensor off state power is 0.0 watts.

The approximate motion sensor coverage pattern is as shown below.


Side Coverage Pattern



Top Coverage Pattern



ECF-APD-MRI



Luminaires with Automatic Profile Dimming and Motion Response Override combine the benefits of both automatic profile dimming and motion response. APD-MRI luminaires utilize Philips DynaDimmer. The luminaire will dim to 50% power, 50% light output, per the dimming profile shown for APD luminaires (see page 4). If motion is detected during the time that the luminaire is operating at 50%, the luminaire goes to 100% power and light output. The luminaire remains on high until no motion is detected for the duration period, after which the luminaire returns to low. Duration period is factory set at 5 minutes.

APD-MRI luminaires are available with 120V or 277V input voltages only.

APD-MRI luminaires use the identical motion sensor as MRI luminaires. See motion sensor details for ECF-MRI.

FS1R-100 Wireless Remote Programming Tool

The FS1R-100 Remote Programming Tool accessory permits adjustment of ECF-MRI and ECF-APD-MRI sensor settings, including duration and dimming level on low, without the need to connect any wires to the luminaire.


The FS1R-100 Wireless IR Programming Tool is a handheld tool for setup and testing of WattStopper FSP-211. It provides wireless access to the FSP-211 sensors for setup and parameter changes.

The FS1R-100 display shows menus and prompts to lead you through each process. The navigation pad provides a familiar way to navigate through the customization fields.

Within a certain mounting height of the sensor, the FS1R-100 allows modification of the system without requiring ladders or tools simply with a touch of a few buttons.


The FS1R-100 IR transceiver allows bi-directional communication between the FSP-211 and the FS1R-100 programming tool. Simple menu screens let you see the current status of the system and make changes. It can change FSP-211 sensor parameters such as high/low mode, sensitivity, time delay, cut off and more. With the FS1R-100 you can also establish and store FSP-211 parameter profiles.

The FS1R-100 operates on three standard 1.5V AAA Alkaline batteries or three rechargeable AAA NiMH batteries. The battery status displays in the upper right corner of the display. Three bars next to BAT= indicates a full battery charge. A warning appears on the display when the battery level falls below a minimum acceptable level. To conserve battery power, the FS1R-100 automatically shuts off 10 minutes after the last key press.



You navigate from one field to another using (up) or (down) arrow keys. The active field is indicated by flashing (alternates between yellow text on black background and black text on yellow background.)

Once active, use the Select button to move to a menu or function within the active field. Value fields are used to adjust parameter settings. They are shown in "less-than/greater-than" symbols: <value>. Once active, change them using (left) and (right) arrow keys. In general the up key increments and the down key decrements a value. Selections wrap-around if you continue to press the key beyond maximum or minimum values. Moving away from the value field overwrites the original value. The Home button takes you to the main menu. The Back button can be thought of as an undo function. It takes you back one screen. Changes that were in process prior to pressing the key are lost. More information on the FS1R-100 Remote Programming Tool is available at wattstopper.com.




ECF EcoForm

Site & Area

Luminaire Configuration Information – EcoForm with LimeLight


ECF-LLC2

EcoForm with Limelight wireless technology
Controller pod attached to luminaire arm and includes radio, photocell and motion sensor with #2 lens for 8-15' mounting heights.




ECF-LLC3

EcoForm with Limelight wireless technology
Controller pod attached to luminaire arm and includes radio, photocell and motion sensor with #3 lens for 15-25' mounting heights.



ECF-LLC4


EcoForm with Limelight wireless technology
Controller pod attached to luminaire arm and includes radio, photocell and motion sensor with #4 lens for 25-40' mounting heights.




Luminaire Configuration Information – EcoForm with LimeLight

ECF-LLC(#)

With this configuration, the controller pod is mounted to the luminaire arm. One controller is required per luminaire. There are three different motion sensor configurations available. Each one corresponds to the desired mounting height that for your specific application. See motion response detection ranges below.



Controller Pod



Wireless Radio

- 1.8 Watts max (no load draw)
- Operating voltage 102-277V RMS
- Communicates using the ZigBee protocol
- Carries out dimming commands from gateway
- Reports internal PCB temperature
- Transmission Systems Operating within the band 2400-2483.5Mhz. IEEE 802.15.4
- ROHS Compliant

Photocell

- Ambient light photocell on every wireless radio that averages the light levels of up to 5 controllers for an accurate reading and optimal light harvesting activity.
- Reports ambient light readings to 1500 Fc.

Motion Response

- Three different lens configurations
- Detects motion through passive InfraRed sensing technology
- Connects directly to radio through modular jack
- Three different mounting heights and detection ranges available

ECF EcoForm

Site & Area

Luminaire Configuration Information – EcoForm with LimeLight (Continued)

Gateway



Overview: One gateway is included with the wireless controls system. The gateway opens up communication with the wireless radios installed with the EcoForm luminaires (or pole), allowing you to control your fixtures straight from the web. One LimeLight gateway can communicate with up to 800 fixtures. Typically one unit is required per parking lot.

Installation: Gateway has 4 blind threaded holes on the back side that accept 10-32 screws. Mount spacing is 10.41" across and 14.19" vertical.

Requirements: The gateway must be mounted in a secure on-site location. The gateway requires 120V. Distance of gateway to the first radio varies upon application; contact factory. Strong internet connection required.

Specifications:

- High density RF Mesh coordinator
- Ethernet or wireless internet connection to LimeLight server
- Proprietor of software "rules of operation"
- Watertight Ethernet connections
- Highly protected, long life ac/dc power supply
- Single board, ARM compliant 520Mhz Intel computer.
- Operating Temperature -20°C to 55°C
- Tamper proof housing



ECF EcoForm

Site & Area

Specifications

Housing

One piece die cast aluminum housing with integral arm and separate, self retained hinged, one piece die cast door frame.

IP Rating

LED light engine rated IP66.

Vibration Resistance

EcoForm with Standard Arm carries a 3G vibration rating that conforms to standards set forth by ANSI C136.31. Testing includes vibration to 3G acceleration in three axes, all performed on the same luminaire.

Electrical

Driver efficiency (>90% standard). 120-480V available (restrictions apply). Open/short circuit protection. Optional 0-10V dimming to 10% power. RoHS compliant. Surge protector standard. 10KA per ANSI/IEEE C62.41.2.

LED Board and Array

32, 48, or 64 LEDs. Color temperatures: 3000K, 4000K, 5700K +/- 250K. Minimum CRI of 70. Aluminum metal clad board. RoHS compliant.

LED Thermal Management

The housing design allows the one piece housing to provide excellent thermal management critical to long LED system life.

Energy Saving Benefits

System efficacy up to 95 lms/W with significant energy savings over Pulse Start Metal Halide luminaires. Optional control options provide added energy savings during unoccupied periods.

LED Performance

Predicted Lumen Depreciation Data¹

Ambient Temperature °C	Driver (mA)	Calculated L ₇₀ Hours ^{1,2}	L ₇₀ Per TM-21 ^{2,3}	Lumen Maintenance % @ 60,000 hours
Up to 40 °C	Up to 1050 mA	> 350,000 hours	> 60,000 hours	97%

1. Predicted performance derived from LED manufacturer's data and engineering design estimates, based on IESNA LM-80 methodology. Actual experience may vary due to field application conditions.
2. L₇₀ is the predicted time when LED performance depreciates to 70% of initial lumen output.
3. Calculated per IESNA TM21-11. Published L₇₀ hours limited to 6 times actual LED test hours.

Wireless Controls

The LimeLight wireless Controls System includes: gateway, controller pod (with wireless radio, motion response, and photocell), and commissioning/training. LimeLight is an intelligent web-based system that operates through a high density mesh (HDM) wireless technology. Wireless radios with motion response and photocell sensors are integrated with PureForm luminaires, and enable the fixtures to communicate via the ZigBee protocol. The gateway is a mini computer that connects to the internet, and is located in a secure location. The central LimeLight database channels communication to and from the gateway, allowing data to be viewed or managed through the web-based graphical user interface (GUI). See LimeLight pages for details and technical information.

Motion Sensors

ECF-MR50, ECF-APD-MRO, ECF-MRI, ECF-APD-MRI luminaires may be specified for additional energy savings during unoccupied periods. See pages 4-6 for complete details.

Optical Systems


Type 2, 3, 4, and 5 distributions available. Internal Shield option mounts to LED optics and is available with Type 2, 3, and 4 distributions to control backlight.

Mounting

Standard luminaire arm mounts to 4" round poles. Square pole adapter included with every luminaire. Round Pole Adapter (RPA) required for 3-3.9" poles.

Retrofit Arm Mount

EcoForm features an innovative retrofit arm kit. When specified with the retrofit arm (RAM) option, EcoForm seamlessly simplifies site conversions to LED by eliminating the need for additional pole drilling on most existing poles. RAM will be boxed separately.



Listings


ETL/cETL listed to the UL 1598 standard, suitable for Wet Locations. Suitable for use in ambients from -40° to 40°C (-40° to 104°F). The quality systems of this facility have been registered by UL to the ISO 9001 series standards. All EcoForm luminaires equipped with NW and CW are DesignLights Consortium® qualified.

Finish

Each standard color luminaire receives a fade and abrasion resistant, electrostatically applied, thermally cured, triglycidyl isocyanurate (TGIC) textured polyester powdercoat finish. Standard colors include bronze (BRP), black (BLP), white (WP), and natural aluminum (NP). Consult factory for specs on optional or custom colors.

Warranty

EcoForm luminaires feature a 5 year limited warranty. Philips Gardco LED luminaires with LED arrays feature a 5 year limited warranty covering the LED arrays. LED Drivers also carry a 5 year limited warranty. Motion sensors are covered by warranty for 5 years by the motion sensor manufacturer.





1 208 MAIN STREET, REDWOOD CITY, CA 94063
 P: (650) 569-4020 • F: (650) 569-4023 • E: info@protech-cal.com

ASBESTOS & LEAD (Pb) REPORT

PARTIAL PRE-DEMO/RENOVATION SURVEY & EVALUATION

DATE: June 4, 2015 **PROJECT NO.:** 338-MA15

REQUESTED BY: Moss & Associates
 (CLIENT) 100 Wonsan Drive
 Ocean Side, California 92058

PROJECT: Santa Cruz Rountree SB1022
 90 Roundtree Lane
 Watsonville, California

PROJECT DESCRIPTION: Minimum Security Jail Modification

SERVICE AREA(S):

1. X-building (Minimum Security Building) including:
 - Wing A Renovation
 - Wing B Renovation
 - Wing C Demolition
 - Wing D Renovation
2. Ancillary Building (Medium Security Building): limited to parts of the building labeled as "areas of work" on Attachment A(7) of the bid set.
3. Classroom Building (Scheduled for demolition)

On April 22, 2015 *ProTech Consulting & Engineering, Inc.* performed a building survey to identify asbestos-containing materials (ACM) and presence of Lead based paint (Pb) at the subject project. The survey was conducted in an effort to comply with pre-demolition/renovation regulatory requirements.

Environmental consulting services were conducted by ProTech's licensed and accredited staff as follows:

CONSULTANT	DISCIPLINE	ISSUING AGENCY	CERTIFICATION NO.
Glen Koutz	Asbestos Lead	Cal OSHA CDPH	11-4830 2204
Emanuel Dounias	Asbestos Lead	Cal OSHA CDPH	00-2766 13059

SERVICES REQUESTED BY CLIENT

Asbestos Survey

Consulting services were limited by the client to the following scope of services:

- Performed a visual survey of the project to identify, document, and assess suspect asbestos-containing materials (ACM).
- Collected representative samples to confirm or rebut the presence of ACM.
- Submitted necessary samples to a certified laboratory for analysis by standard polarized light microscopy (PLM) to determine asbestos content.
- Assess the friability and abatement classification of identified ACM;
- Prepared this written report presenting an evaluation and assessment of the data.

ProTech is only responsible for the specific scope of work as stated. No other services are intended or implied.

LBP Survey

- Performed a visual survey of the project to identify, document, and assess suspect lead-based paint (LBP).
- Tested painted/coated surfaces using a calibrated X-ray fluorescence analyzer (XRF).
- Collected representative confirmational paint chip samples to confirm or rebut the presence of lead. Submitted paint chip samples to a certified laboratory for analysis.
- Prepared this written report presenting an evaluation and assessment of the data.

RESULTS & REGULATORY ASSESSMENT

Asbestos types are abbreviated as follows: Chr = Chrysotile; Amo = Amosite; Cro = Crocidolite; Tre = Tremolite; Act = Actinolite.

<i>Confirmed Less Than 1% Asbestos Materials</i>						
MATERIAL DESCRIPTION	MATERIAL, SYSTEM, LOCATION	SMPL NOS.	APPROX. QUANT.	LAB RESULT	REGULATORY ASSESSMENT	
					CAL OSHA	EPA/AQMD
X-Bldg.						
1. White drywall, joint tape and compound	Some walls and ceilings in various areas throughout most walls and ceilings with concrete and wood	01*, 02, 03, 04*, 05*, 06, 07	Approximately 12,000 sq ft.	Confirmed <1% Chr	Class II Abatement	Non-Friable
2. Brown/gray window glazing	Exterior windows	32*, 33*, 34, 35	3500 ln ft.	Confirmed <1% Chr	Class II Abatement	Non-Friable

* No asbestos detected in sample

Non-Asbestos Materials

No asbestos was detected in the following materials.

MATERIAL DESCRIPTION	MATERIAL LOCATION(S)	SAMPLE NUMBERS
X-Bldg.		
1. Yellow carpet mastic	Probation office	08
2. Yellow carpet mastic	Officers office	09
3. Smooth 1 x 1 ceiling tiles with brown mastic	Upper module area	10
4. Perforated 1 x 1 ceiling tile with tan mastic	Lower module area	11
5. Gray concrete pad	Upper module floor	12
6. Gray ceramic tile mortar	Kitchen splash and urinal area	13, 14
7. Brown cementitious coating	On concrete and CMU in the exterior maintenance closet, kitchen slop sink and the shower toilet area.	15, 16, 17, 18
8. Brown baseboard mastic	Dorm, recreation room/library area, module	19, 20, 21
9. Interior window glazing	Interior partition walls for class and wood panels	22, 23, 24, 25, 26
10. Yellow wall panel mastic	Exterior restrooms	27
11. Brown Window caulking	Exterior rough openings of windows	28, 29, 30, 31
12. White pipe jacket	Hot water pipes throughout	36, 37
13. White take jacket	Hot water heater tank in mechanical room	38
14. Gray roof caulking	Flashing and penetrations	39, 40
15. Gray roof mastic	Small out patches throughout	41, 42
16. Brown composite shingle roof	Main roof field	43, 44, 45, 46, 47
Ancillary Building		
17. Drywall, joint tape and compound	Most walls in kitchen area	01, 02, 03
18. Smooth 2 x 4 ceiling panels	Kitchen dish wash area	04
19. Yellow wall panel mastic	Kitchen dish wash area	05
20. Gray HVAC joint mastic	Above ceiling on ducts	06
21. Gray epoxy floor	Kitchen area	07
22. White tank insulation(foam)	Mechanical room	08
23. Drywall, joint tape and compound	Most some ceiling reception office area	09, 10, 11
24. 2 x 4 ceiling panels	Most ceilings reception office area	12, 13
25. Tan baseboard mastic	Most walls reception office area	14
26. White 12 x 12 vinyl floor tile with yellow mastic	Storage closet and copy room	15
27. Gray sheet flooring	Restroom	16
28. Yellow carpet mastic	Office and hall	17, 18
29. Gray concrete caulking	At seams and all rough openings	19, 20
30. White pipe jacket	most water pipes	21, 22
31. Gray monocoat fireproofing	Throughout above ceiling areas	23, 24, 25, 26, 27,
32. Green 12 x 12 vinyl floor tile with yellow mastic	Housing corridor	28
33. Stucco	Exterior south soffit	29
Classroom building		
34. Drywall, joint tape and compound	Walls of center build outs	01, 02, 03
35. Topping texture	Storeroom and office	04, 05
36. Fibrous wall panels with mastic	Classrooms	06, 07
37. 2 x 4 ceiling panels	Throughout	08, 09
38. Yellow carpet mastic	Throughout most	10, 11
39. Gray pebble pattern sheet flooring	Kitchenette and restroom	12
40. Gray composite shingle roof	Roof field	13, 14

ACM Note: Conflicting Laboratory Results

The EPA has a specific protocol for sampling suspect asbestos building materials. In general, it recommends collecting multiple samples (often a minimum of three) of each suspect asbestos material. Multiple samples are recommended by the EPA to increase the statistical reliability of the results and to minimize the potential for field or laboratory error.

Sometimes, multiple samples representing a particular material will yield both positive and negative results. When this happens, the negative sample result(s) are superseded by the positive results. **Once a single positive sample is identified, the material represented by the sampling is treated as an asbestos-containing material.**

However, if additional sampling data, as-built plans, or other reliable data can adequately explain or confirm that area(s) that tested positive are different (not homogeneous) from areas that tested negative, this information can be used to more accurately quantify ACM and define the scope of an asbestos abatement job.

LEAD

Painted/coated surfaces were tested in the field using an X-Ray fluorescence (XRF) spectrum analyzer and/or sampled (paint chips) and submitted to a certified laboratory for analysis by atomic absorption spectroscopy (AAS). Lead paint samples fell in to 1 of 3 types - as follows:

Types of Lead Materials		
LEAD TYPES	DEFINITION	LEAD CONTENT STANDARD
LBP	Lead-based paint (or material)	By XRF: 1 mg/cm ² or greater By Paint Chip: 0.5 weight % or 5,000 mg/kg (at or above)
LCM	Lead containing material (or paint)	By XRF: <1 mg/cm ² By Paint Chip: Below 0.5 wt % of 5,000 mg/kg
ND	No lead detected	By XRF: Requires paint chip confirmation By Paint Chip: No lead Detected or <0.006 wt %

Lead-Based Paint (LBP) – By XRF

XRF READINGS	• 14 (fourteen) XRF readings tested positive for lead-based paint/coating (see XRF report).	
SUMMARY OF LBP COMPONENTS	INTERIOR COMPONENTS	X Building: metal door components, Vinyl window components (Interior build outs and perimeter walls) Ancillary Building: Metal door components, Metal/concrete bumper posts, metal pantry cage, Structure Steel (beams, columns, etc)
	EXTERIOR COMPONENTS	X Building: Vinyl window components, metal railings Classroom building: Metal railings

Lead-Containing Material (LCM) – By XRF

XRF READINGS	• 34 (thirty-four) XRF readings tested positive for low levels of lead (see XRF) report.	
SUMMARY OF LCM COMPONENTS	INTERIOR COMPONENTS	• SEE XRF REPORT
	EXTERIOR COMPONENTS	• SEE XRF REPORT

Non-Lead – By XRF

XRF READINGS	<p>• 70 (seventy) XRF readings tested negative (no lead detected) for the presence of lead (see XRF report). (Note: Cal OSAH does not accept XRF to prove "non-lead" – paint-chip lab analysis is required)</p>
---------------------	--

Paint-Chip – By Laboratory Analysis

Representative paint-chip samples were collected to confirm (or rebut) the presence of lead in materials the showed very low (or no) lead content by XRF analysis.

COMPONENT TYPE/DESCRIPTION	SUBSTRATE	SAMPLE NO(S)	RESULTS WT%	TYPE
X-Building				
1 Gray concrete paint in weight room area- 150 sq ft loose and peeling paint	Concrete	LP-01	<0.006	ND
2 White drywall paint	Drywall	LP-02	<0.006	ND
3 Gray wood wall paint	Wood	LP-03	<0.006	ND
4 Blue wood door paint	Wood	LP-04	<0.006	ND
Ancillary Building				
5 Gray drywall paint	Drywall	LP-05	<0.006	ND
6 Interior white concrete paint	Concrete	LP-06	<0.006	ND
7 Exterior white concrete paint	Concrete	LP-07	<0.006	ND
Classroom Building				
8 Exterior blue wood deck/railing paint	Deck	LP-08	<0.006	ND
9 Exterior brown wood siding paint	Wood	LP-09	<0.006	ND

ASBESTOS REGULATORY NOTES

Cal OSHA (DOSH)

Asbestos-Containing Material (ACM): A material is an asbestos containing material (ACM) when the sample aggregate or any one of its layers (analyzed individually) contains greater than 1% asbestos. Cal OSHA does **not** allow composite analysis (mixing layers of materials together).

Less than 1% Asbestos: Materials containing less than 1% asbestos are not regulated by most governmental agencies. However, Cal OSHA is not one of those agencies. The Cal OSHA asbestos standard must be followed for work involving materials that contain a concentration of asbestos as low as **0.1%**.

If a material can be shown to contain less than 1% asbestos by PLM point count (or other approved method), it can be treated as an asbestos-containing construction material (ACCM). ACCM is a term Cal OSHA uses to describe materials containing **less than 1%** (but greater than 0.1%) asbestos. In certain situations, there may be some economic advantages to making this characterization. The decision to do so is evaluated on a case-by-case basis at the client's request.

Less than 0.1% Asbestos: If a material can be shown to contain less than **0.1%** asbestos by an approved method, it can be treated as a non-asbestos material. In certain situations, there may be

some economic advantages to making this characterization. The decision to do so is evaluated on a case-by-case basis at the client's request.

Class I Asbestos Work: Cal OSHA prescribes specific work practices involving the removal of asbestos-containing insulation and surfacing (i.e. sprayed-on) materials.

Class II Asbestos Work: Cal OSHA prescribes specific work practices involving the removal of ACM which is not insulation or surfacing material. This includes, but is not limited to, the removal of asbestos-containing wallboard, floor tile and sheeting, roofing, cement products, and construction mastics.

EPA/AQMD

Asbestos-Containing Material (ACM): Any building material which contains commercial asbestos in an amount greater than 1%.

Less than 1% Asbestos: Materials that are found to contain less than 1% asbestos by standard polarized light microscopy (PLM) may be considered non-asbestos (by EPA/AQMD) if confirmation analysis is performed. To be treated as a non-asbestos material, the EPA and AQMD require analytical verification by PLM Point Count (or better). This verification is required because the standard PLM analysis is not sensitive enough to accurately determine asbestos content at or below 1%. In certain situations, there may be some cost advantages to making this characterization. The decision to do so is evaluated on a case-by-case basis at the client's request.

Regulated Asbestos-Containing Material (RACM): RACM includes friable (easily crumbled) ACM, or Category I nonfriable ACM that has or will become friable or that has been subjected to sanding, drilling, grinding, cutting, or abrading, or Category II nonfriable ACM that may become or has become crumbled, pulverized, or reduced to powder.

Friable: Materials that can be crumbled, pulverized, or reduced to powder, when dry, by hand pressure.

Non-Friable: Materials that **cannot** be easily crumbled, pulverized, or reduced to powder, when dry, by hand pressure. Non-friable materials are categorized by EPA/AQMD as follows:

- **Category I Nonfriable ACM:** Asbestos-containing packings, gaskets, resilient floor coverings, mastics and asphalt roofing products.
- **Category II Nonfriable ACM:** Asbestos-containing material, excluding Category I nonfriable asbestos-containing material, that, when dry, and in its present form, cannot be crumbled, pulverized, or reduced to powder by hand pressure.

LEAD REGULATORY NOTES

Lead-Based Paint (LBP)

MATERIAL DESCRIPTION		REGULATORY ASSESSMENT GOVERNING REGULATIONS
1.	Lead-based paint components (LBP)	<ul style="list-style-type: none"> • Cal OSHA standards apply if LBP will be disturbed by employees/workers • CDPH standards apply if lead "abatement" is performed • DTSC requires characterization of waste and proper disposal • US EPA standards apply if LBP is disturbed in a children occupied site
2.	Lead containing materials (LCM)	<ul style="list-style-type: none"> • Cal OSHA standards apply if LCM will be disturbed by employees • CDPH standards apply if worker exposure standards are exceeded • DTSC requires characterization of waste and proper disposal
3.	No Lead Detected by XRF	<ul style="list-style-type: none"> • Cal OSHA standards apply unless paint chip laboratory analysis confirms non-lead
4.	No Lead Detected by Paint-chip	<ul style="list-style-type: none"> • No regulations apply

Regulatory Assessment Notes

California Occupational Safety & Health Administration (Cal OSHA):

- Regulates any detectable amount of lead (does not have to be LBP) when trigger tasks are performed
- Requires worker training
- Regulates employee safety during lead-related work
- Enforces proper work practices
- Requires notification when 100 sq ft (or more) of LBP is disturbed.

California Department of Public Health (CDPH):

- Regulates "abatement" of Lead-based paint
- Requires *accredited* training for workers and supervisors
- Provides certification of workers and supervisors performing abatement
- Mandates lead abatement be performed in accordance with US HUD guidelines
- Defines "abatement" as an action performed for the purpose and intent of reducing or eliminating a lead "hazard"
- Requires notification when abatement is performed

California Department of Toxic Substance Control (DTSC):

- Regulates disposal of lead waste
- Requires testing of waste stream to characterize hazard level

US Environmental Protection Agency (US EPA):

- Regulates Lead-based paint in child occupied facilities
- Regulates work involving the disturbance of as little as 6 sq ft of interior & 20 sq ft exterior LBP
- Requires *accredited* training for workers and supervisors
- Requires certification of companies performing LBP work
- Mandates minimal work practices

LEAD DISCUSSION

Lead-Based Paint & Lead Containing Materials

Lead-based paint (LBP) is defined as a material/coating/paint which contains a lead content at or in excess of 5,000 parts per million (PPM), 0.5% by weight, or 1 mg/cm² (by XRF). Materials containing a lead content below these levels are not considered LBP and are not considered a hazard by most regulatory agencies. However, the dust from materials containing low levels of lead can produce a lead hazard if enough lead dust accumulates.

Cal OSHA Trigger Tasks

Cal OSHA defines lead paint at the Consumer Product Safety Commission's (CPAC) level of 600 ppm for non-trigger tasks. However, Cal OSHA regulates **any detectable amount of lead** when trigger tasks are conducted.

The following table lists the Cal OSHA trigger tasks, presumed exposure and the type of respiratory protection that is required while performing those tasks:

CAL OSHA TRIGGER TASK	PRESUMED EXPOSURE	REQUIRED RESPIRATORY PROTECTION
<ul style="list-style-type: none">Manual demolitionManual scraping and sandingHeat gun useUse of power tools with dust collection systemsSpray painting with lead paintAny other activity that the employer has any reason to believe that an employee may be exposed in excess of the PEL.	50-100 $\mu\text{m}/\text{m}^3$	Half-mask, air purifying
<ul style="list-style-type: none">Using lead containing mortarLead burningRivet bustingPower tool cleaning without dust collection systemClean-up of dry abrasive blast residue.	500-2500 $\mu\text{m}/\text{m}^3$	Full-face, air purifying, or Tight fitting PAPR, or Supplied air, contiguous flow
<ul style="list-style-type: none">Abrasive blastingWeldingCuttingTorch burning.	>2500 $\mu\text{m}/\text{m}^3$	Supplied air, pressure demand

SURVEY & REPORT LIMITATIONS

- Scope of work limitations were established by the Client to include items of interest and concern to the Client. *ProTech* is only responsible for the specific scope of work performed. No other services are intended or implied.
- This report has been prepared for the exclusive use of *ProTech*'s client and is not intended for use by any other party. The scope of work and results presented in this report may not be appropriate for uses by any other party. Any use by a third party of this report shall be at their own risk and shall constitute a release and an agreement to defend and indemnify *ProTech* from any and all liability in connection therewith whether arising out of *ProTech*'s negligence or otherwise.
- This project may contain undiscovered asbestos in areas that were not accessible or identified during *ProTech*'s survey. Suspect asbestos may be discovered during demolition, renovation, or maintenance. If suspect asbestos is discovered, stop all work that could impact asbestos to allow properly trained personnel to perform sampling and or removal.
- This report and it's evaluations/conclusions are based on the current condition of the project. This report does not assess or anticipate future events that may impact or damage asbestos materials. Future changes in the condition of asbestos materials will require a new assessment by a certified asbestos consultant/technician.
- The quantities of asbestos stated in this report are approximations. This report is not a work plan or project specification. Contractors should not rely on this document for bidding purposes.
- Reasonable efforts were made to examine below **carpeted areas and resilient floor coverings** to determine and quantify the presence of suspect asbestos materials. *ProTech* accepts no liability for additional materials or under-reporting of asbestos materials which exist below other floor coverings.
- **Glass fiber insulated mechanical systems** were inspected as completely as possibly without destroying the integrity of the glass fiber insulation. The condition and presence or absence of asbestos associated with mechanical systems is assumed to be consistent with those areas exposed and examined during our inspection. However, *ProTech* does not guarantee that this is the case.
- *ProTech* does not represent this **limited survey** as a comprehensive inspection or evaluation. *ProTech* recommends that an expanded, comprehensive asbestos survey be conducted at this site if renovation or demolition activities are expected to impact any building materials other than those specifically addressed in this report.

- Because this survey was conducted in an **occupied building**, intrusive inspection methods were limited. Specific care and caution were observed to:
 1. Avoid significant aesthetic impact to architectural finishes.
 2. Avoid disturbing tenants and patrons.
 3. Avoid disturbing tenant spaces.

SURVEY APPROACH

Inspection & Sample Collection

ProTech performed a survey of the project to identify and document accessible suspect asbestos. Identified suspect asbestos materials categorized by homogenous area and sampled. Samples were collected by misting small areas with water, then cutting or scraping the sample from the substrate with an appropriate sampling tool. Whenever possible, samples were collected from areas previously damaged or deteriorating. No building systems, components, or structures were demolished to obtain samples of potentially hidden ACM.

Each suspect bulk sample was sealed in its own Zip-lock plastic container and labeled with a unique identification number. Sampling tools were individually cleaned before and after each sample was collected to avoid sample cross contamination. Decontamination was accomplished using single-use, pre-moistened cloths.

Sample information was recorded on ProTech's chain-of-custody form. This form accompanied the samples to a laboratory possessing accreditation from the National Voluntary Laboratory Accreditation Program (NVLAP). Samples were submitted to Forensic Analytical Services, Inc. of Hayward, California.

Sample Analysis

Bulk sample analysis was conducted in accordance with the EPA interim method for determination of asbestos in bulk materials. Samples were first examined by a stereoscopic microscope for determination of homogeneity and preliminary evaluation of composition and presence of fibers. Fibers observed during this examination were then mounted in various refractive index oils and examined in polarized light. During this examination, all minerals and/or man-made materials were identified and the percentages of each were estimated and/or counted.

Evaluation of Asbestos-Containing Materials

In evaluating each asbestos material, the adhesion of the asbestos material to the underlying substrate, deterioration, and damage from vandalism or any other cause was assessed. Evidence of debris on horizontal surfaces, hanging material, dislodged chunks, scraping, indentations, cracking, etc. would be indicators of poor material condition.

Accidental or deliberate physical contact with asbestos materials can result in damage. Inspectors looked for any evidence that asbestos-containing materials had been disturbed. Indicators such as: finger marks in the material, graffiti, pieces dislodged or missing, scraping marks from movable equipment, or furniture, or an accumulation of suspect asbestos dust or debris on floors, shelves, or other horizontal surfaces indicate poor material condition.

Asbestos-containing materials may deteriorate as a result of either the quality of the installation or environmental factors which affect the cohesive strength of the asbestos-containing material or the strength of the adhesion to the substrate. Deterioration can result in an accumulation of dust on the surface of the asbestos-containing material, delamination of the material, or an adhesive failure of the material where it pulls away from the substrate and either hangs loosely or falls to the floor and exposes the substrate. Inspectors touch the asbestos-containing material to determine if dust is released when the material is lightly brushed or rubbed.

CONCLUSIONS & RECOMMENDATIONS

Asbestos Removal

ACM should be removed prior to activity that may disturb it. Prior to ACM disturbance/removal, the following should be performed:

	Task	Task Description	Fee
1.	Prepare Project Specification	Prepare a written scope of work & instructions to bidders (site plans not included).	\$800.00 - \$1,200.00
2.	Bid Review and Contractor Selection	Select qualified contractors (prospective bidders), review bids and award contract.	\$680.00
3.	Project Monitoring & Oversight	Monitoring asbestos abatement work and document contractor compliance.	Pricing upon request
4.	Project Clearance	Perform final inspection and collect air samples to certify work area clearance.	Pricing upon request

LEAD

- Cal OSHA worker protection rules, CDPH certification requirements, US EPA standards, and DTSC disposal requirements need to be assessed by each contractor/employer who performs work on this project.
- Contractors, whose employees work at this site, are required to assess if their work will be subject to the requirements of the Cal OSHA lead construction standard (CCR Title 8 § 1532). Cal OSHA standards are designed to regulate and enforce on-the-job worker safety. Employers are required by law to ensure that employees are not exposed to airborne lead levels which exceed the permissible exposure limit (PEL). The standard requires worker exposure monitoring, medical surveillance, training, special work practices, etc.

- Each contractor/employer who bids and/or performs work at the site will need to assess potential lead exposure to employees performing their particular scope of work. Contractors who perform work at this site may need to obtain additional data (beyond the data presented in this report) during their assessment and Cal OSHA compliance planning. Individual contractors/sub-contractors should be allowed access to the project to obtain any needed data (samples, consultation, etc.) to complete their employee exposure assessment.
- ProTech recommends that the building owner and/or general contractor disseminate this report as well as any other lead-related information to all prospective contractors bidding work at the subject site.
- Contractors, whose employees disturbs more that 100 sq ft of lead-based paint (LBP), are required to submit written notification to Cal OSHA (per Health and Safety Code, Title 17 CCR Section 36000 (c)). The Cal OSHA LBP notification rule requires 24-hour advance notice prior to LBP disturbance.
- Any work performed at the site where LBP or LCP is likely to be disturbed should be performed by a contractor trained and qualified to perform lead-related construction work. Any work that exceeds Cal OSHA's permissible exposure limit or is performed to remediate a lead hazard must be conducted by CDPH certified personnel. All lead related work should be conducted employing lead work practices in accordance with HUD guidelines.

LEGEND

HOW TO READ THE REPORT

Wall A, is the front wall of the building.

Walls B, C and D go clockwise around the building or room

REPORTS

Summary-- Gives only those readings at or above the action level of 1.0mg/cm².

Detailed Report— Gives all reading by room and component.

Readings are not in numerical order. This report also gives comments

PAINT CONDITION

I=Intact

F=Fair

P=Poor

Comments

There were 124 readings taken, including calibrations, using the RMD XRF instrument. 14 of the readings registered at or above the action level of 1.0mg/cm². A contractor practicing Lead Safe Practices should do any repairs or repainting of the actionable areas.

“ A copy of this summary report must be provided to new lessees and purchasers of this property under Federal Law (24 CFR part 35 and 40 CFR part 745) before they become obligated under lease or sales contract. The complete report must also be provided to new purchasers and it must be made available to new tenants. Landlords and sellers are also required to distribute an educational pamphlet and include standard warning language in their leases or sales contracts to ensure that parents have the information they need to protect their children from lead-based paint hazards.”

Emanuel Dounias
DPH 13095

Date

Comments

There were 124 readings taken, including calibrations, using the RMD XRF instrument. 14 of the readings registered at or above the action level of 1.0mg/cm². A contractor practicing Lead Safe Practices should do any repairs or repainting of the actionable areas.

“ A copy of this summary report must be provided to new lessees and purchasers of this property under Federal Law (24 CFR part 35 and 40 CFR part 745) before they become obligated under lease or sales contract. The complete report must also be provided to new purchasers and it must be made available to new tenants. Landlords and sellers are also required to distribute an educational pamphlet and include standard warning language in their leases or sales contracts to ensure that parents have the information they need to protect their children from lead-based paint hazards.”

Emanuel Dounias
DPH 13095

Date

LEAD PAINT INSPECTION REPORT

REPORT NUMBER: S#01369 - 04/22/15 12:26

INSPECTION FOR: Moss & Associates
100 Wonsan Drive.
Ocean Side, CA

PERFORMED AT: Santa Cruz Roundtree SB10022
90 Roundtree Lane
Watsonville, CA
Limited Areas

INSPECTION DATE: 04/22/15

INSTRUMENT TYPE: R M D
MODEL LPA-1
XRF TYPE ANALYZER
Serial Number: 01369

ACTION LEVEL: 1.0 mg/cm**2

OPERATOR LICENSE: California General

STATEMENT: Lead paint survey as agreed.
No representations are made for any areas not tested.

SIGNED _____ DATE _____
ProTech Consulting & Engineering
1208 Main Street
Redwood City, Ca. 94063
Phone: 650-569-4020
Fax: 650-569-4023

SEQUENTIAL REPORT OF LEAD PAINT INSPECTION FOR: Moss & Associates

Inspection Date: 04/22/15 Santa Cruz Roundtree SB10022
 Report Date: 4/29/2015 90 Roundtree Lane
 Abatement Level: 1.0 Watsonville, CA
 Report No. S#01369 - 04/22/15 12:26 Limited Areas
 Total Readings: 124
 Job Started: 04/22/15 12:26
 Job Finished: 04/23/15 18:05

Read No.	Room	Room Name	Wall Structure	Location	Member	Paint		Paint Color	Lead (mg/cm ²)	Mode
						Cond	Substrate			
1		CALIBRATION							0.9	TC
2		CALIBRATION							0.9	TC
3		CALIBRATION							1.0	TC
4	001	X Module	A Wall	L Ctr		I Wood		White	0.0	QM
5	001	X Module	B Wall	L Ctr		I Wood		White	0.2	QM
6	001	X Module	D Wall	L Ctr		I Drywall		White	0.0	QM
7	001	X Module	B Window		Ctr Rgt casing	I Wood		Blue	0.2	QM
8	001	X Module	A Door		Ctr Rgt casing	I Wood		Blue	0.1	QM
9	001	X Module	A Window		Ctr Rgt casing	I Wood		Brown	0.0	QM
10	001	X Module	B Wall	L Lft		I Wood		Blue	0.0	QM
11	002	X Dorm	A Beam		Ctr	I Wood		Black	0.0	QM
12	002	X Dorm	A Beam		Ctr	I Wood		Brown	0.0	QM
13	002	X Dorm	A Wall	L Ctr		I Concrete		White	0.0	QM
14	002	X Dorm	C Wall	U Ctr		I Concrete		White	0.3	QM
15	002	X Dorm	B Door		Rgt U Ctr	I Metal		Blue	0.3	QM
16	002	X Dorm	B Door		Rgt Rgt casing	I Metal		Blue	1.0	QM
17	003	X Wash Area	C Door		Rgt Rgt casing	I Metal		Blue	1.0	QM
18	003	X Wash Area	C Door		Rgt U Ctr	I Metal		Blue	0.0	QM
19	003	X Wash Area	D Wall	L Ctr		I Concrete		White	-0.1	QM
20	003	X Wash Area	A Wall	L Ctr		I Concrete		White	0.0	QM
21	003	X Wash Area	B Wall	L Ctr		I Concrete		White	-0.2	QM
22	003	X Wash Area	B Wall	L Rgt		I Ceramic		White	-0.1	QM
23	003	X Wash Area	A Floor			I Concrete		Gray	-0.1	QM
24	003	X Wash Area	B Window		Rgt Sash	I Vinyl		Blue	4.9	QM
25	003	X Wash Area	B Beam		Rgt	I Wood		Black	0.1	QM
26	003	X Wash Area	B Beam		Rgt	I Wood		Brown	0.0	QM
27	004	X Din. Area	C Beam		Rgt	I Wood		Brown	0.0	QM
28	004	X Din. Area	C Beam		Rgt	I Wood		Black	0.0	QM
29	004	X Din. Area	B Wall	U Rgt		I Concrete		White	0.0	QM
30	004	X Din. Area	D Chair rail		Ctr	I Concrete		White	0.0	QM
31	004	X Din. Area	C Floor			I Concrete		Gray	-0.1	QM
32	004	X Din. Area	B Wall	L Rgt		I Ceramic		Tan	-0.1	QM
33	004	X Din. Area	C Wall	U Ctr		I Drywall		White	0.0	QM
34	004	X Din. Area	C Ceiling			I Wood		White	0.1	QM
35	004	X Din. Area	D Door		Ctr U Ctr	I Wood		Blue	0.1	QM
36	004	X Din. Area	C Window		Ctr Sash	I Vinyl		Blue	4.9	QM
37	004	X Din. Area	B Window		Ctr Rgt casing	I Vinyl		Blue	5.7	QM
38	004	X Din. Area	C Window		Ctr Rgt casing	I Vinyl		Blue	3.8	QM
39	004	X Din. Area	B Window		Ctr Rgt casing	I Vinyl		Blue	6.3	QM
40	004	X Din. Area	B Window		Ctr Apron	I Wood		Blue	0.0	QM
41	004	X Din. Area	B Door		Lft Header	I Wood		Blue	0.0	QM
42	004	X Din. Area	B Beam		Lft	I Wood		Black	0.0	QM
43	004	X Din. Area	B Beam		Lft	I Wood		Brown	0.0	QM
44	004	X Din. Area	B Bench		Lft	I Wood		Brown	0.0	QM
45	004	X Din. Area	D Wall	L Ctr		I Drywall		White	0.0	QM
46	004	X Din. Area	B Wall	L Ctr		I Drywall		White	0.0	QM
47	004	X Din. Area	D Wall	U Rgt		I Concrete		Blue	0.0	QM
48	004	X Din. Area	B Wall	U Rgt		I Concrete		White	-0.1	QM
49	004	X Din. Area	B Door		Lft U Ctr	I Metal		Blue	0.1	QM
50	001	X Bldg Ext	A Beam		Rgt	I Wood		Brown	0.0	QM
51	001	X Bldg Ext	A Soffit			I Wood		Brown	0.1	QM

52	001 X Bldg Ext	A	Fascia			I Metal	Brown	0.1	QM
53	001 X Bldg Ext	A	Wall	U Lft		I Wood	Blue	0.1	QM
54	001 X Bldg Ext	D	Beam	Ctr		I Wood	Brown	0.0	QM
55	001 X Bldg Ext	D	Soffit			I Wood	Brown	0.1	QM
56	001 X Bldg Ext	C	Door	Lft U Ctr		I Metal	Blue	0.0	QM
57	001 X Bldg Ext	C	Window	Ctr Rgt casing		I Vinyl	Brown	3.0	QM
58	001 X Bldg Ext	C	Railing	Lft Railing		I Wood	Brown	0.0	QM
59	001 X Bldg Ext	D	Door	Lft U Ctr		I Metal	Blue	0.3	QM
60	001 X Bldg Ext	C	Railing	Ctr Railing		I Metal	Yellow	4.6	QM
61	001 X Bldg Ext	C	Dock	Ctr		I Concrete	Yellow	0.0	QM
62	001 X Bldg Ext	C	Rollup Door	Ctr		I Metal	Blue	0.0	QM
63	001 X Bldg Ext	B	Beam	Rgt		I Wood	Brown	0.0	QM
64	005 Ans. Kitch	B	Wall	L Ctr		I Concrete	Gray	0.1	QM
65	005 Ans. Kitch	C	Wall	L Ctr		I Concrete	Gray	-0.1	QM
66	005 Ans. Kitch	C	Cage	Ctr		I Metal	Gray	1.0	QM
67	005 Ans. Kitch	B	Post	Rgt		I Metal	Gray	1.0	QM
68	005 Ans. Kitch	B	Door	Rgt U Ctr		I Metal	Green	0.2	QM
69	005 Ans. Kitch	B	Door	Rgt Lft casing		I Metal	Green	0.3	QM
70	005 Ans. Kitch	B	Door	Ctr U Ctr		I Metal	Blue	1.0	QM
71	005 Ans. Kitch	B	Door	Ctr Lft casing		I Metal	Blue	0.3	QM
72	005 Ans. Kitch	D	Window	Ctr Rgt casing		I Metal	Green	0.0	QM
73	005 Ans. Kitch	D	Window	Ctr Rgt casing		I Metal	Blue	-0.1	QM
74	005 Ans. Kitch	B	Wall	L Lft		I Drywall	Gray	0.3	QM
75	005 Ans. Kitch	C	Beam	Ctr		I Metal	Red	2.1	QM
76	006 Ans. Office	D	Wall	L Rgt		I Concrete	Tan	0.0	QM
77	006 Ans. Office	A	Wall	L Ctr		I Concrete	Gray	-0.2	QM
78	006 Ans. Office	B	Wall	L Lft		I Drywall	Gray	0.0	QM
79	006 Ans. Office	D	Wall	L Ctr		I Drywall	Gray	0.0	QM
80	006 Ans. Office	D	Wall	U Rgt		I Drywall	Tan	0.0	QM
81	006 Ans. Office	C	Wall	L Rgt		I Concrete	Green	0.0	QM
82	006 Ans. Office	C	Door	Rgt U Ctr		I Wood	Beige	0.0	QM
83	006 Ans. Office	C	Door	Rgt Rgt casing		I Metal	Beige	0.2	QM
84	006 Ans. Office	D	Window	Rgt Rgt casing		I Wood	White	0.0	QM
85	002 Ans. Ext	A	Wall	L Rgt		I Concrete	White	0.0	QM
86	002 Ans. Ext	A	Wall	L Ctr		I Concrete	White	0.0	QM
87	002 Ans. Ext	A	Window	Ctr Rgt casing		I Vinyl	Blue	0.0	QM
88	002 Ans. Ext	B	Window	Ctr Rgt casing		I Vinyl	Blue	0.0	QM
89	002 Ans. Ext	B	Door	Lft U Ctr		I Metal	Blue	0.2	QM
90	002 Ans. Ext	B	Door	Lft Rgt jamb		I Metal	Blue	0.1	QM
91	002 Ans. Ext	B	Post	Ctr		I Metal	White	0.2	QM
92	002 Ans. Ext	B	Wall	L Rgt		I Concrete	White	-0.1	QM
93	002 Ans. Ext	B	Wall	L Lft		I Concrete	White	-0.1	QM
94	002 Ans. Ext	B	Soffit			I Stucco	White	0.1	QM
95	008 Number Only	C	Wall	U Ctr		I Drywall	White	0.0	QM
96	008 Number Only	A	Wall	L Ctr		I Drywall	White	0.0	QM
97	008 Number Only	A	Wall	U Ctr		I Drywall	White	0.0	QM
98	008 Number Only	C	Shelves	Ctr		I Wood	White	0.1	QM
99	008 Number Only	C	Cabinet	Ctr		I Wood	White	0.0	QM
100	008 Number Only	A	Window	Lft Sill		I Wood	White	0.0	QM
101	008 Number Only	B	Window	Ctr Sill		I Wood	White	-0.1	QM
102	008 Number Only	B	Door	Ctr U Ctr		I Wood	White	0.0	QM
103	008 Number Only	B	Door	Ctr Rgt casing		I Wood	White	0.1	QM
104	008 Number Only	A	Door	Rgt Rgt casing		I Wood	White	0.3	QM
105	008 Number Only	A	Door	Rgt U Ctr		I Metal	White	0.0	QM
106	003 Classrm Ext	A	Door	Ctr U Ctr		I Metal	Blue	0.6	QM
107	003 Classrm Ext	A	Door	Ctr Rgt casing		I Wood	Blue	0.0	QM
108	003 Classrm Ext	A	Deck	Ctr		I Wood	Blue	0.0	QM
109	003 Classrm Ext	A	Railing	Ctr Railing		I Wood	Blue	0.0	QM
110	003 Classrm Ext	A	Column	Ctr U column		I Wood	Blue	0.1	QM
111	003 Classrm Ext	A	Railing	Ctr Railing		I Metal	Blue	1.0	QM
112	003 Classrm Ext	A	Down Spout	Ctr		I Metal	Brown	0.3	QM
113	003 Classrm Ext	A	Pipe	Ctr		I Metal	Brown	0.3	QM
114	003 Classrm Ext	A	Gutter			I Metal	Blue	0.6	QM
115	003 Classrm Ext	A	Soffit			I Wood	Brown	0.3	QM
116	003 Classrm Ext	A	Fascia			I Wood	Brown	0.0	QM

117	003	Classrm Ext	A	Wall	L	Ctr	I	Wood	Brown	0.0	QM		
118	003	Classrm Ext	D	Wall	L	Ctr	I	Wood	Brown	0.1	QM		
119	003	Classrm Ext	C	Wall	L	Ctr	I	Wood	Brown	0.0	QM		
120	003	Classrm Ext	D	Window			Ctr	Rgt casing	I	Wood	Blue	0.0	QM
121	003	Classrm Ext	C	Foundation			Ctr		I	Concrete	Brown	0.0	QM
122		CALIBRATION										0.8	TC
123		CALIBRATION										1.0	TC
124		CALIBRATION										1.0	TC

---- End of Readings ----

SUMMARY REPORT OF LEAD PAINT INSPECTION FOR: Moss & Associates

Inspection Date:	04/22/15	Santa Cruz Roundtree SB10022
Report Date:	4/29/2015	90 Roundtree Lane
Abatement Level:	1.0	Watsonville, CA
Report No.	S#01369 - 04/22/15 12:26	Limited Areas
Total Readings:	124 Actionable: 14	
Job Started:	04/22/15 12:26	
Job Finished:	04/23/15 18:05	

Read No.	Wall	Structure	Location	Member	Paint Cond	Substrate	Paint Color	Lead (mg/cm ²)	Mode
Exterior Room 001 X Bldg Ext									
057	C	Window	Ctr	Rgt casing	I	Vinyl	Brown	3.0	QM
060	C	Railing	Ctr	Railing	I	Metal	Yellow	4.6	QM
Exterior Room 003 Classrm Ext									
111	A	Railing	Ctr	Railing	I	Metal	Blue	1.0	QM
Interior Room 002 X Dorm									
016	B	Door	Rgt	Rgt casing	I	Metal	Blue	1.0	QM
Interior Room 003 X Wash Area									
024	B	Window	Rgt	Sash	I	Vinyl	Blue	4.9	QM
017	C	Door	Rgt	Rgt casing	I	Metal	Blue	1.0	QM
Interior Room 004 X Din. Area									
037	B	Window	Ctr	Rgt casing	I	Vinyl	Blue	5.7	QM
039	B	Window	Ctr	Rgt casing	I	Vinyl	Blue	6.3	QM
038	C	Window	Ctr	Rgt casing	I	Vinyl	Blue	3.8	QM
036	C	Window	Ctr	Sash	I	Vinyl	Blue	4.9	QM
Interior Room 005 Ans. Kitch									
070	B	Door	Ctr	U Ctr	I	Metal	Blue	1.0	QM
067	B	Post	Rgt		I	Metal	Gray	1.0	QM
066	C	Cage	Ctr		I	Metal	Gray	1.0	QM
075	C	Beam	Ctr		I	Metal	Red	2.1	QM

Calibration Readings

---- End of Readings ----

DETAILED REPORT OF LEAD PAINT INSPECTION FOR: Moss & Associates

Inspection Date: 04/22/15 Santa Cruz Roundtree SB10022
 Report Date: 4/29/2015 90 Roundtree Lane
 Abatement Level: 1.0 Watsonville, CA
 Report No. S#01369 - 04/22/15 12:26 Limited Areas
 Total Readings: 124
 Job Started: 04/22/15 12:26
 Job Finished: 04/23/15 18:05

Read No.	Wall	Structure	Location	Member	Paint Cond	Substrate	Paint Color	Lead (mg/cm ²)	Mode
Exterior Room 001 X Bldg Ext									
053	A	Wall	U Lft		I	Wood	Blue	0.1	QM
052	A	Fascia			I	Metal	Brown	0.1	QM
051	A	Soffit			I	Wood	Brown	0.1	QM
050	A	Beam	Rgt		I	Wood	Brown	0.0	QM
063	B	Beam	Rgt		I	Wood	Brown	0.0	QM
057	C	Window	Ctr	Rgt casing	I	Vinyl	Brown	3.0	QM
056	C	Door	Lft	U Ctr	I	Metal	Blue	0.0	QM
058	C	Railing	Lft	Railing	I	Wood	Brown	0.0	QM
060	C	Railing	Ctr	Railing	I	Metal	Yellow	4.6	QM
061	C	Dock	Ctr		I	Concrete	Yellow	0.0	QM
062	C	Rollup Door	Ctr		I	Metal	Blue	0.0	QM
055	D	Soffit			I	Wood	Brown	0.1	QM
059	D	Door	Lft	U Ctr	I	Metal	Blue	0.3	QM
054	D	Beam	Ctr		I	Wood	Brown	0.0	QM
Exterior Room 002 Ans. Ext									
086	A	Wall	L Ctr		I	Concrete	White	0.0	QM
085	A	Wall	L Rgt		I	Concrete	White	0.0	QM
087	A	Window	Ctr	Rgt casing	I	Vinyl	Blue	0.0	QM
093	B	Wall	L Lft		I	Concrete	White	-0.1	QM
092	B	Wall	L Rgt		I	Concrete	White	-0.1	QM
094	B	Soffit			I	Stucco	White	0.1	QM
088	B	Window	Ctr	Rgt casing	I	Vinyl	Blue	0.0	QM
090	B	Door	Lft	Rgt jamb	I	Metal	Blue	0.1	QM
089	B	Door	Lft	U Ctr	I	Metal	Blue	0.2	QM
091	B	Post	Ctr		I	Metal	White	0.2	QM
Exterior Room 003 Classrm Ext									
117	A	Wall	L Ctr		I	Wood	Brown	0.0	QM
116	A	Fascia			I	Wood	Brown	0.0	QM
114	A	Gutter			I	Metal	Blue	0.6	QM
115	A	Soffit			I	Wood	Brown	0.3	QM
107	A	Door	Ctr	Rgt casing	I	Wood	Blue	0.0	QM
106	A	Door	Ctr	U Ctr	I	Metal	Blue	0.6	QM
109	A	Railing	Ctr	Railing	I	Wood	Blue	0.0	QM
111	A	Railing	Ctr	Railing	I	Metal	Blue	1.0	QM
110	A	Column	Ctr	U column	I	Wood	Blue	0.1	QM
108	A	Deck	Ctr		I	Wood	Blue	0.0	QM
112	A	Down Spout	Ctr		I	Metal	Brown	0.3	QM
113	A	Pipe	Ctr		I	Metal	Brown	0.3	QM
119	C	Wall	L Ctr		I	Wood	Brown	0.0	QM
121	C	Foundation	Ctr		I	Concrete	Brown	0.0	QM
118	D	Wall	L Ctr		I	Wood	Brown	0.1	QM
120	D	Window	Ctr	Rgt casing	I	Wood	Blue	0.0	QM
Interior Room 001 X Module									
004	A	Wall	L Ctr		I	Wood	White	0.0	QM
009	A	Window	Ctr	Rgt casing	I	Wood	Brown	0.0	QM
008	A	Door	Ctr	Rgt casing	I	Wood	Blue	0.1	QM
010	B	Wall	L Lft		I	Wood	Blue	0.0	QM

005	B	Wall	L Ctr		I	Wood	White	0.2	QM
007	B	Window	Ctr	Rgt casing	I	Wood	Blue	0.2	QM
006	D	Wall	L Ctr		I	Drywall	White	0.0	QM

Interior Room 002 X Dorm

013	A	Wall	L Ctr		I	Concrete	White	0.0	QM
011	A	Beam	Ctr		I	Wood	Black	0.0	QM
012	A	Beam	Ctr		I	Wood	Brown	0.0	QM
016	B	Door	Rgt	Rgt casing	I	Metal	Blue	1.0	QM
015	B	Door	Rgt	U Ctr	I	Metal	Blue	0.3	QM
014	C	Wall	U Ctr		I	Concrete	White	0.3	QM

Interior Room 003 X Wash Area

020	A	Wall	L Ctr		I	Concrete	White	0.0	QM
023	A	Floor			I	Concrete	Gray	-0.1	QM
021	B	Wall	L Ctr		I	Concrete	White	-0.2	QM
022	B	Wall	L Rgt		I	Ceramic	White	-0.1	QM
024	B	Window	Rgt	Sash	I	Vinyl	Blue	4.9	QM
025	B	Beam	Rgt		I	Wood	Black	0.1	QM
026	B	Beam	Rgt		I	Wood	Brown	0.0	QM
017	C	Door	Rgt	Rgt casing	I	Metal	Blue	1.0	QM
018	C	Door	Rgt	U Ctr	I	Metal	Blue	0.0	QM
019	D	Wall	L Ctr		I	Concrete	White	-0.1	QM

Interior Room 004 X Din. Area

046	B	Wall	L Ctr		I	Drywall	White	0.0	QM
032	B	Wall	L Rgt		I	Ceramic	Tan	-0.1	QM
029	B	Wall	U Rgt		I	Concrete	White	0.0	QM
048	B	Wall	U Rgt		I	Concrete	White	-0.1	QM
037	B	Window	Ctr	Rgt casing	I	Vinyl	Blue	5.7	QM
039	B	Window	Ctr	Rgt casing	I	Vinyl	Blue	6.3	QM
040	B	Window	Ctr	Apron	I	Wood	Blue	0.0	QM
041	B	Door	Lft	Header	I	Wood	Blue	0.0	QM
049	B	Door	Lft	U Ctr	I	Metal	Blue	0.1	QM
042	B	Beam	Lft		I	Wood	Black	0.0	QM
043	B	Beam	Lft		I	Wood	Brown	0.0	QM
044	B	Bench	Lft		I	Wood	Brown	0.0	QM
033	C	Wall	U Ctr		I	Drywall	White	0.0	QM
031	C	Floor			I	Concrete	Gray	-0.1	QM
034	C	Ceiling			I	Wood	White	0.1	QM
038	C	Window	Ctr	Rgt casing	I	Vinyl	Blue	3.8	QM
036	C	Window	Ctr	Sash	I	Vinyl	Blue	4.9	QM
027	C	Beam	Rgt		I	Wood	Brown	0.0	QM
028	C	Beam	Rgt		I	Wood	Black	0.0	QM
045	D	Wall	L Ctr		I	Drywall	White	0.0	QM
047	D	Wall	U Rgt		I	Concrete	Blue	0.0	QM
030	D	Chair rail	Ctr		I	Concrete	White	0.0	QM
035	D	Door	Ctr	U Ctr	I	Wood	Blue	0.1	QM

Interior Room 005 Ans. Kitch

074	B	Wall	L Lft		I	Drywall	Gray	0.3	QM
064	B	Wall	L Ctr		I	Concrete	Gray	0.1	QM
071	B	Door	Ctr	Lft casing	I	Metal	Blue	0.3	QM
070	B	Door	Ctr	U Ctr	I	Metal	Blue	1.0	QM
069	B	Door	Rgt	Lft casing	I	Metal	Green	0.3	QM
068	B	Door	Rgt	U Ctr	I	Metal	Green	0.2	QM
067	B	Post	Rgt		I	Metal	Gray	1.0	QM
065	C	Wall	L Ctr		I	Concrete	Gray	-0.1	QM
066	C	Cage	Ctr		I	Metal	Gray	1.0	QM
075	C	Beam	Ctr		I	Metal	Red	2.1	QM
072	D	Window	Ctr	Rgt casing	I	Metal	Green	0.0	QM
073	D	Window	Ctr	Rgt casing	I	Metal	Blue	-0.1	QM

Interior Room 006 Ans. Office

077	A	Wall	L Ctr		I	Concrete	Gray	-0.2	QM
-----	---	------	-------	--	---	----------	------	------	----

078	B	Wall	L Lft		I	Drywall	Gray	0.0	QM
081	C	Wall	L Rgt		I	Concrete	Green	0.0	QM
083	C	Door	Rgt	Rgt casing	I	Metal	Beige	0.2	QM
082	C	Door	Rgt	U Ctr	I	Wood	Beige	0.0	QM
079	D	Wall	L Ctr		I	Drywall	Gray	0.0	QM
076	D	Wall	L Rgt		I	Concrete	Tan	0.0	QM
080	D	Wall	U Rgt		I	Drywall	Tan	0.0	QM
084	D	Window	Rgt	Rgt casing	I	Wood	White	0.0	QM

Interior Room 008 Number Only

096	A	Wall	L Ctr		I	Drywall	White	0.0	QM
097	A	Wall	U Ctr		I	Drywall	White	0.0	QM
100	A	Window	Lft	Sill	I	Wood	White	0.0	QM
104	A	Door	Rgt	Rgt casing	I	Wood	White	0.3	QM
105	A	Door	Rgt	U Ctr	I	Metal	White	0.0	QM
101	B	Window	Ctr	Sill	I	Wood	White	-0.1	QM
103	B	Door	Ctr	Rgt casing	I	Wood	White	0.1	QM
102	B	Door	Ctr	U Ctr	I	Wood	White	0.0	QM
095	C	Wall	U Ctr		I	Drywall	White	0.0	QM
098	C	Shelves	Ctr		I	Wood	White	0.1	QM
099	C	Cabinet	Ctr		I	Wood	White	0.0	QM

Calibration Readings

001								0.9	TC
002								0.9	TC
003								1.0	TC
122								0.8	TC
123								1.0	TC
124								1.0	TC

---- End of Readings ----

DISTRIBUTION REPORT OF LEAD PAINT INSPECTION FOR: Moss & Associates

Inspection Date: 04/22/15 Santa Cruz Roundtree SB10022
 Report Date: 4/29/2015 90 Roundtree Lane
 Abatement Level: 1.0 Watsonville, CA
 Report No. S#01369 - 04/22/15 12:26 Limited Areas
 Total Reading Sets: 118
 Job Started: 04/22/15 12:26
 Job Finished: 04/23/15 18:05

Structure	Total	Structure Distribution		
		Positive	Negative	Inconclusive
Beam	12	1 <8%>	11 <92%>	0 <0%>
Bench	1	0 <0%>	1 <100%>	0 <0%>
Cabinet	1	0 <0%>	1 <100%>	0 <0%>
Cage	1	1 <100%>	0 <0%>	0 <0%>
Ceiling	1	0 <0%>	1 <100%>	0 <0%>
Chair rail	1	0 <0%>	1 <100%>	0 <0%>
Column U column	1	0 <0%>	1 <100%>	0 <0%>
Deck	1	0 <0%>	1 <100%>	0 <0%>
Dock	1	0 <0%>	1 <100%>	0 <0%>
Door Header	1	0 <0%>	1 <100%>	0 <0%>
Door Lft casing	2	0 <0%>	2 <100%>	0 <0%>
Door Rgt casing	7	2 <29%>	5 <71%>	0 <0%>
Door Rgt jamb	1	0 <0%>	1 <100%>	0 <0%>
Door U Ctr	13	1 <8%>	12 <92%>	0 <0%>
Down Spout	1	0 <0%>	1 <100%>	0 <0%>
Fascia	2	0 <0%>	2 <100%>	0 <0%>
Floor	2	0 <0%>	2 <100%>	0 <0%>
Foundation	1	0 <0%>	1 <100%>	0 <0%>
Gutter	1	0 <0%>	1 <100%>	0 <0%>
Pipe	1	0 <0%>	1 <100%>	0 <0%>
Post	2	1 <50%>	1 <50%>	0 <0%>
Railing Railing	4	2 <50%>	2 <50%>	0 <0%>
Rollup Door	1	0 <0%>	1 <100%>	0 <0%>
Shelves	1	0 <0%>	1 <100%>	0 <0%>
Soffit	4	0 <0%>	4 <100%>	0 <0%>
Wall	37	0 <0%>	37 <100%>	0 <0%>
Window Apron	1	0 <0%>	1 <100%>	0 <0%>
Window Rgt casing	12	4 <33%>	8 <67%>	0 <0%>
Window Sash	2	2 <100%>	0 <0%>	0 <0%>
Window Sill	2	0 <0%>	2 <100%>	0 <0%>
Inspection Totals:	118	14 <12%>	104 <88%>	0 <0%>



Bulk Asbestos Point Count Analysis

(NESHAP Final Rule, 40 CFR, Part 61)

Protech Consulting & Engineers Inc.
Project Manager

1208 Main St.
Redwood City, CA 94063

Client ID: 1454
Report Number: N007153
Date Received: 04/24/15
Date Analyzed: 05/19/15
Date Printed: 05/19/15

Job ID/Site: 338-MA15, 423-338-47 - Santa Cruz Roundtree SB1022, X Building

FALI Job ID: 1454
Total Samples Submitted: 6
Total Samples Analyzed: 6

PLM Report Number: B204709

Sample Preparation and Analysis:

The NESHAP Final Rule does not define the preparation method for multi-layered samples. In order to determine the composite quantity of asbestos, the volume percent of each layer is determined, the asbestos containing layers are analyzed by point counting and the composite quantity of asbestos is calculated. The NESHAP Final Rule can not be applied to matrices that dissolve in refractive index liquid. This includes tar, mastic or adhesive typically found on the back of floor tiles. According to the NESHAP Final Rule, point count data is only necessary when the visual estimate of asbestos is below 10%.

Sample ID	Lab Number	Layer Description
02	11635715	Composite of ALL Layers White Drywall Off-White Skimcoat/Joint Compound Paint

Point Count Results:

Number of asbestos points counted: 0
Number of non-empty points: 400
Layer percentage of entire sample: 100
Percent asbestos in layer: < 1

Asbestos type(s) detected: Chrysotile

Comment: Asbestos was detected but no points were counted due to counting criteria. Therefore quantitation deemed to be < 1%.

03	11635716	Composite of ALL Layers White Drywall White Skimcoat/Joint Compound White Tape Off-White Skimcoat/Joint Compound Paint
----	----------	---

Point Count Results:

Number of asbestos points counted: 0
Number of non-empty points: 400
Layer percentage of entire sample: 100
Percent asbestos in layer: < 1

Asbestos type(s) detected: Chrysotile

Comment: Asbestos was detected but no points were counted due to counting criteria. Therefore quantitation deemed to be < 1%.



Bulk Asbestos Point Count Analysis

(NESHAP Final Rule, 40 CFR, Part 61)

Protech Consulting & Engineers Inc.
Project Manager

1208 Main St.
Redwood City, CA 94063

Client ID: 1454
Report Number: N007153
Date Received: 04/24/15
Date Analyzed: 05/19/15
Date Printed: 05/19/15

Job ID/Site: 338-MA15, 423-338-47 - Santa Cruz Roundtree SB1022, X Building

FALI Job ID: 1454
Total Samples Submitted: 6
Total Samples Analyzed: 6

PLM Report Number: B204709

Sample Preparation and Analysis:

The NESHAP Final Rule does not define the preparation method for multi-layered samples. In order to determine the composite quantity of asbestos, the volume percent of each layer is determined, the asbestos containing layers are analyzed by point counting and the composite quantity of asbestos is calculated. The NESHAP Final Rule can not be applied to matrices that dissolve in refractive index liquid. This includes tar, mastic or adhesive typically found on the back of floor tiles. According to the NESHAP Final Rule, point count data is only necessary when the visual estimate of asbestos is below 10%.

Sample ID	Lab Number	Layer Description
06	11635719	Composite of ALL Layers White Drywall White Skimcoat/Joint Compound White Tape Off-White Skimcoat/Joint Compound Paint

Point Count Results:

Number of asbestos points counted: 0
Number of non-empty points: 400
Layer percentage of entire sample: 100
Percent asbestos in layer: < 1

Asbestos type(s) detected: Chrysotile

Comment: Asbestos was detected but no points were counted due to counting criteria. Therefore quantitation deemed to be < 1%.

07	11635720	Composite of ALL Layers White Drywall Off-White Skimcoat/Joint Compound Paint
----	----------	---

Point Count Results:

Number of asbestos points counted: 0
Number of non-empty points: 400
Layer percentage of entire sample: 100
Percent asbestos in layer: < 1

Asbestos type(s) detected: Chrysotile

Comment: Asbestos was detected but no points were counted due to counting criteria. Therefore quantitation deemed to be < 1%.



Bulk Asbestos Point Count Analysis

(NESHAP Final Rule, 40 CFR, Part 61)

Protech Consulting & Engineers Inc.
Project Manager

1208 Main St.
Redwood City, CA 94063

Client ID: 1454
Report Number: N007153
Date Received: 04/24/15
Date Analyzed: 05/19/15
Date Printed: 05/19/15

Job ID/Site: 338-MA15, 423-338-47 - Santa Cruz Roundtree SB1022, X Building

FALI Job ID: 1454

PLM Report Number: B204709

Total Samples Submitted: 6
Total Samples Analyzed: 6

Sample Preparation and Analysis:

The NESHAP Final Rule does not define the preparation method for multi-layered samples. In order to determine the composite quantity of asbestos, the volume percent of each layer is determined, the asbestos containing layers are analyzed by point counting and the composite quantity of asbestos is calculated. The NESHAP Final Rule can not be applied to matrices that dissolve in refractive index liquid. This includes tar, mastic or adhesive typically found on the back of floor tiles. According to the NESHAP Final Rule, point count data is only necessary when the visual estimate of asbestos is below 10%.

Sample ID	Lab Number	Layer Description
34	11635747	Brown Non-Fibrous Material
<i>Point Count Results:</i>		
Number of asbestos points counted: 2		
Number of non-empty points: 400		
Layer percentage of entire sample: 100		
Percent asbestos in layer: < 1		
Asbestos type(s) detected: Chrysotile		
Comment:		
35	11635748	Brown Non-Fibrous Material
<i>Point Count Results:</i>		
Number of asbestos points counted: 1		
Number of non-empty points: 400		
Layer percentage of entire sample: 15		
Percent asbestos in layer: < 1		
Asbestos type(s) detected: Chrysotile		
Comment:		

Note: Point count results are reported to the nearest percent per EPA method.

Tad Thrower, Laboratory Supervisor, Hayward Laboratory

Note: Limit of Quantification (LOQ) = 1%. Trace denotes the presence of asbestos below the LOQ. ND = None Detected.

Analytical results and reports are generated by Forensic Analytical Laboratories Inc. (FALI) at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by FALI to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by FALI. The client is solely responsible for the use and interpretation of test results and reports requested from FALI. Forensic Analytical Laboratories Inc. is not able to assess the degree of hazard resulting from materials analyzed. FALI reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.

General Information

Date: 04-23-15
 Job ID: Santa Cruz Roundtree
SBI022
X-Building
 Collected By: EWJ
 Lab: FAST

Analysis Requested

- PCM NIOSH 7400
- TEM
- AHERA
- Level 2
- Bulk Quantitative
- Bulk Qualitative
- PLM BULK - EPA/600/R/116
- Lead
- AA
- TTLC
- STLC
- TCLP
- Mold
- Other

Turn Around Time

- Rush
- 12 hours
- 24 hours
- 48 hours
- 3-5 days
-

Special Instructions


Prior Positive

Filter Type: MCE, 0.8 µm, 25mm MCE, 0.45µm, 25mm MCE, 0.8µm, 37mm Other

Sample # Date	Sample Type	Sample Protocol	Location / Activity / Material Description	Time On/Off	LPM	Total Min. Total Vol. Fibers/Facids	Results
# 01-07 08-09	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	D.W. Mastic	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 10-11 12	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	IXI CT w/mastic Concrete	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 13-14 15-18	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Mortar Coating	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 19-21 22-26	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Mastic Glazing	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 27 28-31	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Mastic Caulk	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 32-35 36-37	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Glazing Jacket	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 38 39-40	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	↓ Caulk	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 41-42 43-47	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Mastic Roofing	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
#	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.		on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		

CHAIN OF CUSTODY

Relinquished By: <u>EWJ</u>	Date/Time	Received By: <u>[Signature]</u>	Date/Time: <u>APR 24 2015</u>
-----------------------------	-----------	---------------------------------	-------------------------------





Metals Analysis of Paints

Protech Consulting & Engineers Inc.
Project Manager

1208 Main St.
Redwood City, CA 94063

Client ID: 1454
Report Number: M160416
Date Received: 04/24/15
Date Analyzed: 04/27/15
Date Printed: 04/27/15
First Reported: 04/27/15

Job ID / Site: 338-MA15, 423-338-09 - Santa Cruz Roundtree SB1022, Paints
Date(s) Collected: 4/23/15

FALI Job ID: 1454
Total Samples Submitted: 9
Total Samples Analyzed: 9

Sample Number	Lab Number	Analyte	Result	Result Units	Reporting Limit*	Method Reference
LP-01	30711151	Pb	< 0.006	wt%	0.006	EPA 3050B/7420
LP-02	30711152	Pb	< 0.006	wt%	0.006	EPA 3050B/7420
LP-03	30711153	Pb	< 0.006	wt%	0.006	EPA 3050B/7420
LP-04	30711154	Pb	< 0.006	wt%	0.006	EPA 3050B/7420
LP-05	30711155	Pb	< 0.006	wt%	0.006	EPA 3050B/7420
LP-06	30711156	Pb	< 0.006	wt%	0.006	EPA 3050B/7420
LP-07	30711157	Pb	< 0.006	wt%	0.006	EPA 3050B/7420
LP-08	30711158	Pb	< 0.006	wt%	0.006	EPA 3050B/7420
LP-09	30711159	Pb	< 0.006	wt%	0.006	EPA 3050B/7420

* The Reporting Limit represents the lowest amount of analyte that the laboratory can confidently detect in the sample, and is not a regulatory level. The Units for the Reporting Limit are the same as the Units for the Final Results.

Daniele Siu, Laboratory Supervisor, Hayward Laboratory

Analytical results and reports are generated by Forensic Analytical at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by Forensic Analytical to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by Forensic Analytical. The client is solely responsible for the use and interpretation of test results and reports requested from Forensic Analytical. Forensic Analytical is not able to assess the degree of hazard resulting from materials analyzed. Forensic Analytical reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. Any modifications that have been made to referenced test methods are documented in Forensic Analytical's Standard Operating Procedures Manual. Sample results have not been blank corrected. Quality control and sample receipt condition were acceptable unless otherwise noted.

General Information

Date: 04-23-15
 Job ID: Santa Cruz Rowaltee
SB1022
Paints
 Collected By: EAD
 Lab: FAST

Analysis Requested

- PCM NIOSH 7400
- TEM
- AHERA
- Level 2
- Bulk Quantitative
- Bulk Qualitative
- PLM BULK - EPA/800/R/116
- Lead
 - AA
 - TTLC
 - STLC
 - TCLP
- Mold
- Other

Turn Around Time

- Rush
- 12 hours
- 24 hours
- 48 hours
- 3-5 days

Special Instructions


Prior Positive

Filter Type: MCE, 0.8 µm, 25mm MCE, 0.45µm, 25mm MCE, 0.8µm, 37mm Other

Sample # Date	Sample Type	Sample Proto	Location / Activity / Material Description	Time On/Off	LPM	Total Vol. Total Vol. Fibers/Fields	Results
# LP-01	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	X-Bldg. Gray Concrete Paint 12 weight Room area 150 sq. ft. loose & Red	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# LP-02	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	White drywall Paint	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# LP-03	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Gray wood wall Paint	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# LP-04	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	V Blue Wood Door Paint	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# LP-05	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Ancillary Bldg. Gray Drywall Paint	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# LP-06	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Interior white concrete Paint	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# LP-07	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Exterior white concrete Paint	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# LP-08	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Classroom Bldg. Ext. Blue Wood Deck/Railing Paint	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# LP-09	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Ext. Brown wood Siding Paint	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		

CHAIN OF CUSTODY

Relinquished By:	Date/Time	Received By:	Date/Time
<u>EAD</u>		<u>[Signature]</u>	APR 24 2015





Bulk Asbestos Analysis

(EPA Method 600/R-93-116, Visual Area Estimation)

Protech Consulting & Engineers Inc.
Project Manager

1208 Main St.
Redwood City, CA 94063

Client ID: 1454
Report Number: B204709
Date Received: 04/24/15
Date Analyzed: 04/28/15
Date Printed: 04/28/15
First Reported: 04/28/15

Job ID/Site: 338-MA15, 423-338-47 - Santa Cruz Roundtree SB1022, X Building

FALI Job ID: 1454
Total Samples Submitted: 47
Total Samples Analyzed: 47

Date(s) Collected: 04/23/2015

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
01	11635714						
Layer: White Drywall			ND				
Layer: White Skimcoat/Joint Compound			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)	Fibrous Glass (10 %)						
02	11635715						
Layer: White Drywall			ND				
Layer: Off-White Skimcoat/Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (10 %)						
03	11635716						
Layer: White Drywall			ND				
Layer: White Skimcoat/Joint Compound		Chrysotile	2 %				
Layer: White Tape			ND				
Layer: Off-White Skimcoat/Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (10 %)						
04	11635717						
Layer: White Drywall			ND				
Layer: White Skimcoat/Joint Compound			ND				
Layer: White Tape			ND				
Layer: White Skimcoat/Joint Compound			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)	Fibrous Glass (10 %)						
05	11635718						
Layer: White Drywall			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)	Fibrous Glass (10 %)						

Client Name: Protech Consulting & Engineers Inc.

Report Number: B204709

Date Printed: 04/28/15

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
06	11635719						
Layer: White Drywall			ND				
Layer: White Skimcoat/Joint Compound		Chrysotile	2 %				
Layer: White Tape			ND				
Layer: Off-White Skimcoat/Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (10 %)						
07	11635720						
Layer: White Drywall			ND				
Layer: Off-White Skimcoat/Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (10 %)						
08	11635721						
Layer: Tan Mastic			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
09	11635722						
Layer: Tan Mastic			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
10	11635723						
Layer: Brown Mastic			ND				
Layer: Yellow Fibrous Tile			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (2 %)	Fibrous Glass (90 %)						
11	11635724						
Layer: Tan Mastic			ND				
Layer: Tan Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (95 %)							
12	11635725						
Layer: Grey Mortar			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
13	11635726						
Layer: Grey Mortar			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							

Report Number: B204709

Date Printed: 04/28/15

Client Name: Protech Consulting & Engineers Inc.

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
14	11635727						
		Layer: Tan Coating					ND
		Layer: Paint					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (Trace)					
15	11635728						
		Layer: Tan Coating					ND
		Layer: Paint					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (Trace)					
16	11635729						
		Layer: Tan Coating					ND
		Layer: Paint					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (Trace)					
17	11635730						
		Layer: Tan Coating					ND
		Layer: Paint					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (Trace)					
18	11635731						
		Layer: Tan Coating					ND
		Layer: Paint					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (Trace)					
19	11635732						
		Layer: Brown Mastic					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (Trace)					
20	11635733						
		Layer: Brown Mastic					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (Trace)					
21	11635734						
		Layer: Brown Mastic					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (Trace)					
22	11635735						
		Layer: Grey Non-Fibrous Material					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (Trace)					

Report Number: B204709

Date Printed: 04/28/15

Client Name: Protech Consulting & Engineers Inc.

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
23	11635736						
Layer: Grey Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
24	11635737						
Layer: Grey Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
25	11635738						
Layer: Grey Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
26	11635739						
Layer: Grey Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
27	11635740						
Layer: Yellow Mastic			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
28	11635741						
Layer: Dark Brown Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace) Fibrous Glass (5 %)							
29	11635742						
Layer: Dark Brown Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace) Fibrous Glass (5 %)							
30	11635743						
Layer: Dark Brown Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace) Fibrous Glass (5 %)							
31	11635744						
Layer: Dark Brown Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace) Fibrous Glass (5 %)							
32	11635745						
Layer: Brown Non-Fibrous Material			ND				
Layer: Grey Non-Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							

Client Name: Protech Consulting & Engineers Inc.

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
33	11635746						
Layer: Brown Non-Fibrous Material			ND				
Layer: Grey Non-Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
34	11635747						
Layer: Brown Non-Fibrous Material		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
35	11635748						
Layer: Brown Non-Fibrous Material		Chrysotile	Trace				
Layer: Grey Non-Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
36	11635749						
Layer: Yellow Fibrous Material			ND				
Layer: Tan Woven Material			ND				
Layer: White Coating			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (75 %) Fibrous Glass (25 %)							
37	11635750						
Layer: Yellow Fibrous Material			ND				
Layer: White Woven Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (75 %) Fibrous Glass (25 %)							
38	11635751						
Layer: Yellow Fibrous Material			ND				
Layer: White Woven Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (75 %) Fibrous Glass (25 %)							
39	11635752						
Layer: Dark Brown Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
40	11635753						
Layer: Dark Brown Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
41	11635754						
Layer: Black Mastic			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							

Report Number: B204709

Date Printed: 04/28/15

Client Name: Protech Consulting & Engineers Inc.


Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
42	11635755						
		Layer: Black Mastic					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (Trace)					
43	11635756						
		Layer: Black Roof Shingle					ND
		Layer: Black Roof Shingle					ND
		Layer: Black Felt					ND
		Layer: Black Felt					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %) Fibrous Glass (35 %)					
		Comment: Bulk complex sample.					
44	11635757						
		Layer: Black Roof Shingle					ND
		Layer: Black Roof Shingle					ND
		Layer: Black Felt					ND
		Layer: Black Felt					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %) Fibrous Glass (35 %)					
		Comment: Bulk complex sample.					
45	11635758						
		Layer: Black Roof Shingle					ND
		Layer: Black Roof Shingle					ND
		Layer: Black Felt					ND
		Layer: Black Felt					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %) Fibrous Glass (35 %)					
		Comment: Bulk complex sample.					
46	11635759						
		Layer: Black Roof Shingle					ND
		Layer: Black Roof Shingle					ND
		Layer: Black Felt					ND
		Layer: Black Felt					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %) Fibrous Glass (35 %)					
		Comment: Bulk complex sample.					
47	11635760						
		Layer: Black Roof Shingle					ND
		Layer: Black Roof Shingle					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %) Fibrous Glass (35 %)					
		Comment: Bulk complex sample.					

Report Number: B204709

Date Printed: 04/28/15

Client Name: Protech Consulting & Engineers Inc.

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
-----------	------------	---------------	------------------	---------------	------------------	---------------	------------------



Tad Thrower, Laboratory Supervisor, Hayward Laboratory

Note: Limit of Quantification ('LOQ') = 1%. 'Trace' denotes the presence of asbestos below the LOQ. 'ND' = 'None Detected'.

Analytical results and reports are generated by Forensic Analytical Laboratories Inc. (FALI) at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by FALI to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by FALI. The client is solely responsible for the use and interpretation of test results and reports requested from FALI. Forensic Analytical Laboratories Inc. is not able to assess the degree of hazard resulting from materials analyzed. FALI reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.

General Information

Date: 04-23-15
 Job ID: Scate Cruz Roundtree
SB1022
X-Building
 Collected By: ESD
 Lab: FAST

Analysis Requested

- PCM NIOSH 7400
- TEM
- AHERA
- Level 2
- Bulk Quantitative
- Bulk Qualitative
- PLM BULK - EPA/600/R/116
- Lead
- AA
- TTLC
- STLC
- TCLP
- Mold
- Other _____

Turn Around Time

- Rush
- 12 hours
- 24 hours
- 48 hours
- 3-5 days
- _____

Special Instructions


Prior Positive

Filter Type: MCE, 0.8 µm, 25mm MCE, 0.45µm, 25mm MCE, 0.8µm, 37mm Other _____

Sample # Date	Sample Type	Sample Protocol	Location / Activity / Material Description	Time On/Off	LPM	Total Min. Total Vol. Fibers/Folds	Results
# 01-07 08-09	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	D.W. Mastic	on _____ off _____ pump# _____	on _____ and _____ Ave _____ Roto# _____		
# 10-11 12	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	IXI C.T. w/mastic Concrete	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 13-14 15-18	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Mortar Coating	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 19-21 22-26	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Mastic Glazing	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 27 28-31	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Mastic Caulk	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 32-35 36-37	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Glazing Jacket	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 38 39-40	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	↓ Caulk	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 41-42 43-47	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Mastic Roofing	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
#	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.		on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		

CHAIN OF CUSTODY

Relinquished By: <u>ESD</u>	Date/Time	Received By: <u>[Signature]</u>	Date/Time <u>APR 24 2015</u>
--------------------------------	-----------	------------------------------------	---------------------------------





Bulk Asbestos Analysis

(EPA Method 600/R-93-116, Visual Area Estimation)

Protech Consulting & Engineers Inc.
Project Manager

1208 Main St.
Redwood City, CA 94063

Client ID: 1454
Report Number: B204707
Date Received: 04/24/15
Date Analyzed: 04/27/15
Date Printed: 04/27/15
First Reported: 04/27/15

Job ID/Site: 338-MA15, 423-338-14 - Santa Cruz Roundtree SB1022, Classroom Building

FALI Job ID: 1454
Total Samples Submitted: 14
Total Samples Analyzed: 14

Date(s) Collected: 04/23/2015

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
01	11635700						
Layer: White Drywall			ND				
Layer: White Woven Material			ND				
Layer: White Skimcoat/Joint Compound			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %) Fibrous Glass (10 %)							
02	11635701						
Layer: White Drywall			ND				
Layer: Yellow Woven Material			ND				
Layer: White Skimcoat/Joint Compound			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %) Fibrous Glass (10 %)							
03	11635702						
Layer: Brown Drywall			ND				
Layer: White Skimcoat/Joint Compound			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %) Fibrous Glass (10 %)							
04	11635703						
Layer: White Drywall			ND				
Layer: White Texture			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %) Fibrous Glass (10 %)							
05	11635704						
Layer: White Drywall			ND				
Layer: White Texture			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %) Fibrous Glass (10 %)							

Client Name: Protech Consulting & Engineers Inc.

Report Number: B204707

Date Printed: 04/27/15

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
06	11635705						
		Layer: Tan Fibrous Material		ND			
		Layer: Paint		ND			
		Layer: Yellow Mastic		ND			
		Total Composite Values of Fibrous Components:	Asbestos (ND)				
		Cellulose (90 %)					
07	11635706						
		Layer: White Non-Fibrous Material		ND			
		Layer: Tan Fibrous Material		ND			
		Layer: Paint		ND			
		Layer: Yellow Mastic		ND			
		Total Composite Values of Fibrous Components:	Asbestos (ND)				
		Cellulose (80 %)					
08	11635707						
		Layer: Beige Fibrous Material		ND			
		Layer: Paint		ND			
		Total Composite Values of Fibrous Components:	Asbestos (ND)				
		Cellulose (35 %) Fibrous Glass (45 %)					
09	11635708						
		Layer: Beige Fibrous Material		ND			
		Layer: Paint		ND			
		Total Composite Values of Fibrous Components:	Asbestos (ND)				
		Cellulose (35 %) Fibrous Glass (45 %)					
10	11635709						
		Layer: Yellow Mastic		ND			
		Total Composite Values of Fibrous Components:	Asbestos (ND)				
11	11635710						
		Layer: Yellow Mastic		ND			
		Total Composite Values of Fibrous Components:	Asbestos (ND)				
12	11635711						
		Layer: Grey Sheet Flooring		ND			
		Layer: Fibrous Backing		ND			
		Layer: Off-White Mastic		ND			
		Total Composite Values of Fibrous Components:	Asbestos (ND)				
		Cellulose (20 %) Fibrous Glass (5 %) Synthetic (10 %)					
13	11635712						
		Layer: Grey Roof Shingle		ND			
		Layer: Black Felt		ND			
		Total Composite Values of Fibrous Components:	Asbestos (ND)				
		Cellulose (30 %) Fibrous Glass (15 %)					

Report Number: B204707

Date Printed: 04/27/15

Client Name: Protech Consulting & Engineers Inc.

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
14	11635713						
Layer: Grey Roof Shingle							ND
Layer: Black Felt							ND
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (30 %)	Fibrous Glass (15 %)						



Tad Thrower, Laboratory Supervisor, Hayward Laboratory

Note: Limit of Quantification ('LOQ') = 1%. 'Trace' denotes the presence of asbestos below the LOQ. 'ND' = 'None Detected'.

Analytical results and reports are generated by Forensic Analytical Laboratories Inc. (FALI) at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by FALI to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by FALI. The client is solely responsible for the use and interpretation of test results and reports requested from FALI. Forensic Analytical Laboratories Inc. is not able to assess the degree of hazard resulting from materials analyzed. FALI reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.



1208 Main Street, Redwood City, CA 94063
 Phone: (650) 569-4020 Fax: (650) 569-4023
 info@protech-cal.com

Page 1 of 1
 Job # 338-MAIS
 P.O. # 423 338-14

CONSULTING & ENGINEERING

Environmental Services

General Information

Date: 04-23-15
 Job ID: Santa Cruz Roundtree
SB1022
Classroom Bldg.
 Collected By: EAD
 Lab: FASII

Analysis Requested

- PCM NIOSH 7400
- TEM
- AHERA
- Level 2
- Bulk Quantitative
- Bulk Qualitative
- PLM BULK - EPA/600/R/116
- Lead
- AA
- TTLC
- STLC
- TCLP
- Mold
- Other

Turn Around Time

- Rush
- 12 hours
- 24 hours
- 48 hours
- 3-5 days

Special Instructions


Prior Positive

Filter Type: MCE, 0.8 µm, 25mm MCE, 0.45µm, 25mm MCE, 0.8µm, 37mm Other

Sample # Date	Sample Type	Sample Protocol	Location / Activity / Material Description	Time On/Off	LPM	Total Min. Total Vol. Fibers/Fields	Results
# 01-03 04-05	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	D.W. T. Text.	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 06-07 08-09	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Parels w/ mastic 2x4 C-Pad	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 10-11 12	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Mastic S.F.	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 13-14	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	C.S. Roof	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
#	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.		on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
#	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.		on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
#	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.		on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
#	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.		on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		

CHAIN OF CUSTODY

Relinquished By:	Date/Time	Received By:	Date/Time
<u>[Signature]</u>		<u>[Signature]</u>	APR 24 2015



WHITE - RETAIN WITH SAMPLES

CANARY - FILE COPY



Bulk Asbestos Analysis

(EPA Method 600/R-93-116, Visual Area Estimation)

Protech Consulting & Engineers Inc.
Project Manager

1208 Main St.
Redwood City, CA 94063

Client ID: 1454
Report Number: B204703
Date Received: 04/24/15
Date Analyzed: 04/27/15
Date Printed: 04/27/15
First Reported: 04/27/15

Job ID/Site: 338-MA15, 423-338-29 - Santa Cruz Roundtree SB1022, Ancillary Bldg.

FALI Job ID: 1454
Total Samples Submitted: 29
Total Samples Analyzed: 29

Date(s) Collected: 04/23/2015

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
01	11635652						
Layer: White Drywall							ND
Layer: White Skimcoat/Joint Compound							ND
Layer: White Tape							ND
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %) Fibrous Glass (10 %)							
02	11635653						
Layer: White Drywall							ND
Layer: White Skimcoat/Joint Compound							ND
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %) Fibrous Glass (10 %)							
03	11635654						
Layer: White Drywall							ND
Layer: White Skimcoat/Joint Compound							ND
Layer: White Tape							ND
Layer: White Skimcoat/Joint Compound							ND
Layer: Paint							ND
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %) Fibrous Glass (10 %)							
04	11635655						
Layer: Beige Fibrous Material							ND
Layer: Yellow Mastic							ND
Layer: White Non-Fibrous Material							ND
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %) Fibrous Glass (45 %)							
05	11635656						
Layer: Yellow Mastic							ND
Layer: Tan Fibrous Material							ND
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (50 %)							
06	11635657						
Layer: Grey Mastic							ND
Total Composite Values of Fibrous Components:		Asbestos (ND)					

Report Number: B204703

Date Printed: 04/27/15

Client Name: Protech Consulting & Engineers Inc.

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
07	11635658						
		Layer: Grey Non-Fibrous Material			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
08	11635659						
		Layer: White Foam			ND		
		Layer: White Non-Fibrous Material			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
09	11635660						
		Layer: White Drywall			ND		
		Layer: White Skimcoat/Joint Compound			ND		
		Layer: White Tape			ND		
		Layer: White Skimcoat/Joint Compound			ND		
		Layer: Paint			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %) Fibrous Glass (10 %)					
10	11635661						
		Layer: Brown Drywall			ND		
		Layer: White Skimcoat/Joint Compound			ND		
		Layer: White Tape			ND		
		Layer: White Skimcoat/Joint Compound			ND		
		Layer: Paint			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %) Fibrous Glass (10 %)					
11	11635662						
		Layer: White Drywall			ND		
		Layer: White Skimcoat/Joint Compound			ND		
		Layer: White Tape			ND		
		Layer: White Skimcoat/Joint Compound			ND		
		Layer: Paint			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %) Fibrous Glass (10 %)					
12	11635663						
		Layer: Beige Fibrous Material			ND		
		Layer: Paint			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (45 %) Fibrous Glass (35 %)					
13	11635664						
		Layer: Beige Fibrous Material			ND		
		Layer: Paint			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (45 %) Fibrous Glass (35 %)					

Report Number: B204703

Date Printed: 04/27/15

Client Name: Protech Consulting & Engineers Inc.

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
14	11635665						
15	11635666						
16	11635667						
17	11635668						
18	11635669						
19	11635670						
20	11635671						
21	11635672						

Report Number: B204703

Date Printed: 04/27/15

Client Name: Protech Consulting & Engineers Inc.

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
22	11635673						
		Layer: Yellow Fibrous Material		ND			
		Layer: Foil		ND			
		Layer: White Fibrous Material		ND			
		Layer: Foil		ND			
		Layer: White Fibrous Material		ND			
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (15 %) Fibrous Glass (75 %)					
23	11635674						
		Layer: Grey Semi-Fibrous Material		ND			
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %)					
24	11635675						
		Layer: Grey Semi-Fibrous Material		ND			
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %)					
25	11635676						
		Layer: Grey Semi-Fibrous Material		ND			
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %)					
26	11635677						
		Layer: Grey Semi-Fibrous Material		ND			
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %)					
27	11635678						
		Layer: Grey Semi-Fibrous Material		ND			
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %)					
28	11635679						
		Layer: White Mastic		ND			
		Layer: Blue Tile		ND			
		Layer: Yellow Mastic		ND			
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (Trace)					
29	11635680						
		Layer: Grey Cementitious Material		ND			
		Layer: Paint		ND			
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (Trace)					

Client Name: Protech Consulting & Engineers Inc.

Report Number: B204703

Date Printed: 04/27/15

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
-----------	------------	---------------	------------------	---------------	------------------	---------------	------------------



Tad Thrower, Laboratory Supervisor, Hayward Laboratory

Note: Limit of Quantification ('LOQ') = 1%. 'Trace' denotes the presence of asbestos below the LOQ. 'ND' = 'None Detected'.

Analytical results and reports are generated by Forensic Analytical Laboratories Inc. (FALI) at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by FALI to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by FALI. The client is solely responsible for the use and interpretation of test results and reports requested from FALI. Forensic Analytical Laboratories Inc. is not able to assess the degree of hazard resulting from materials analyzed. FALI reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.

General Information

Date: 04-23-15
 Job ID: Santa Cruz Roundtree
SB1022
Ancillary Bldg.
 Collected By: FAST
 Lab: FAST

Analysis Requested

- PCM NIOSH 7400
- TEM
- AHERA
- Level 2
- Bulk Quantitative
- Bulk Qualitative
- PLM BULK - EPA/600/R/116
- Lead
- AA
- TTLC
- STLC
- TCLP
- Mold
- Other

Turn Around Time

- Rush
- 12 hours
- 24 hours
- 48 hours
- 3-5 days

Special Instructions


Prior Positive

Filter Type: MCE, 0.8 µm, 25mm MCE, 0.45µm, 25mm MCE, 0.8µm, 37mm Other

Sample # Date	Sample Type	Sample Protocol	Location / Activity / Material Description	Time On/Off	LPM	Total Vol. Total Vol. Fibers/Fields	Results
# 01-03 04	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	D.W. 2x4 C.P.	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 05 06	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	w. P. Mastic Mastic	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 07 08	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Epoxy Insulation	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 09-11 12-13	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	D.W. 2x4 Gily Panel	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 14 15	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	B.B. Mastic	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 16 17-18	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	12X12 VFT w/m. Mastic	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 19-20 21-22	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Chulk. Jacket	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 23-27 28	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Fireproofing 12X12 VFT w/m	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 29	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Stucco	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		

CHAIN OF CUSTODY

Relinquished By: <u>[Signature]</u>	Date/Time	Received By: <u>[Signature]</u>	Date/Time
			<u>APR 24 2015</u>





1208 MAIN STREET, REDWOOD CITY, CA 94063
 P: (650) 569-4020 • F: (650) 569-4023 • E: info@protech-cal.com

ASBESTOS & LEAD (PB) REPORT

PARTIAL PRE-DEMO/RENOVATION SURVEY & EVALUATION

DATE: June 4, 2015 **PROJECT NO.:** 338-MA15

REQUESTED BY: Moss & Associates
 (CLIENT) 100 Wonsan Drive
 Ocean Side, California 92058

PROJECT: Santa Cruz Rountree SB1022
 90 Roundtree Lane
 Watsonville, California

PROJECT DESCRIPTION: Minimum Security Jail Modification

SERVICE AREA(S):

1. X-building (Minimum Security Building) including:
 - Wing A Renovation
 - Wing B Renovation
 - Wing C Demolition
 - Wing D Renovation
2. Ancillary Building (Medium Security Building): limited to parts of the building labeled as "areas of work" on Attachment A(7) of the bid set.
3. Classroom Building (Scheduled for demolition)

On April 22, 2015 **ProTech Consulting & Engineering, Inc.** performed a building survey to identify asbestos-containing materials (ACM) and presence of Lead based paint (Pb) at the subject project. The survey was conducted in an effort to comply with pre-demolition/renovation regulatory requirements.

Environmental consulting services were conducted by ProTech's licensed and accredited staff as follows:

CONSULTANT	DISCIPLINE	ISSUING AGENCY	CERTIFICATION NO.
Glen Koutz	Asbestos Lead	Cal OSHA CDPH	11-4830 2204
Emanuel Dounias	Asbestos Lead	Cal OSHA CDPH	00-2766 13059

SERVICES REQUESTED BY CLIENT

Asbestos Survey

Consulting services were limited by the client to the following scope of services:

- Performed a visual survey of the project to identify, document, and assess suspect asbestos-containing materials (ACM).
- Collected representative samples to confirm or rebut the presence of ACM.
- Submitted necessary samples to a certified laboratory for analysis by standard polarized light microscopy (PLM) to determine asbestos content.
- Assess the friability and abatement classification of identified ACM;
- Prepared this written report presenting an evaluation and assessment of the data.

ProTech is only responsible for the specific scope of work as stated. No other services are intended or implied.

LBP Survey

- Performed a visual survey of the project to identify, document, and assess suspect lead-based paint (LBP).
- Tested painted/coated surfaces using a calibrated X-ray fluorescence analyzer (XRF).
- Collected representative confirmational paint chip samples to confirm or rebut the presence of lead. Submitted paint chip samples to a certified laboratory for analysis.
- Prepared this written report presenting an evaluation and assessment of the data.

RESULTS & REGULATORY ASSESSMENT

Asbestos types are abbreviated as follows: Chr = Chrysotile; Amo = Amosite; Cro = Crocidolite; Tre = Tremolite; Act = Actinolite.

<i>Confirmed Less Than 1% Asbestos Materials</i>							
MATERIAL DESCRIPTION	MATERIAL, SYSTEM, LOCATION	SMPL NOS.	APPROX. QUANT.	LAB RESULT	REGULATORY ASSESSMENT		
					CAL OSHA	EPA/AQMD	
X-Bldg.							
1. White drywall, joint tape and compound	Some walls and ceilings in various areas throughout most walls and ceilings with concrete and wood	01*, 02, 03, 04*, 05*, 06, 07	Approximately 12,000 sq ft.	Confirmed <1% Chr	Class II Abatement	Non-Friable	
2. Brown/gray window glazing	Exterior windows	32*, 33*, 34, 35	3500 ln ft.	Confirmed <1% Chr	Class II Abatement	Non-Friable	

* No asbestos detected in sample

Non-Asbestos Materials

No asbestos was detected in the following materials.

MATERIAL DESCRIPTION	MATERIAL LOCATION(S)	SAMPLE NUMBERS
X-Bldg.		
1. Yellow carpet mastic	Probation office	08
2 Yellow carpet mastic	Officers office	09
3 Smooth 1 x 1 ceiling tiles with brown mastic	Upper module area	10
4 Perforated 1 x 1 ceiling tile with tan mastic	Lower module area	11
5 Gray concrete pad	Upper module floor	12
6 Gray ceramic tile mortar	Kitchen splash and urinal area	13, 14
7 Brown cementitious coating	On concrete and CMU in the exterior maintenance closet, kitchen slop sink and the shower toilet area.	15, 16, 17, 18
8 Brown baseboard mastic	Dom, recreation room/library area, module	19, 20, 21
9 Interior window glazing	Interior partition walls for class and wood panels	22, 23, 24, 25, 26
10 Yellow wall panel mastic	Exterior restrooms	27
11 Brown Window caulking	Exterior rough openings of windows	28, 29, 30, 31
12 White pipe jacket	Hot water pipes throughout	36, 37
13 White take jacket	Hot water heater tank in mechanical room	38
14 Gray roof caulking	Flashing and penetrations	39, 40
15 Gray roof mastic	Small out patches throughout	41, 42
16 Brown composite shingle roof	Main roof field	43, 44, 45, 46, 47
Ancillary Building		
17 Drywall, joint tape and compound	Most walls in kitchen area	01, 02, 03
18 Smooth 2 x 4 ceiling panels	Kitchen dish wash area	04
19 Yellow wall panel mastic	Kitchen dish wash area	05
20 Gray HVAC joint mastic	Above ceiling on ducts	06
21 Gray epoxy floor	Kitchen area	07
22 White tank insulation(foam)	Mechanical room	08
23 Drywall, joint tape and compound	Most some ceiling reception office area	09, 10, 11
24 2 x 4 ceiling panels	Most ceilings reception office area	12, 13
25 Tan baseboard mastic	Most walls reception office area	14
26 White 12 x 12 vinyl floor tile with yellow mastic	Storage closet and copy room	15
27 Gray sheet flooring	Restroom	16
28 Yellow carpet mastic	Office and hall	17, 18
29 Gray concrete caulking	At seams and all rough openings	19, 20
30 White pipe jacket	most water pipes	21, 22
31 Gray monocoat fireproofing	Throughout above ceiling areas	23, 24, 25, 26, 27,
32 Green 12 x 12 vinyl floor tile with yellow mastic	Housing corridor	28
33 Stucco	Exterior south soffit	29
Classroom building		
34 Drywall, joint tape and compound	Walls of center build outs	01, 02, 03
35 Topping texture	Storeroom and office	04, 05
36 Fibrous wall panels with mastic	Classrooms	06, 07
37 2 x 4 ceiling panels	Throughout	08, 09
38 Yellow carpet mastic	Throughout most	10, 11
39 Gray pebble pattern sheet flooring	Kitchenette and restroom	12
40 Gray composite shingle roof	Roof field	13, 14

ACM Note: Conflicting Laboratory Results

The EPA has a specific protocol for sampling suspect asbestos building materials. In general, it recommends collecting multiple samples (often a minimum of three) of each suspect asbestos material. Multiple samples are recommended by the EPA to increase the statistical reliability of the results and to minimize the potential for field or laboratory error.

Sometimes, multiple samples representing a particular material will yield both positive and negative results. When this happens, the negative sample result(s) are superseded by the positive results. **Once a single positive sample is identified, the material represented by the sampling is treated as an asbestos-containing material.**

However, if additional sampling data, as-built plans, or other reliable data can adequately explain or confirm that area(s) that tested positive are different (not homogeneous) from areas that tested negative, this information can be used to more accurately quantify ACM and define the scope of an asbestos abatement job.

LEAD

Painted/coated surfaces were tested in the field using an X-Ray fluorescence (XRF) spectrum analyzer and/or sampled (paint chips) and submitted to a certified laboratory for analysis by atomic absorption spectroscopy (AAS). Lead paint samples fell in to 1 of 3 types - as follows:

Types of Lead Materials		
LEAD TYPES	DEFINITION	LEAD CONTENT STANDARD
LBP	Lead-based paint (or material)	By XRF: 1 mg/cm ² or greater By Paint Chip: 0.5 weight % or 5,000 mg/kg (at or above)
LCM	Lead containing material (or paint)	By XRF: <1 mg/cm ² By Paint Chip: Below 0.5 wt % of 5,000 mg/kg
ND	No lead detected	By XRF: Requires paint chip confirmation By Paint Chip: No lead Detected or <0.006 wt %

Lead-Based Paint (LBP) – By XRF

XRF READINGS	• 14 (fourteen) XRF readings tested positive for lead-based paint/coating (see XRF report).	
SUMMARY OF LBP COMPONENTS	INTERIOR COMPONENTS	X Building: metal door components, Vinyl window components (Interior build outs and perimeter walls) Ancillary Building: Metal door components, Metal/concrete bumper posts, metal pantry cage, Structure Steel (beams, columns, etc)
	EXTERIOR COMPONENTS	X Building: Vinyl window components, metal railings Classroom building: Metal railings

Lead-Containing Material (LCM) – By XRF

XRF READINGS	• 34 (thirty-four) XRF readings tested positive for low levels of lead (see XRF) report.	
SUMMARY OF LCM COMPONENTS	INTERIOR COMPONENTS	• SEE XRF REPORT
	EXTERIOR COMPONENTS	• SEE XRF REPORT

Non-Lead – By XRF

XRF READINGS

• **70 (seventy)** XRF readings tested negative (no lead detected) for the presence of lead (see XRF report). (Note: Cal OSAH does not accept XRF to prove "non-lead" – paint-chip lab analysis is required)

Paint-Chip – By Laboratory Analysis

Representative paint-chip samples were collected to confirm (or rebut) the presence of lead in materials the showed very low (or no) lead content by XRF analysis.

COMPONENT TYPE/DESCRIPTION	SUBSTRATE	SAMPLE NO(S)	RESULTS WT%	TYPE
X-Building				
1 Gray concrete paint in weight room area- 150 sq ft loose and peeling paint	Concrete	LP-01	<0.006	ND
2 White drywall paint	Drywall	LP-02	<0.006	ND
3 Gray wood wall paint	Wood	LP-03	<0.006	ND
4 Blue wood door paint	Wood	LP-04	<0.006	ND
Ancillary Building				
5 Gray drywall paint	Drywall	LP-05	<0.006	ND
6 Interior white concrete paint	Concrete	LP-06	<0.006	ND
7 Exterior white concrete paint	Concrete	LP-07	<0.006	ND
Classroom Building				
8 Exterior blue wood deck/railing paint	Deck	LP-08	<0.006	ND
9 Exterior brown wood siding paint	Wood	LP-09	<0.006	ND

ASBESTOS REGULATORY NOTES

Cal OSHA (DOSH)

Asbestos-Containing Material (ACM): A material is an asbestos containing material (ACM) when the sample aggregate or any one of its layers (analyzed individually) contains greater than 1% asbestos. Cal OSHA does **not** allow composite analysis (mixing layers of materials together).

Less than 1% Asbestos: Materials containing less than 1% asbestos are not regulated by most governmental agencies. However, Cal OSHA is not one of those agencies. The Cal OSHA asbestos standard must be followed for work involving materials that contain a concentration of asbestos as low as **0.1%**.

If a material can be shown to contain less than 1% asbestos by PLM point count (or other approved method), it can be treated as an asbestos-containing construction material (ACCM). ACCM is a term Cal OSHA uses to describe materials containing **less than 1%** (but greater than 0.1%) asbestos. In certain situations, there may be some economic advantages to making this characterization. The decision to do so is evaluated on a case-by-case basis at the client's request.

Less than 0.1% Asbestos: If a material can be shown to contain less than **0.1%** asbestos by an approved method, it can be treated as a non-asbestos material. In certain situations, there may be

some economic advantages to making this characterization. The decision to do so is evaluated on a case-by-case basis at the client's request.

Class I Asbestos Work: Cal OSHA prescribes specific work practices involving the removal of asbestos-containing insulation and surfacing (i.e. sprayed-on) materials.

Class II Asbestos Work: Cal OSHA prescribes specific work practices involving the removal of ACM which is not insulation or surfacing material. This includes, but is not limited to, the removal of asbestos-containing wallboard, floor tile and sheeting, roofing, cement products, and construction mastics.

EPA/AQMD

Asbestos-Containing Material (ACM): Any building material which contains commercial asbestos in an amount greater than 1%.

Less than 1% Asbestos: Materials that are found to contain less than 1% asbestos by standard polarized light microscopy (PLM) may be considered non-asbestos (by EPA/AQMD) if confirmation analysis is performed. To be treated as a non-asbestos material, the EPA and AQMD require analytical verification by PLM Point Count (or better). This verification is required because the standard PLM analysis is not sensitive enough to accurately determine asbestos content at or below 1%. In certain situations, there may be some cost advantages to making this characterization. The decision to do so is evaluated on a case-by-case basis at the client's request.

Regulated Asbestos-Containing Material (RACM): RACM includes friable (easily crumbled) ACM, or Category I nonfriable ACM that has or will become friable or that has been subjected to sanding, drilling, grinding, cutting, or abrading, or Category II nonfriable ACM that may become or has become crumbled, pulverized, or reduced to powder.

Friable: Materials that can be crumbled, pulverized, or reduced to powder, when dry, by hand pressure.

Non-Friable: Materials that **cannot** be easily crumbled, pulverized, or reduced to powder, when dry, by hand pressure. Non-friable materials are categorized by EPA/AQMD as follows:

- **Category I Nonfriable ACM:** Asbestos-containing packings, gaskets, resilient floor coverings, mastics and asphalt roofing products.
- **Category II Nonfriable ACM:** Asbestos-containing material, excluding Category I nonfriable asbestos-containing material, that, when dry, and in its present form, cannot be crumbled, pulverized, or reduced to powder by hand pressure.

LEAD REGULATORY NOTES

Lead-Based Paint (LBP)

MATERIAL DESCRIPTION		REGULATORY ASSESSMENT GOVERNING REGULATIONS
1.	Lead-based paint components (LBP)	<ul style="list-style-type: none"> • Cal OSHA standards apply if LBP will be disturbed by employees/workers • CDPH standards apply if lead "abatement" is performed • DTSC requires characterization of waste and proper disposal • US EPA standards apply if LBP is disturbed in a children occupied site
2.	Lead containing materials (LCM)	<ul style="list-style-type: none"> • Cal OSHA standards apply if LCM will be disturbed by employees • CDPH standards apply if worker exposure standards are exceeded • DTSC requires characterization of waste and proper disposal
3.	No Lead Detected by XRF	<ul style="list-style-type: none"> • Cal OSHA standards apply unless paint chip laboratory analysis confirms non-lead
4.	No Lead Detected by Paint-chip	<ul style="list-style-type: none"> • No regulations apply

Regulatory Assessment Notes

California Occupational Safety & Health Administration (Cal OSHA):

- Regulates any detectable amount of lead (does not have to be LBP) when trigger tasks are performed
- Requires worker training
- Regulates employee safety during lead-related work
- Enforces proper work practices
- Requires notification when 100 sq ft (or more) of LBP is disturbed.

California Department of Public Health (CDPH):

- Regulates "abatement" of Lead-based paint
- Requires *accredited* training for workers and supervisors
- Provides certification of workers and supervisors performing abatement
- Mandates lead abatement be performed in accordance with US HUD guidelines
- Defines "abatement" as an action performed for the purpose and intent of reducing or eliminating a lead "hazard"
- Requires notification when abatement is performed

California Department of Toxic Substance Control (DTSC):

- Regulates disposal of lead waste
- Requires testing of waste stream to characterize hazard level

US Environmental Protection Agency (US EPA):

- Regulates Lead-based paint in child occupied facilities
- Regulates work involving the disturbance of as little as 6 sq ft of interior & 20 sq ft exterior LBP
- Requires *accredited* training for workers and supervisors
- Requires certification of companies performing LBP work
- Mandates minimal work practices

LEAD DISCUSSION

Lead-Based Paint & Lead Containing Materials

Lead-based paint (LBP) is defined as a material/coating/paint which contains a lead content at or in excess of 5,000 parts per million (PPM), 0.5% by weight, or 1 mg/cm² (by XRF). Materials containing a lead content below these levels are not considered LBP and are not considered a hazard by most regulatory agencies. However, the dust from materials containing low levels of lead can produce a lead hazard if enough lead dust accumulates.

Cal OSHA Trigger Tasks

Cal OSHA defines lead paint at the Consumer Product Safety Commission's (CPAC) level of 600 ppm for non-trigger tasks. However, Cal OSHA regulates **any detectable amount of lead** when trigger tasks are conducted.

The following table lists the Cal OSHA trigger tasks, presumed exposure and the type of respiratory protection that is required while performing those tasks:

CAL OSHA TRIGGER TASK	PRESUMED EXPOSURE	REQUIRED RESPIRATORY PROTECTION
<ul style="list-style-type: none">• Manual demolition• Manual scraping and sanding• Heat gun use• Use of power tools with dust collection systems• Spray painting with lead paint• Any other activity that the employer has any reason to believe that an employee may be exposed in excess of the PEL.	50-100 $\mu\text{m}/\text{m}^3$	Half-mask, air purifying
<ul style="list-style-type: none">• Using lead containing mortar• Lead burning• Rivet busting• Power tool cleaning without dust collection system• Clean-up of dry abrasive blast residue.	500-2500 $\mu\text{m}/\text{m}^3$	Full-face, air purifying, or Tight fitting PAPR, or Supplied air, contiguous flow
<ul style="list-style-type: none">• Abrasive blasting• Welding• Cutting• Torch burning.	>2500 $\mu\text{m}/\text{m}^3$	Supplied air, pressure demand

SURVEY & REPORT LIMITATIONS

- Scope of work limitations were established by the Client to include items of interest and concern to the Client. *ProTech* is only responsible for the specific scope of work performed. No other services are intended or implied.
- This report has been prepared for the exclusive use of *ProTech*'s client and is not intended for use by any other party. The scope of work and results presented in this report may not be appropriate for uses by any other party. Any use by a third party of this report shall be at their own risk and shall constitute a release and an agreement to defend and indemnify *ProTech* from any and all liability in connection therewith whether arising out of *ProTech*'s negligence or otherwise.
- This project may contain undiscovered asbestos in areas that were not accessible or identified during *ProTech*'s survey. Suspect asbestos may be discovered during demolition, renovation, or maintenance. If suspect asbestos is discovered, stop all work that could impact asbestos to allow properly trained personnel to perform sampling and or removal.
- This report and its evaluations/conclusions are based on the current condition of the project. This report does not assess or anticipate future events that may impact or damage asbestos materials. Future changes in the condition of asbestos materials will require a new assessment by a certified asbestos consultant/technician.
- The quantities of asbestos stated in this report are approximations. This report is not a work plan or project specification. Contractors should not rely on this document for bidding purposes.
- Reasonable efforts were made to examine below **carpeted areas and resilient floor coverings** to determine and quantify the presence of suspect asbestos materials. *ProTech* accepts no liability for additional materials or under-reporting of asbestos materials which exist below other floor coverings.
- **Glass fiber insulated mechanical systems** were inspected as completely as possibly without destroying the integrity of the glass fiber insulation. The condition and presence or absence of asbestos associated with mechanical systems is assumed to be consistent with those areas exposed and examined during our inspection. However, *ProTech* does not guarantee that this is the case.
- *ProTech* does not represent this **limited survey** as a comprehensive inspection or evaluation. *ProTech* recommends that an expanded, comprehensive asbestos survey be conducted at this site if renovation or demolition activities are expected to impact any building materials other than those specifically addressed in this report.

- Because this survey was conducted in an **occupied building**, intrusive inspection methods were limited. Specific care and caution were observed to:
 1. Avoid significant aesthetic impact to architectural finishes.
 2. Avoid disturbing tenants and patrons.
 3. Avoid disturbing tenant spaces.

SURVEY APPROACH

Inspection & Sample Collection

ProTech performed a survey of the project to identify and document accessible suspect asbestos. Identified suspect asbestos materials categorized by homogenous area and sampled. Samples were collected by misting small areas with water, then cutting or scraping the sample from the substrate with an appropriate sampling tool. Whenever possible, samples were collected from areas previously damaged or deteriorating. No building systems, components, or structures were demolished to obtain samples of potentially hidden ACM.

Each suspect bulk sample was sealed in its own Zip-lock plastic container and labeled with a unique identification number. Sampling tools were individually cleaned before and after each sample was collected to avoid sample cross contamination. Decontamination was accomplished using single-use, pre-moistened cloths.

Sample information was recorded on ProTech's chain-of-custody form. This form accompanied the samples to a laboratory possessing accreditation from the National Voluntary Laboratory Accreditation Program (NVLAP). Samples were submitted to Forensic Analytical Services, Inc. of Hayward, California.

Sample Analysis

Bulk sample analysis was conducted in accordance with the EPA interim method for determination of asbestos in bulk materials. Samples were first examined by a stereoscopic microscope for determination of homogeneity and preliminary evaluation of composition and presence of fibers. Fibers observed during this examination were then mounted in various refractive index oils and examined in polarized light. During this examination, all minerals and/or man-made materials were identified and the percentages of each were estimated and/or counted.

Evaluation of Asbestos-Containing Materials

In evaluating each asbestos material, the adhesion of the asbestos material to the underlying substrate, deterioration, and damage from vandalism or any other cause was assessed. Evidence of debris on horizontal surfaces, hanging material, dislodged chunks, scraping, indentations, cracking, etc. would be indicators of poor material condition.

Accidental or deliberate physical contact with asbestos materials can result in damage. Inspectors looked for any evidence that asbestos-containing materials had been disturbed. Indicators such as: finger marks in the material, graffiti, pieces dislodged or missing, scraping marks from movable equipment, or furniture, or an accumulation of suspect asbestos dust or debris on floors, shelves, or other horizontal surfaces indicate poor material condition.

Asbestos-containing materials may deteriorate as a result of either the quality of the installation or environmental factors which affect the cohesive strength of the asbestos-containing material or the strength of the adhesion to the substrate. Deterioration can result in an accumulation of dust on the surface of the asbestos-containing material, delamination of the material, or an adhesive failure of the material where it pulls away from the substrate and either hangs loosely or falls to the floor and exposes the substrate. Inspectors touch the asbestos-containing material to determine if dust is released when the material is lightly brushed or rubbed.

CONCLUSIONS & RECOMMENDATIONS

Asbestos Removal

ACM should be removed prior to activity that may disturb it. Prior to ACM disturbance/removal, the following should be performed:

	Task	Task Description	Fee
1.	Prepare Project Specification	Prepare a written scope of work & instructions to bidders (site plans not included).	\$800.00 - \$1,200.00
2.	Bid Review and Contractor Selection	Select qualified contractors (prospective bidders), review bids and award contract.	\$680.00
3.	Project Monitoring & Oversight	Monitoring asbestos abatement work and document contractor compliance.	Pricing upon request
4.	Project Clearance	Perform final inspection and collect air samples to certify work area clearance.	Pricing upon request

LEAD

- Cal OSHA worker protection rules, CDPH certification requirements, US EPA standards, and DTSC disposal requirements need to be assessed by each contractor/employer who performs work on this project.
- Contractors, whose employees work at this site, are required to assess if their work will be subject to the requirements of the Cal OSHA lead construction standard (CCR Title 8 § 1532). Cal OSHA standards are designed to regulate and enforce on-the-job worker safety. Employers are required by law to ensure that employees are not exposed to airborne lead levels which exceed the permissible exposure limit (PEL). The standard requires worker exposure monitoring, medical surveillance, training, special work practices, etc.

- Each contractor/employer who bids and/or performs work at the site will need to assess potential lead exposure to employees performing their particular scope of work. Contractors who perform work at this site may need to obtain additional data (beyond the data presented in this report) during their assessment and Cal OSHA compliance planning. Individual contractors/sub-contractors should be allowed access to the project to obtain any needed data (samples, consultation, etc.) to complete their employee exposure assessment.
- ProTech recommends that the building owner and/or general contractor disseminate this report as well as any other lead-related information to all prospective contractors bidding work at the subject site.
- Contractors, whose employees disturb more than 100 sq ft of lead-based paint (LBP), are required to submit written notification to Cal OSHA (per Health and Safety Code, Title 17 CCR Section 36000 (c)). The Cal OSHA LBP notification rule requires 24-hour advance notice prior to LBP disturbance.
- Any work performed at the site where LBP or LCP is likely to be disturbed should be performed by a contractor trained and qualified to perform lead-related construction work. Any work that exceeds Cal OSHA's permissible exposure limit or is performed to remediate a lead hazard must be conducted by CDPH certified personnel. All lead related work should be conducted employing lead work practices in accordance with HUD guidelines.

LEGEND

HOW TO READ THE REPORT

Wall A, is the front wall of the building.

Walls B, C and D go clockwise around the building or room

REPORTS

Summary-- Gives only those readings at or above the action level of 1.0mg/cm².

Detailed Report— Gives all reading by room and component.

Readings are not in numerical order. This report also gives comments

PAINT CONDITION

I=Intact

F=Fair

P=Poor

Comments

There were 124 readings taken, including calibrations, using the RMD XRF instrument. 14 of the readings registered at or above the action level of 1.0mg/cm². A contractor practicing Lead Safe Practices should do any repairs or repainting of the actionable areas.

“ A copy of this summary report must be provided to new lessees and purchasers of this property under Federal Law (24 CFR part 35 and 40 CFR part 745) before they become obligated under lease or sales contract. The complete report must also be provided to new purchasers and it must be made available to new tenants. Landlords and sellers are also required to distribute an educational pamphlet and include standard warning language in their leases or sales contracts to ensure that parents have the information they need to protect their children from lead-based paint hazards.”

Emanuel Dounias
DPH 13095

Date

LEAD PAINT INSPECTION REPORT

REPORT NUMBER: S#01369 - 04/22/15 12:26

INSPECTION FOR: Moss & Associates
100 Wonsan Drive.
Ocean Side, CA

PERFORMED AT: Santa Cruz Roundtree SB10022
90 Roundtree Lane
Watsonville, CA
Limited Areas

INSPECTION DATE: 04/22/15

INSTRUMENT TYPE: R M D
MODEL LPA-1
XRF TYPE ANALYZER
Serial Number: 01369

ACTION LEVEL: 1.0 mg/cm**2

OPERATOR LICENSE: California General

STATEMENT: Lead paint survey as agreed.
No representations are made for any areas not tested.

SIGNED _____ DATE _____
ProTech Consulting & Engineering
1208 Main Street
Redwood City, Ca. 94063
Phone: 650-569-4020
Fax: 650-569-4023

SEQUENTIAL REPORT OF LEAD PAINT INSPECTION FOR: Moss & Associates

Inspection Date: 04/22/15 Santa Cruz Roundtree SB10022
 Report Date: 4/29/2015 90 Roundtree Lane
 Abatement Level: 1.0 Watsonville, CA
 Report No. S#01369 - 04/22/15 12:26 Limited Areas
 Total Readings: 124
 Job Started: 04/22/15 12:26
 Job Finished: 04/23/15 18:05

Read No.	Room Rm	Room Name	Wall Structure	Location	Member	Paint Cond	Substrate	Paint Color	Lead (mg/cm ²)	Mode
1		CALIBRATION							0.9	TC
2		CALIBRATION							0.9	TC
3		CALIBRATION							1.0	TC
4	001	X Module	A Wall	L Ctr		I Wood		White	0.0	QM
5	001	X Module	B Wall	L Ctr		I Wood		White	0.2	QM
6	001	X Module	D Wall	L Ctr		I Drywall		White	0.0	QM
7	001	X Module	B Window		Ctr Rgt casing	I Wood		Blue	0.2	QM
8	001	X Module	A Door		Ctr Rgt casing	I Wood		Blue	0.1	QM
9	001	X Module	A Window		Ctr Rgt casing	I Wood		Brown	0.0	QM
10	001	X Module	B Wall	L Lft		I Wood		Blue	0.0	QM
11	002	X Dorm	A Beam		Ctr	I Wood		Black	0.0	QM
12	002	X Dorm	A Beam		Ctr	I Wood		Brown	0.0	QM
13	002	X Dorm	A Wall	L Ctr		I Concrete		White	0.0	QM
14	002	X Dorm	C Wall	U Ctr		I Concrete		White	0.3	QM
15	002	X Dorm	B Door		Rgt U Ctr	I Metal		Blue	0.3	QM
16	002	X Dorm	B Door		Rgt Rgt casing	I Metal		Blue	1.0	QM
17	003	X Wash Area	C Door		Rgt Rgt casing	I Metal		Blue	1.0	QM
18	003	X Wash Area	C Door		Rgt U Ctr	I Metal		Blue	0.0	QM
19	003	X Wash Area	D Wall	L Ctr		I Concrete		White	-0.1	QM
20	003	X Wash Area	A Wall	L Ctr		I Concrete		White	0.0	QM
21	003	X Wash Area	B Wall	L Ctr		I Concrete		White	-0.2	QM
22	003	X Wash Area	B Wall	L Rgt		I Ceramic		White	-0.1	QM
23	003	X Wash Area	A Floor			I Concrete		Gray	-0.1	QM
24	003	X Wash Area	B Window		Rgt Sash	I Vinyl		Blue	4.9	QM
25	003	X Wash Area	B Beam		Rgt	I Wood		Black	0.1	QM
26	003	X Wash Area	B Beam		Rgt	I Wood		Brown	0.0	QM
27	004	X Din. Area	C Beam		Rgt	I Wood		Brown	0.0	QM
28	004	X Din. Area	C Beam		Rgt	I Wood		Black	0.0	QM
29	004	X Din. Area	B Wall	U Rgt		I Concrete		White	0.0	QM
30	004	X Din. Area	D Chair rail		Ctr	I Concrete		White	0.0	QM
31	004	X Din. Area	C Floor			I Concrete		Gray	-0.1	QM
32	004	X Din. Area	B Wall	L Rgt		I Ceramic		Tan	-0.1	QM
33	004	X Din. Area	C Wall	U Ctr		I Drywall		White	0.0	QM
34	004	X Din. Area	C Ceiling			I Wood		White	0.1	QM
35	004	X Din. Area	D Door		Ctr U Ctr	I Wood		Blue	0.1	QM
36	004	X Din. Area	C Window		Ctr Sash	I Vinyl		Blue	4.9	QM
37	004	X Din. Area	B Window		Ctr Rgt casing	I Vinyl		Blue	5.7	QM
38	004	X Din. Area	C Window		Ctr Rgt casing	I Vinyl		Blue	3.8	QM
39	004	X Din. Area	B Window		Ctr Rgt casing	I Vinyl		Blue	6.3	QM
40	004	X Din. Area	B Window		Ctr Apron	I Wood		Blue	0.0	QM
41	004	X Din. Area	B Door		Lft Header	I Wood		Blue	0.0	QM
42	004	X Din. Area	B Beam		Lft	I Wood		Black	0.0	QM
43	004	X Din. Area	B Beam		Lft	I Wood		Brown	0.0	QM
44	004	X Din. Area	B Bench		Lft	I Wood		Brown	0.0	QM
45	004	X Din. Area	D Wall	L Ctr		I Drywall		White	0.0	QM
46	004	X Din. Area	B Wall	L Ctr		I Drywall		White	0.0	QM
47	004	X Din. Area	D Wall	U Rgt		I Concrete		Blue	0.0	QM
48	004	X Din. Area	B Wall	U Rgt		I Concrete		White	-0.1	QM
49	004	X Din. Area	B Door		Lft U Ctr	I Metal		Blue	0.1	QM
50	001	X Bldg Ext	A Beam		Rgt	I Wood		Brown	0.0	QM
51	001	X Bldg Ext	A Soffit			I Wood		Brown	0.1	QM

52	001 X Bldg Ext	A	Fascia			I Metal	Brown	0.1	QM
53	001 X Bldg Ext	A	Wall	U Lft		I Wood	Blue	0.1	QM
54	001 X Bldg Ext	D	Beam	Ctr		I Wood	Brown	0.0	QM
55	001 X Bldg Ext	D	Soffit			I Wood	Brown	0.1	QM
56	001 X Bldg Ext	C	Door	Lft U Ctr		I Metal	Blue	0.0	QM
57	001 X Bldg Ext	C	Window	Ctr Rgt casing		I Vinyl	Brown	3.0	QM
58	001 X Bldg Ext	C	Railing	Lft Railing		I Wood	Brown	0.0	QM
59	001 X Bldg Ext	D	Door	Lft U Ctr		I Metal	Blue	0.3	QM
60	001 X Bldg Ext	C	Railing	Ctr Railing		I Metal	Yellow	4.6	QM
61	001 X Bldg Ext	C	Dock	Ctr		I Concrete	Yellow	0.0	QM
62	001 X Bldg Ext	C	Rollup Door	Ctr		I Metal	Blue	0.0	QM
63	001 X Bldg Ext	B	Beam	Rgt		I Wood	Brown	0.0	QM
64	005 Ans. Kitch	B	Wall	L Ctr		I Concrete	Gray	0.1	QM
65	005 Ans. Kitch	C	Wall	L Ctr		I Concrete	Gray	-0.1	QM
66	005 Ans. Kitch	C	Cage	Ctr		I Metal	Gray	1.0	QM
67	005 Ans. Kitch	B	Post	Rgt		I Metal	Gray	1.0	QM
68	005 Ans. Kitch	B	Door	Rgt U Ctr		I Metal	Green	0.2	QM
69	005 Ans. Kitch	B	Door	Rgt Lft casing		I Metal	Green	0.3	QM
70	005 Ans. Kitch	B	Door	Ctr U Ctr		I Metal	Blue	1.0	QM
71	005 Ans. Kitch	B	Door	Ctr Lft casing		I Metal	Blue	0.3	QM
72	005 Ans. Kitch	D	Window	Ctr Rgt casing		I Metal	Green	0.0	QM
73	005 Ans. Kitch	D	Window	Ctr Rgt casing		I Metal	Blue	-0.1	QM
74	005 Ans. Kitch	B	Wall	L Lft		I Drywall	Gray	0.3	QM
75	005 Ans. Kitch	C	Beam	Ctr		I Metal	Red	2.1	QM
76	006 Ans. Office	D	Wall	L Rgt		I Concrete	Tan	0.0	QM
77	006 Ans. Office	A	Wall	L Ctr		I Concrete	Gray	-0.2	QM
78	006 Ans. Office	B	Wall	L Lft		I Drywall	Gray	0.0	QM
79	006 Ans. Office	D	Wall	L Ctr		I Drywall	Gray	0.0	QM
80	006 Ans. Office	D	Wall	U Rgt		I Drywall	Tan	0.0	QM
81	006 Ans. Office	C	Wall	L Rgt		I Concrete	Green	0.0	QM
82	006 Ans. Office	C	Door	Rgt U Ctr		I Wood	Beige	0.0	QM
83	006 Ans. Office	C	Door	Rgt Rgt casing		I Metal	Beige	0.2	QM
84	006 Ans. Office	D	Window	Rgt Rgt casing		I Wood	White	0.0	QM
85	002 Ans. Ext	A	Wall	L Rgt		I Concrete	White	0.0	QM
86	002 Ans. Ext	A	Wall	L Ctr		I Concrete	White	0.0	QM
87	002 Ans. Ext	A	Window	Ctr Rgt casing		I Vinyl	Blue	0.0	QM
88	002 Ans. Ext	B	Window	Ctr Rgt casing		I Vinyl	Blue	0.0	QM
89	002 Ans. Ext	B	Door	Lft U Ctr		I Metal	Blue	0.2	QM
90	002 Ans. Ext	B	Door	Lft Rgt jamb		I Metal	Blue	0.1	QM
91	002 Ans. Ext	B	Post	Ctr		I Metal	White	0.2	QM
92	002 Ans. Ext	B	Wall	L Rgt		I Concrete	White	-0.1	QM
93	002 Ans. Ext	B	Wall	L Lft		I Concrete	White	-0.1	QM
94	002 Ans. Ext	B	Soffit			I Stucco	White	0.1	QM
95	008 Number Only	C	Wall	U Ctr		I Drywall	White	0.0	QM
96	008 Number Only	A	Wall	L Ctr		I Drywall	White	0.0	QM
97	008 Number Only	A	Wall	U Ctr		I Drywall	White	0.0	QM
98	008 Number Only	C	Shelves	Ctr		I Wood	White	0.1	QM
99	008 Number Only	C	Cabinet	Ctr		I Wood	White	0.0	QM
100	008 Number Only	A	Window	Lft Sill		I Wood	White	0.0	QM
101	008 Number Only	B	Window	Ctr Sill		I Wood	White	-0.1	QM
102	008 Number Only	B	Door	Ctr U Ctr		I Wood	White	0.0	QM
103	008 Number Only	B	Door	Rgt Rgt casing		I Wood	White	0.1	QM
104	008 Number Only	A	Door	Rgt Rgt casing		I Wood	White	0.3	QM
105	008 Number Only	A	Door	Rgt U Ctr		I Metal	White	0.0	QM
106	003 Classrm Ext	A	Door	Ctr U Ctr		I Metal	Blue	0.6	QM
107	003 Classrm Ext	A	Door	Ctr Rgt casing		I Wood	Blue	0.0	QM
108	003 Classrm Ext	A	Deck	Ctr		I Wood	Blue	0.0	QM
109	003 Classrm Ext	A	Railing	Ctr Railing		I Wood	Blue	0.0	QM
110	003 Classrm Ext	A	Column	Ctr U column		I Wood	Blue	0.1	QM
111	003 Classrm Ext	A	Railing	Ctr Railing		I Metal	Blue	1.0	QM
112	003 Classrm Ext	A	Down Spout	Ctr		I Metal	Brown	0.3	QM
113	003 Classrm Ext	A	Pipe	Ctr		I Metal	Brown	0.3	QM
114	003 Classrm Ext	A	Gutter			I Metal	Blue	0.6	QM
115	003 Classrm Ext	A	Soffit			I Wood	Brown	0.3	QM
116	003 Classrm Ext	A	Fascia			I Wood	Brown	0.0	QM

117	003	Classrm Ext	A	Wall	L	Ctr	I	Wood	Brown	0.0	QM
118	003	Classrm Ext	D	Wall	L	Ctr	I	Wood	Brown	0.1	QM
119	003	Classrm Ext	C	Wall	L	Ctr	I	Wood	Brown	0.0	QM
120	003	Classrm Ext	D	Window		Ctr Rgt casing	I	Wood	Blue	0.0	QM
121	003	Classrm Ext	C	Foundation		Ctr	I	Concrete	Brown	0.0	QM
122		CALIBRATION								0.8	TC
123		CALIBRATION								1.0	TC
124		CALIBRATION								1.0	TC

---- End of Readings ----

SUMMARY REPORT OF LEAD PAINT INSPECTION FOR: Moss & Associates

Inspection Date: 04/22/15 Santa Cruz Roundtree SB10022
 Report Date: 4/29/2015 90 Roundtree Lane
 Abatement Level: 1.0 Watsonville, CA
 Report No. S#01369 - 04/22/15 12:26 Limited Areas
 Total Readings: 124 Actionable: 14
 Job Started: 04/22/15 12:26
 Job Finished: 04/23/15 18:05

Read No.	Wall	Structure	Location	Member	Paint Cond	Substrate	Paint Color	Lead (mg/cm ²)	Mode
Exterior Room 001 X Bldg Ext									
057	C	Window	Ctr	Rgt casing	I	Vinyl	Brown	3.0	QM
060	C	Railing	Ctr	Railing	I	Metal	Yellow	4.6	QM
Exterior Room 003 Classrm Ext									
111	A	Railing	Ctr	Railing	I	Metal	Blue	1.0	QM
Interior Room 002 X Dorm									
016	B	Door	Rgt	Rgt casing	I	Metal	Blue	1.0	QM
Interior Room 003 X Wash Area									
024	B	Window	Rgt	Sash	I	Vinyl	Blue	4.9	QM
017	C	Door	Rgt	Rgt casing	I	Metal	Blue	1.0	QM
Interior Room 004 X Din. Area									
037	B	Window	Ctr	Rgt casing	I	Vinyl	Blue	5.7	QM
039	B	Window	Ctr	Rgt casing	I	Vinyl	Blue	6.3	QM
038	C	Window	Ctr	Rgt casing	I	Vinyl	Blue	3.8	QM
036	C	Window	Ctr	Sash	I	Vinyl	Blue	4.9	QM
Interior Room 005 Ans. Kitch									
070	B	Door	Ctr	U Ctr	I	Metal	Blue	1.0	QM
067	B	Post	Rgt		I	Metal	Gray	1.0	QM
066	C	Cage	Ctr		I	Metal	Gray	1.0	QM
075	C	Beam	Ctr		I	Metal	Red	2.1	QM

Calibration Readings

---- End of Readings ----

DETAILED REPORT OF LEAD PAINT INSPECTION FOR: Moss & Associates

Inspection Date: 04/22/15 Santa Cruz Roundtree SB10022
 Report Date: 4/29/2015 90 Roundtree Lane
 Abatement Level: 1.0 Watsonville, CA
 Report No. S#01369 - 04/22/15 12:26 Limited Areas
 Total Readings: 124
 Job Started: 04/22/15 12:26
 Job Finished: 04/23/15 18:05

Read No.	Wall	Structure	Location	Member	Paint Cond	Substrate	Paint Color	Lead (mg/cm ²)	Mode
Exterior Room 001 X Bldg Ext									
053	A	Wall	U Lft		I	Wood	Blue	0.1	QM
052	A	Fascia			I	Metal	Brown	0.1	QM
051	A	Soffit			I	Wood	Brown	0.1	QM
050	A	Beam	Rgt		I	Wood	Brown	0.0	QM
063	B	Beam	Rgt		I	Wood	Brown	0.0	QM
057	C	Window	Ctr	Rgt casing	I	Vinyl	Brown	3.0	QM
056	C	Door	Lft	U Ctr	I	Metal	Blue	0.0	QM
058	C	Railing	Lft	Railing	I	Wood	Brown	0.0	QM
060	C	Railing	Ctr	Railing	I	Metal	Yellow	4.6	QM
061	C	Dock	Ctr		I	Concrete	Yellow	0.0	QM
062	C	Rollup Door	Ctr		I	Metal	Blue	0.0	QM
055	D	Soffit			I	Wood	Brown	0.1	QM
059	D	Door	Lft	U Ctr	I	Metal	Blue	0.3	QM
054	D	Beam	Ctr		I	Wood	Brown	0.0	QM
Exterior Room 002 Ans. Ext									
086	A	Wall	L Ctr		I	Concrete	White	0.0	QM
085	A	Wall	L Rgt		I	Concrete	White	0.0	QM
087	A	Window	Ctr	Rgt casing	I	Vinyl	Blue	0.0	QM
093	B	Wall	L Lft		I	Concrete	White	-0.1	QM
092	B	Wall	L Rgt		I	Concrete	White	-0.1	QM
094	B	Soffit			I	Stucco	White	0.1	QM
088	B	Window	Ctr	Rgt casing	I	Vinyl	Blue	0.0	QM
090	B	Door	Lft	Rgt jamb	I	Metal	Blue	0.1	QM
089	B	Door	Lft	U Ctr	I	Metal	Blue	0.2	QM
091	B	Post	Ctr		I	Metal	White	0.2	QM
Exterior Room 003 Classrm Ext									
117	A	Wall	L Ctr		I	Wood	Brown	0.0	QM
116	A	Fascia			I	Wood	Brown	0.0	QM
114	A	Gutter			I	Metal	Blue	0.6	QM
115	A	Soffit			I	Wood	Brown	0.3	QM
107	A	Door	Ctr	Rgt casing	I	Wood	Blue	0.0	QM
106	A	Door	Ctr	U Ctr	I	Metal	Blue	0.6	QM
109	A	Railing	Ctr	Railing	I	Wood	Blue	0.0	QM
111	A	Railing	Ctr	Railing	I	Metal	Blue	1.0	QM
110	A	Column	Ctr	U column	I	Wood	Blue	0.1	QM
108	A	Deck	Ctr		I	Wood	Blue	0.0	QM
112	A	Down Spout	Ctr		I	Metal	Brown	0.3	QM
113	A	Pipe	Ctr		I	Metal	Brown	0.3	QM
119	C	Wall	L Ctr		I	Wood	Brown	0.0	QM
121	C	Foundation	Ctr		I	Concrete	Brown	0.0	QM
118	D	Wall	L Ctr		I	Wood	Brown	0.1	QM
120	D	Window	Ctr	Rgt casing	I	Wood	Blue	0.0	QM
Interior Room 001 X Module									
004	A	Wall	L Ctr		I	Wood	White	0.0	QM
009	A	Window	Ctr	Rgt casing	I	Wood	Brown	0.0	QM
008	A	Door	Ctr	Rgt casing	I	Wood	Blue	0.1	QM
010	B	Wall	L Lft		I	Wood	Blue	0.0	QM

005	B	Wall	L Ctr		I	Wood	White	0.2	QM
007	B	Window	Ctr	Rgt casing	I	Wood	Blue	0.2	QM
006	D	Wall	L Ctr		I	Drywall	White	0.0	QM

Interior Room 002 X Dorm

013	A	Wall	L Ctr		I	Concrete	White	0.0	QM
011	A	Beam	Ctr		I	Wood	Black	0.0	QM
012	A	Beam	Ctr		I	Wood	Brown	0.0	QM
016	B	Door	Rgt	Rgt casing	I	Metal	Blue	1.0	QM
015	B	Door	Rgt	U Ctr	I	Metal	Blue	0.3	QM
014	C	Wall	U Ctr		I	Concrete	White	0.3	QM

Interior Room 003 X Wash Area

020	A	Wall	L Ctr		I	Concrete	White	0.0	QM
023	A	Floor			I	Concrete	Gray	-0.1	QM
021	B	Wall	L Ctr		I	Concrete	White	-0.2	QM
022	B	Wall	L Rgt		I	Ceramic	White	-0.1	QM
024	B	Window	Rgt	Sash	I	Vinyl	Blue	4.9	QM
025	B	Beam	Rgt		I	Wood	Black	0.1	QM
026	B	Beam	Rgt		I	Wood	Brown	0.0	QM
017	C	Door	Rgt	Rgt casing	I	Metal	Blue	1.0	QM
018	C	Door	Rgt	U Ctr	I	Metal	Blue	0.0	QM
019	D	Wall	L Ctr		I	Concrete	White	-0.1	QM

Interior Room 004 X Din. Area

046	B	Wall	L Ctr		I	Drywall	White	0.0	QM
032	B	Wall	L Rgt		I	Ceramic	Tan	-0.1	QM
029	B	Wall	U Rgt		I	Concrete	White	0.0	QM
048	B	Wall	U Rgt		I	Concrete	White	-0.1	QM
037	B	Window	Ctr	Rgt casing	I	Vinyl	Blue	5.7	QM
039	B	Window	Ctr	Rgt casing	I	Vinyl	Blue	6.3	QM
040	B	Window	Ctr	Apron	I	Wood	Blue	0.0	QM
041	B	Door	Lft	Header	I	Wood	Blue	0.0	QM
049	B	Door	Lft	U Ctr	I	Metal	Blue	0.1	QM
042	B	Beam	Lft		I	Wood	Black	0.0	QM
043	B	Beam	Lft		I	Wood	Brown	0.0	QM
044	B	Bench	Lft		I	Wood	Brown	0.0	QM
033	C	Wall	U Ctr		I	Drywall	White	0.0	QM
031	C	Floor			I	Concrete	Gray	-0.1	QM
034	C	Ceiling			I	Wood	White	0.1	QM
038	C	Window	Ctr	Rgt casing	I	Vinyl	Blue	3.8	QM
036	C	Window	Ctr	Sash	I	Vinyl	Blue	4.9	QM
027	C	Beam	Rgt		I	Wood	Brown	0.0	QM
028	C	Beam	Rgt		I	Wood	Black	0.0	QM
045	D	Wall	L Ctr		I	Drywall	White	0.0	QM
047	D	Wall	U Rgt		I	Concrete	Blue	0.0	QM
030	D	Chair rail	Ctr		I	Concrete	White	0.0	QM
035	D	Door	Ctr	U Ctr	I	Wood	Blue	0.1	QM

Interior Room 005 Ans. Kitch

074	B	Wall	L Lft		I	Drywall	Gray	0.3	QM
064	B	Wall	L Ctr		I	Concrete	Gray	0.1	QM
071	B	Door	Ctr	Lft casing	I	Metal	Blue	0.3	QM
070	B	Door	Ctr	U Ctr	I	Metal	Blue	1.0	QM
069	B	Door	Rgt	Lft casing	I	Metal	Green	0.3	QM
068	B	Door	Rgt	U Ctr	I	Metal	Green	0.2	QM
067	B	Post	Rgt		I	Metal	Gray	1.0	QM
065	C	Wall	L Ctr		I	Concrete	Gray	-0.1	QM
066	C	Cage	Ctr		I	Metal	Gray	1.0	QM
075	C	Beam	Ctr		I	Metal	Red	2.1	QM
072	D	Window	Ctr	Rgt casing	I	Metal	Green	0.0	QM
073	D	Window	Ctr	Rgt casing	I	Metal	Blue	-0.1	QM

Interior Room 006 Ans. Office

077	A	Wall	L Ctr		I	Concrete	Gray	-0.2	QM
-----	---	------	-------	--	---	----------	------	------	----

078	B	Wall	L Lft		I	Drywall	Gray	0.0	QM
081	C	Wall	L Rgt		I	Concrete	Green	0.0	QM
083	C	Door	Rgt	Rgt casing	I	Metal	Beige	0.2	QM
082	C	Door	Rgt	U Ctr	I	Wood	Beige	0.0	QM
079	D	Wall	L Ctr		I	Drywall	Gray	0.0	QM
076	D	Wall	L Rgt		I	Concrete	Tan	0.0	QM
080	D	Wall	U Rgt		I	Drywall	Tan	0.0	QM
084	D	Window	Rgt	Rgt casing	I	Wood	White	0.0	QM

Interior Room 008 Number Only

096	A	Wall	L Ctr		I	Drywall	White	0.0	QM
097	A	Wall	U Ctr		I	Drywall	White	0.0	QM
100	A	Window	Lft	Sill	I	Wood	White	0.0	QM
104	A	Door	Rgt	Rgt casing	I	Wood	White	0.3	QM
105	A	Door	Rgt	U Ctr	I	Metal	White	0.0	QM
101	B	Window	Ctr	Sill	I	Wood	White	-0.1	QM
103	B	Door	Ctr	Rgt casing	I	Wood	White	0.1	QM
102	B	Door	Ctr	U Ctr	I	Wood	White	0.0	QM
095	C	Wall	U Ctr		I	Drywall	White	0.0	QM
098	C	Shelves	Ctr		I	Wood	White	0.1	QM
099	C	Cabinet	Ctr		I	Wood	White	0.0	QM

Calibration Readings

001								0.9	TC
002								0.9	TC
003								1.0	TC
122								0.8	TC
123								1.0	TC
124								1.0	TC

---- End of Readings ----

DISTRIBUTION REPORT OF LEAD PAINT INSPECTION FOR: Moss & Associates

Inspection Date: 04/22/15 Santa Cruz Roundtree SB10022
 Report Date: 4/29/2015 90 Roundtree Lane
 Abatement Level: 1.0 Watsonville, CA
 Report No. S#01369 - 04/22/15 12:26 Limited Areas
 Total Reading Sets: 118
 Job Started: 04/22/15 12:26
 Job Finished: 04/23/15 18:05

Structure	Total	Structure Distribution		
		Positive	Negative	Inconclusive
Beam	12	1 <8%>	11 <92%>	0 <0%>
Bench	1	0 <0%>	1 <100%>	0 <0%>
Cabinet	1	0 <0%>	1 <100%>	0 <0%>
Cage	1	1 <100%>	0 <0%>	0 <0%>
Ceiling	1	0 <0%>	1 <100%>	0 <0%>
Chair rail	1	0 <0%>	1 <100%>	0 <0%>
Column U column	1	0 <0%>	1 <100%>	0 <0%>
Deck	1	0 <0%>	1 <100%>	0 <0%>
Dock	1	0 <0%>	1 <100%>	0 <0%>
Door Header	1	0 <0%>	1 <100%>	0 <0%>
Door Lft casing	2	0 <0%>	2 <100%>	0 <0%>
Door Rgt casing	7	2 <29%>	5 <71%>	0 <0%>
Door Rgt jamb	1	0 <0%>	1 <100%>	0 <0%>
Door U Ctr	13	1 <8%>	12 <92%>	0 <0%>
Down Spout	1	0 <0%>	1 <100%>	0 <0%>
Fascia	2	0 <0%>	2 <100%>	0 <0%>
Floor	2	0 <0%>	2 <100%>	0 <0%>
Foundation	1	0 <0%>	1 <100%>	0 <0%>
Gutter	1	0 <0%>	1 <100%>	0 <0%>
Pipe	1	0 <0%>	1 <100%>	0 <0%>
Post	2	1 <50%>	1 <50%>	0 <0%>
Railing Railing	4	2 <50%>	2 <50%>	0 <0%>
Rollup Door	1	0 <0%>	1 <100%>	0 <0%>
Shelves	1	0 <0%>	1 <100%>	0 <0%>
Soffit	4	0 <0%>	4 <100%>	0 <0%>
Wall	37	0 <0%>	37 <100%>	0 <0%>
Window Apron	1	0 <0%>	1 <100%>	0 <0%>
Window Rgt casing	12	4 <33%>	8 <67%>	0 <0%>
Window Sash	2	2 <100%>	0 <0%>	0 <0%>
Window Sill	2	0 <0%>	2 <100%>	0 <0%>
Inspection Totals:	118	14 <12%>	104 <88%>	0 <0%>



Bulk Asbestos Point Count Analysis

(NESHAP Final Rule, 40 CFR, Part 61)

Protech Consulting & Engineers Inc.
Project Manager

1208 Main St.
Redwood City, CA 94063

Client ID: 1454
Report Number: N007153
Date Received: 04/24/15
Date Analyzed: 05/19/15
Date Printed: 05/19/15

Job ID/Site: 338-MA15, 423-338-47 - Santa Cruz Roundtree SB1022, X Building

FALI Job ID: 1454
Total Samples Submitted: 6
Total Samples Analyzed: 6

PLM Report Number: B204709

Sample Preparation and Analysis:

The NESHAP Final Rule does not define the preparation method for multi-layered samples. In order to determine the composite quantity of asbestos, the volume percent of each layer is determined, the asbestos containing layers are analyzed by point counting and the composite quantity of asbestos is calculated. The NESHAP Final Rule can not be applied to matrices that dissolve in refractive index liquid. This includes tar, mastic or adhesive typically found on the back of floor tiles. According to the NESHAP Final Rule, point count data is only necessary when the visual estimate of asbestos is below 10%.

Sample ID	Lab Number	Layer Description
02	11635715	Composite of ALL Layers White Drywall Off-White Skimcoat/Joint Compound Paint

Point Count Results:

Number of asbestos points counted: 0
Number of non-empty points: 400
Layer percentage of entire sample: 100
Percent asbestos in layer: < 1

Asbestos type(s) detected: Chrysotile

Comment: Asbestos was detected but no points were counted due to counting criteria. Therefore quantitation deemed to be < 1%.

03	11635716	Composite of ALL Layers White Drywall White Skimcoat/Joint Compound White Tape Off-White Skimcoat/Joint Compound Paint
----	----------	---

Point Count Results:

Number of asbestos points counted: 0
Number of non-empty points: 400
Layer percentage of entire sample: 100
Percent asbestos in layer: < 1

Asbestos type(s) detected: Chrysotile

Comment: Asbestos was detected but no points were counted due to counting criteria. Therefore quantitation deemed to be < 1%.



Bulk Asbestos Point Count Analysis

(NESHAP Final Rule, 40 CFR, Part 61)

Protech Consulting & Engineers Inc.
Project Manager

1208 Main St.
Redwood City, CA 94063

Client ID: 1454
Report Number: N007153
Date Received: 04/24/15
Date Analyzed: 05/19/15
Date Printed: 05/19/15

Job ID/Site: 338-MA15, 423-338-47 - Santa Cruz Roundtree SB1022, X Building

FALI Job ID: 1454
Total Samples Submitted: 6
Total Samples Analyzed: 6

PLM Report Number: B204709

Sample Preparation and Analysis:

The NESHAP Final Rule does not define the preparation method for multi-layered samples. In order to determine the composite quantity of asbestos, the volume percent of each layer is determined, the asbestos containing layers are analyzed by point counting and the composite quantity of asbestos is calculated. The NESHAP Final Rule can not be applied to matrices that dissolve in refractive index liquid. This includes tar, mastic or adhesive typically found on the back of floor tiles. According to the NESHAP Final Rule, point count data is only necessary when the visual estimate of asbestos is below 10%.

Sample ID	Lab Number	Layer Description
06	11635719	Composite of ALL Layers White Drywall White Skimcoat/Joint Compound White Tape Off-White Skimcoat/Joint Compound Paint

Point Count Results:

Number of asbestos points counted: 0
 Number of non-empty points: 400
 Layer percentage of entire sample: 100
Percent asbestos in layer: < 1

Asbestos type(s) detected: Chrysotile

Comment: Asbestos was detected but no points were counted due to counting criteria. Therefore quantitation deemed to be < 1%.

07	11635720	Composite of ALL Layers White Drywall Off-White Skimcoat/Joint Compound Paint
----	----------	---

Point Count Results:

Number of asbestos points counted: 0
 Number of non-empty points: 400
 Layer percentage of entire sample: 100
Percent asbestos in layer: < 1

Asbestos type(s) detected: Chrysotile

Comment: Asbestos was detected but no points were counted due to counting criteria. Therefore quantitation deemed to be < 1%.



Bulk Asbestos Point Count Analysis

(NESHAP Final Rule, 40 CFR, Part 61)

Protech Consulting & Engineers Inc.
Project Manager

1208 Main St.
Redwood City, CA 94063

Client ID: 1454
Report Number: N007153
Date Received: 04/24/15
Date Analyzed: 05/19/15
Date Printed: 05/19/15

Job ID/Site: 338-MA15, 423-338-47 - Santa Cruz Roundtree SB1022, X Building

FALI Job ID: 1454
Total Samples Submitted: 6
Total Samples Analyzed: 6

PLM Report Number: B204709

Sample Preparation and Analysis:

The NESHAP Final Rule does not define the preparation method for multi-layered samples. In order to determine the composite quantity of asbestos, the volume percent of each layer is determined, the asbestos containing layers are analyzed by point counting and the composite quantity of asbestos is calculated. The NESHAP Final Rule can not be applied to matrices that dissolve in refractive index liquid. This includes tar, mastic or adhesive typically found on the back of floor tiles. According to the NESHAP Final Rule, point count data is only necessary when the visual estimate of asbestos is below 10%.

Sample ID	Lab Number	Layer Description
34	11635747	Brown Non-Fibrous Material
<i>Point Count Results:</i>		
Number of asbestos points counted: 2		
Number of non-empty points: 400		
Layer percentage of entire sample: 100		
Percent asbestos in layer: < 1		
Asbestos type(s) detected: Chrysotile		
Comment:		
35	11635748	Brown Non-Fibrous Material
<i>Point Count Results:</i>		
Number of asbestos points counted: 1		
Number of non-empty points: 400		
Layer percentage of entire sample: 15		
Percent asbestos in layer: < 1		
Asbestos type(s) detected: Chrysotile		
Comment:		

Note: Point count results are reported to the nearest percent per EPA method.

Tad Thrower, Laboratory Supervisor, Hayward Laboratory

Note: Limit of Quantification (LOQ) = 1%. Trace denotes the presence of asbestos below the LOQ. ND = None Detected.

Analytical results and reports are generated by Forensic Analytical Laboratories Inc. (FALI) at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by FALI to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by FALI. The client is solely responsible for the use and interpretation of test results and reports requested from FALI. Forensic Analytical Laboratories Inc. is not able to assess the degree of hazard resulting from materials analyzed. FALI reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.



1206 Main Street, Redwood City, CA 94063
 Phone: (650) 569-1020 Fax: (650) 569 4023
 info@protech-cal.com

Page 1 of 1
 Job # 338-MAIS
 P.O. # 423-338-47

Consulting & Engineers

Environmental Services

General Information

Date: 04-23-15
 Job ID: Scate Cruz Roundtree
SBI022
X-Building
 Collected By: ED
 Lab: FAST

Analysis Requested

- PCM NIOSH 7400
- TEM
- AHERA
- Level 2
- Bulk Quantitative
- Bulk Qualitative
- PLM BULK - EPA/800/R116
- Lead
- AA
- TTLC
- STLC
- TCLP
- Mold
- Other

Turn Around Time

- Rush
- 12 hours
- 24 hours
- 48 hours
- 3-5 days

Special Instructions


Prior Positive

Filter Type: MCE, 0.8 µm, 25mm MCE, 0.45µm, 25mm MCE, 0.8µm, 37mm Other

Sample # Date	Sample Type	Sample Protocol	Location / Activity / Material Description	Time On/Off	LPM	Total Min. Total Vol. Fibers/Fields	Results
# 01-07 08-09	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	D.W. Mastic	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 10-11 12	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	IXI CT w/mastic Concrete	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 13-14 15-18	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Mortar Coating	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 19-21 22-26	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Mastic Glazing	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 27 28-31	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Mastic Caulk	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 32-35 36-37	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Glazing Jacket	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 38 39-40	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Caulk	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 41-42 43-47	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Mastic Roofing	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
#	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.		on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		

CHAIN OF CUSTODY

Relinquished By: <u>ED</u>	Date/Time	Received By: <u>[Signature]</u>	RECEIVED Date/Time <u>APR 24 2015</u>
----------------------------	-----------	---------------------------------	---





Metals Analysis of Paints

Protech Consulting & Engineers Inc.
Project Manager

1208 Main St.
Redwood City, CA 94063

Client ID: 1454
Report Number: M160416
Date Received: 04/24/15
Date Analyzed: 04/27/15
Date Printed: 04/27/15
First Reported: 04/27/15

Job ID / Site: 338-MA15, 423-338-09 - Santa Cruz Roundtree SB1022, Paints
Date(s) Collected: 4/23/15

FALI Job ID: 1454
Total Samples Submitted: 9
Total Samples Analyzed: 9

Sample Number	Lab Number	Analyte	Result	Result Units	Reporting Limit*	Method Reference
LP-01	30711151	Pb	< 0.006	wt%	0.006	EPA 3050B/7420
LP-02	30711152	Pb	< 0.006	wt%	0.006	EPA 3050B/7420
LP-03	30711153	Pb	< 0.006	wt%	0.006	EPA 3050B/7420
LP-04	30711154	Pb	< 0.006	wt%	0.006	EPA 3050B/7420
LP-05	30711155	Pb	< 0.006	wt%	0.006	EPA 3050B/7420
LP-06	30711156	Pb	< 0.006	wt%	0.006	EPA 3050B/7420
LP-07	30711157	Pb	< 0.006	wt%	0.006	EPA 3050B/7420
LP-08	30711158	Pb	< 0.006	wt%	0.006	EPA 3050B/7420
LP-09	30711159	Pb	< 0.006	wt%	0.006	EPA 3050B/7420

* The Reporting Limit represents the lowest amount of analyte that the laboratory can confidently detect in the sample, and is not a regulatory level. The Units for the Reporting Limit are the same as the Units for the Final Results.

Daniele Siu

Daniele Siu, Laboratory Supervisor, Hayward Laboratory

Analytical results and reports are generated by Forensic Analytical at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by Forensic Analytical to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by Forensic Analytical. The client is solely responsible for the use and interpretation of test results and reports requested from Forensic Analytical. Forensic Analytical is not able to assess the degree of hazard resulting from materials analyzed. Forensic Analytical reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. Any modifications that have been made to referenced test methods are documented in Forensic Analytical's Standard Operating Procedures Manual. Sample results have not been blank corrected. Quality control and sample receipt condition were acceptable unless otherwise noted.



1208 Main Street, Redwood City, CA 94063
 Phone: (650) 569-4020 Fax: (650) 569-4023
 info@protech-cal.com

Page 1 of 1
 Job # 338-MAIS
 P.O. # 423-378-09

CONSULTING & ENGINEERING

Environmental Services

General Information

Analysis Requested

Turn Around Time

Special Instructions

Date: 04-23-15
 Job ID: Santa Cruz Rowdtree
SB1022
Paints
 Collected By: EO
 Lab: FA5I

- PCM NIOSH 7400
- TEM
 - AHERA
 - Level 2
 - Bulk Quantitative
 - Bulk Qualitative
- PLM BULK - EPA/600/RV116
- Lead
 - AA
 - TTLC
 - STLC
 - TCLP
- Mold
- Other _____

- Rush
- 12 hours
- 24 hours
- 48 hours
- 3-5 days


Prior Positive

Filter Type: MCE, 0.8 µm, 25mm MCE, 0.45µm, 25mm MCE, 0.8µm, 37mm Other _____

Sample # Date	Sample Type	Sample Protocol	Location / Activity / Material Descriptor	Time On/Off	LPM	Total Min. Total Vol. Fibers/Fields	Results
* LP-01	<input type="checkbox"/> Post Area Background Personal Blank Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	X-Bldg. Gray Concrete Paint 1st weight Room area 150 sq. ft. loose & Red	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
* LP-02	<input type="checkbox"/> Post Area Background Personal Blank Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	White drywall Paint	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
* LP-03	<input type="checkbox"/> Post Area Background Personal Blank Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Gray wood wall Paint	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
* LP-04	<input type="checkbox"/> Post Area Background Personal Blank Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	V Blue wood Door Paint	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
* LP-05	<input type="checkbox"/> Post Area Background Personal Blank Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Ancillary Room Bldg. Gray Drywall Paint	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
* LP-06	<input type="checkbox"/> Post Area Background Personal Blank Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Interior white concrete paint	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
* LP-07	<input type="checkbox"/> Post Area Background Personal Blank Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	V Exterior white concrete paint	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
* LP-08	<input type="checkbox"/> Post Area Background Personal Blank Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Classroom Bldg. Ext. Blue wood Deck/Railing Paint	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
* LP-09	<input type="checkbox"/> Post Area Background Personal Blank Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Ext. Brown wood Siding Paint	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		

CHAIN OF CUSTODY

Relinquished By: <u>EO</u>	Date/Time	Received By: <u>[Signature]</u>	Date/Time: <u>APR 24 2015</u>
----------------------------	-----------	---------------------------------	-------------------------------





Bulk Asbestos Analysis

(EPA Method 600/R-93-116, Visual Area Estimation)

Protech Consulting & Engineers Inc.
Project Manager

1208 Main St.
Redwood City, CA 94063

Client ID: 1454
Report Number: B204709
Date Received: 04/24/15
Date Analyzed: 04/28/15
Date Printed: 04/28/15
First Reported: 04/28/15

Job ID/Site: 338-MA15, 423-338-47 - Santa Cruz Roundtree SB1022, X Building

Date(s) Collected: 04/23/2015

FALI Job ID: 1454
Total Samples Submitted: 47
Total Samples Analyzed: 47

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
01	11635714						
Layer: White Drywall			ND				
Layer: White Skimcoat/Joint Compound			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)	Fibrous Glass (10 %)						
02	11635715						
Layer: White Drywall			ND				
Layer: Off-White Skimcoat/Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (10 %)						
03	11635716						
Layer: White Drywall			ND				
Layer: White Skimcoat/Joint Compound		Chrysotile	2 %				
Layer: White Tape			ND				
Layer: Off-White Skimcoat/Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (10 %)						
04	11635717						
Layer: White Drywall			ND				
Layer: White Skimcoat/Joint Compound			ND				
Layer: White Tape			ND				
Layer: White Skimcoat/Joint Compound			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)	Fibrous Glass (10 %)						
05	11635718						
Layer: White Drywall			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)	Fibrous Glass (10 %)						

Client Name: Protech Consulting & Engineers Inc.

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
06	11635719						
Layer: White Drywall							ND
Layer: White Skimcoat/Joint Compound		Chrysotile	2 %				
Layer: White Tape							ND
Layer: Off-White Skimcoat/Joint Compound		Chrysotile	2 %				
Layer: Paint							ND
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %) Fibrous Glass (10 %)							
07	11635720						
Layer: White Drywall							ND
Layer: Off-White Skimcoat/Joint Compound		Chrysotile	2 %				
Layer: Paint							ND
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %) Fibrous Glass (10 %)							
08	11635721						
Layer: Tan Mastic							ND
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
09	11635722						
Layer: Tan Mastic							ND
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
10	11635723						
Layer: Brown Mastic							ND
Layer: Yellow Fibrous Tile							ND
Layer: Paint							ND
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (2 %) Fibrous Glass (90 %)							
11	11635724						
Layer: Tan Mastic							ND
Layer: Tan Fibrous Material							ND
Layer: Paint							ND
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (95 %)							
12	11635725						
Layer: Grey Mortar							ND
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
13	11635726						
Layer: Grey Mortar							ND
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							

Client Name: Protech Consulting & Engineers Inc.

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
23	11635736						
			Layer: Grey Non-Fibrous Material				ND
			Total Composite Values of Fibrous Components:	Asbestos (ND)			
			Cellulose (Trace)				
24	11635737						
			Layer: Grey Non-Fibrous Material				ND
			Total Composite Values of Fibrous Components:	Asbestos (ND)			
			Cellulose (Trace)				
25	11635738						
			Layer: Grey Non-Fibrous Material				ND
			Total Composite Values of Fibrous Components:	Asbestos (ND)			
			Cellulose (Trace)				
26	11635739						
			Layer: Grey Non-Fibrous Material				ND
			Total Composite Values of Fibrous Components:	Asbestos (ND)			
			Cellulose (Trace)				
27	11635740						
			Layer: Yellow Mastic				ND
			Total Composite Values of Fibrous Components:	Asbestos (ND)			
			Cellulose (Trace)				
28	11635741						
			Layer: Dark Brown Non-Fibrous Material				ND
			Total Composite Values of Fibrous Components:	Asbestos (ND)			
			Cellulose (Trace) Fibrous Glass (5 %)				
29	11635742						
			Layer: Dark Brown Non-Fibrous Material				ND
			Total Composite Values of Fibrous Components:	Asbestos (ND)			
			Cellulose (Trace) Fibrous Glass (5 %)				
30	11635743						
			Layer: Dark Brown Non-Fibrous Material				ND
			Total Composite Values of Fibrous Components:	Asbestos (ND)			
			Cellulose (Trace) Fibrous Glass (5 %)				
31	11635744						
			Layer: Dark Brown Non-Fibrous Material				ND
			Total Composite Values of Fibrous Components:	Asbestos (ND)			
			Cellulose (Trace) Fibrous Glass (5 %)				
32	11635745						
			Layer: Brown Non-Fibrous Material				ND
			Layer: Grey Non-Fibrous Material				ND
			Layer: Paint				ND
			Total Composite Values of Fibrous Components:	Asbestos (ND)			
			Cellulose (Trace)				

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
33	11635746						
		Layer: Brown Non-Fibrous Material			ND		
		Layer: Grey Non-Fibrous Material			ND		
		Layer: Paint			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (Trace)					
34	11635747						
		Layer: Brown Non-Fibrous Material		Chrysotile	Trace		
		Total Composite Values of Fibrous Components:		Asbestos (Trace)			
		Cellulose (Trace)					
35	11635748						
		Layer: Brown Non-Fibrous Material		Chrysotile	Trace		
		Layer: Grey Non-Fibrous Material			ND		
		Layer: Paint			ND		
		Total Composite Values of Fibrous Components:		Asbestos (Trace)			
		Cellulose (Trace)					
36	11635749						
		Layer: Yellow Fibrous Material			ND		
		Layer: Tan Woven Material			ND		
		Layer: White Coating			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (75 %) Fibrous Glass (25 %)					
37	11635750						
		Layer: Yellow Fibrous Material			ND		
		Layer: White Woven Material			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (75 %) Fibrous Glass (25 %)					
38	11635751						
		Layer: Yellow Fibrous Material			ND		
		Layer: White Woven Material			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (75 %) Fibrous Glass (25 %)					
39	11635752						
		Layer: Dark Brown Non-Fibrous Material			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (Trace)					
40	11635753						
		Layer: Dark Brown Non-Fibrous Material			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (Trace)					
41	11635754						
		Layer: Black Mastic			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (Trace)					

Client Name: Protech Consulting & Engineers Inc.

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
42	11635755						
		Layer: Black Mastic					ND
		Total Composite Values of Fibrous Components:				Asbestos (ND)	
		Cellulose (Trace)					
43	11635756						
		Layer: Black Roof Shingle					ND
		Layer: Black Roof Shingle					ND
		Layer: Black Felt					ND
		Layer: Black Felt					ND
		Total Composite Values of Fibrous Components:				Asbestos (ND)	
		Cellulose (20 %) Fibrous Glass (35 %)					
		Comment: Bulk complex sample.					
44	11635757						
		Layer: Black Roof Shingle					ND
		Layer: Black Roof Shingle					ND
		Layer: Black Felt					ND
		Layer: Black Felt					ND
		Total Composite Values of Fibrous Components:				Asbestos (ND)	
		Cellulose (20 %) Fibrous Glass (35 %)					
		Comment: Bulk complex sample.					
45	11635758						
		Layer: Black Roof Shingle					ND
		Layer: Black Roof Shingle					ND
		Layer: Black Felt					ND
		Layer: Black Felt					ND
		Total Composite Values of Fibrous Components:				Asbestos (ND)	
		Cellulose (20 %) Fibrous Glass (35 %)					
		Comment: Bulk complex sample.					
46	11635759						
		Layer: Black Roof Shingle					ND
		Layer: Black Roof Shingle					ND
		Layer: Black Felt					ND
		Layer: Black Felt					ND
		Total Composite Values of Fibrous Components:				Asbestos (ND)	
		Cellulose (20 %) Fibrous Glass (35 %)					
		Comment: Bulk complex sample.					
47	11635760						
		Layer: Black Roof Shingle					ND
		Layer: Black Roof Shingle					ND
		Total Composite Values of Fibrous Components:				Asbestos (ND)	
		Cellulose (20 %) Fibrous Glass (35 %)					
		Comment: Bulk complex sample.					

Client Name: Protech Consulting & Engineers Inc.

Report Number: B204709

Date Printed: 04/28/15

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
-----------	------------	---------------	------------------	---------------	------------------	---------------	------------------

Tad Thrower

Tad Thrower, Laboratory Supervisor, Hayward Laboratory

Note: Limit of Quantification ('LOQ') = 1%. 'Trace' denotes the presence of asbestos below the LOQ. 'ND' = 'None Detected'.

Analytical results and reports are generated by Forensic Analytical Laboratories Inc. (FALI) at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by FALI to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by FALI. The client is solely responsible for the use and interpretation of test results and reports requested from FALI. Forensic Analytical Laboratories Inc. is not able to assess the degree of hazard resulting from materials analyzed. FALI reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.

General Information

Date: 04-23-15
Job ID: Scate Cruz Roundtree
SB1022
X- Building
Collected By: EW
Lab: FAST

Analysis Requested

- PCM NIOSH 7400
- TEM
- AHERA
- Level 2
- Bulk Quantitative
- Bulk Qualitative
- PLM BULK - EPA/600/RV116
- Lead
- AA
- TTLC
- STLC
- TCLP
- Mold
- Other _____

Turn Around Time

- Rush
- 12 hours
- 24 hours
- 48 hours
- 3-5 days

Special Instructions


Prior Positive

Filter Type: MCE, 0.8 µm, 25mm MCE, 0.45µm, 25mm MCE, 0.8µm, 37mm Other _____

Sample # Date	Sample Type	Sample Protocol	Location / Activity / Material Description	Time On/Off	LPM	Total Min. Total Vol. Fibers/Fields	Results
# 01-07 08-09	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	D.W. Mastic	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 10-11 12	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	1X1 C.T. w/mastic Concrete	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 13-14 15-18	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Mortar Coating	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 19-21 22-26	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Mastic Glazing	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 27 28-31	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Mastic Caulk	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 32-35 36-37	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Glazing Jacket	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 38 39-40	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	↓ Caulk	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
# 41-42 43-47	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Mastic Roofing	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
#	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.		on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		

CHAIN OF CUSTODY

Relinquished By: <u>EW</u>	Date/Time	Received By: <u>[Signature]</u>	RECEIVED Date/Time <u>APR 24 2015</u>
----------------------------	-----------	---------------------------------	---





Bulk Asbestos Analysis

(EPA Method 600/R-93-116, Visual Area Estimation)

Protech Consulting & Engineers Inc.
Project Manager

1208 Main St.
Redwood City, CA 94063

Client ID: 1454
Report Number: B204707
Date Received: 04/24/15
Date Analyzed: 04/27/15
Date Printed: 04/27/15
First Reported: 04/27/15

Job ID/Site: 338-MA15, 423-338-14 - Santa Cruz Roundtree SB1022, Classroom Building

FALI Job ID: 1454
Total Samples Submitted: 14
Total Samples Analyzed: 14

Date(s) Collected: 04/23/2015

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
01	11635700						
		Layer: White Drywall			ND		
		Layer: White Woven Material			ND		
		Layer: White Skimcoat/Joint Compound			ND		
		Layer: Paint			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %) Fibrous Glass (10 %)					
02	11635701						
		Layer: White Drywall			ND		
		Layer: Yellow Woven Material			ND		
		Layer: White Skimcoat/Joint Compound			ND		
		Layer: Paint			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %) Fibrous Glass (10 %)					
03	11635702						
		Layer: Brown Drywall			ND		
		Layer: White Skimcoat/Joint Compound			ND		
		Layer: Paint			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %) Fibrous Glass (10 %)					
04	11635703						
		Layer: White Drywall			ND		
		Layer: White Texture			ND		
		Layer: Paint			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %) Fibrous Glass (10 %)					
05	11635704						
		Layer: White Drywall			ND		
		Layer: White Texture			ND		
		Layer: Paint			ND		
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %) Fibrous Glass (10 %)					

Client Name: Protech Consulting & Engineers Inc.

Report Number: B204707

Date Printed: 04/27/15

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
06	11635705						
		Layer: Tan Fibrous Material		ND			
		Layer: Paint		ND			
		Layer: Yellow Mastic		ND			
		Total Composite Values of Fibrous Components:	Asbestos (ND)				
		Cellulose (90 %)					
07	11635706						
		Layer: White Non-Fibrous Material		ND			
		Layer: Tan Fibrous Material		ND			
		Layer: Paint		ND			
		Layer: Yellow Mastic		ND			
		Total Composite Values of Fibrous Components:	Asbestos (ND)				
		Cellulose (80 %)					
08	11635707						
		Layer: Beige Fibrous Material		ND			
		Layer: Paint		ND			
		Total Composite Values of Fibrous Components:	Asbestos (ND)				
		Cellulose (35 %) Fibrous Glass (45 %)					
09	11635708						
		Layer: Beige Fibrous Material		ND			
		Layer: Paint		ND			
		Total Composite Values of Fibrous Components:	Asbestos (ND)				
		Cellulose (35 %) Fibrous Glass (45 %)					
10	11635709						
		Layer: Yellow Mastic		ND			
		Total Composite Values of Fibrous Components:	Asbestos (ND)				
11	11635710						
		Layer: Yellow Mastic		ND			
		Total Composite Values of Fibrous Components:	Asbestos (ND)				
12	11635711						
		Layer: Grey Sheet Flooring		ND			
		Layer: Fibrous Backing		ND			
		Layer: Off-White Mastic		ND			
		Total Composite Values of Fibrous Components:	Asbestos (ND)				
		Cellulose (20 %) Fibrous Glass (5 %) Synthetic (10 %)					
13	11635712						
		Layer: Grey Roof Shingle		ND			
		Layer: Black Felt		ND			
		Total Composite Values of Fibrous Components:	Asbestos (ND)				
		Cellulose (30 %) Fibrous Glass (15 %)					

Client Name: Protech Consulting & Engineers Inc.

Report Number: B204707

Date Printed: 04/27/15

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
14	11635713						
Layer: Grey Roof Shingle			ND				
Layer: Black Felt			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (30 %)	Fibrous Glass (15 %)						



Tad Thrower, Laboratory Supervisor, Hayward Laboratory

Note: Limit of Quantification ('LOQ') = 1%. 'Trace' denotes the presence of asbestos below the LOQ. 'ND' = 'None Detected'.

Analytical results and reports are generated by Forensic Analytical Laboratories Inc. (FALI) at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by FALI to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by FALI. The client is solely responsible for the use and interpretation of test results and reports requested from FALI. Forensic Analytical Laboratories Inc. is not able to assess the degree of hazard resulting from materials analyzed. FALI reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.



1208 Main Street, Redwood City, CA 94063
 Phone: (650) 569-4020 Fax: (650) 569-4023
 info@protech-cal.com

Page 1 of 1
 Job # 338-MAIS
 P.O. # 423 338-14

ENVIRONMENTAL SERVICES

General Information

Date: 04-23-15
 Job ID: Santa Cruz Roundtree
SB1022
Classroom Bldg.
 Collected By: EMD
 Lab: FAST

Analysis Requested

- PCM NIOSH 7400
- TEM
 - AHERA
 - Level 2
 - Bulk Quantitative
 - Bulk Qualitative
- PLM BULK - EPA/600/R-116
- Lead
 - AA
 - TTLC
 - STLC
 - TCLP
- Mold
- Other _____

Turn Around Time

- Rush
- 12 hours
- 24 hours
- 48 hours
- 3-5 days
- _____

Special Instructions


Prior Positive

Filter Type: MCE, 0.8 µm, 25mm MCE, 0.45µm, 25mm MCE, 0.8µm, 37mm Other _____

Sample # Date	Sample Type	Sample Protocol	Location / Activity / Material Description	Time On/Off	LPM	Total Min. Total Vol Fibers/Fields	Results
# 01-03	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	D.W.	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
04-05			T.Text.				
# 06-07	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Pavls w/mastic	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
08-09			2x4 C.Pad				
# 10-11	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Mastic	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
12			S.F.				
# 13-14	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	C.S. Roof	on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
#	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.		on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
#	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.		on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
#	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.		on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		
#	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.		on _____ off _____ pump# _____	on _____ end _____ Ave _____ Roto# _____		

CHAIN OF CUSTODY

Relinquished By:	Date/Time	Received By:	Date/Time
<u>[Signature]</u>		<u>[Signature]</u>	APR 24 2015





Bulk Asbestos Analysis

(EPA Method 600/R-93-116, Visual Area Estimation)

Protech Consulting & Engineers Inc.
Project Manager

1208 Main St.
Redwood City, CA 94063

Client ID: 1454
Report Number: B204703
Date Received: 04/24/15
Date Analyzed: 04/27/15
Date Printed: 04/27/15
First Reported: 04/27/15

Job ID/Site: 338-MA15, 423-338-29 - Santa Cruz Roundtree SB1022, Ancillary Bldg.

Date(s) Collected: 04/23/2015

FALI Job ID: 1454
Total Samples Submitted: 29
Total Samples Analyzed: 29

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
01	11635652						
Layer: White Drywall			ND				
Layer: White Skimcoat/Joint Compound			ND				
Layer: White Tape			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %) Fibrous Glass (10 %)							
02	11635653						
Layer: White Drywall			ND				
Layer: White Skimcoat/Joint Compound			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %) Fibrous Glass (10 %)							
03	11635654						
Layer: White Drywall			ND				
Layer: White Skimcoat/Joint Compound			ND				
Layer: White Tape			ND				
Layer: White Skimcoat/Joint Compound			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %) Fibrous Glass (10 %)							
04	11635655						
Layer: Beige Fibrous Material			ND				
Layer: Yellow Mastic			ND				
Layer: White Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %) Fibrous Glass (45 %)							
05	11635656						
Layer: Yellow Mastic			ND				
Layer: Tan Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (50 %)							
06	11635657						
Layer: Grey Mastic			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					

Client Name: Protech Consulting & Engineers Inc.

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
07	11635658						
		Layer: Grey Non-Fibrous Material					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
08	11635659						
		Layer: White Foam					ND
		Layer: White Non-Fibrous Material					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
09	11635660						
		Layer: White Drywall					ND
		Layer: White Skimcoat/Joint Compound					ND
		Layer: White Tape					ND
		Layer: White Skimcoat/Joint Compound					ND
		Layer: Paint					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %) Fibrous Glass (10 %)					
10	11635661						
		Layer: Brown Drywall					ND
		Layer: White Skimcoat/Joint Compound					ND
		Layer: White Tape					ND
		Layer: White Skimcoat/Joint Compound					ND
		Layer: Paint					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %) Fibrous Glass (10 %)					
11	11635662						
		Layer: White Drywall					ND
		Layer: White Skimcoat/Joint Compound					ND
		Layer: White Tape					ND
		Layer: White Skimcoat/Joint Compound					ND
		Layer: Paint					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (20 %) Fibrous Glass (10 %)					
12	11635663						
		Layer: Beige Fibrous Material					ND
		Layer: Paint					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (45 %) Fibrous Glass (35 %)					
13	11635664						
		Layer: Beige Fibrous Material					ND
		Layer: Paint					ND
		Total Composite Values of Fibrous Components:		Asbestos (ND)			
		Cellulose (45 %) Fibrous Glass (35 %)					

Client Name: Protech Consulting & Engineers Inc.

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
22	11635673						
Layer: Yellow Fibrous Material			ND				
Layer: Foil			ND				
Layer: White Fibrous Material			ND				
Layer: Foil			ND				
Layer: White Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (15 %) Fibrous Glass (75 %)							
23	11635674						
Layer: Grey Semi-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)							
24	11635675						
Layer: Grey Semi-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)							
25	11635676						
Layer: Grey Semi-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)							
26	11635677						
Layer: Grey Semi-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)							
27	11635678						
Layer: Grey Semi-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)							
28	11635679						
Layer: White Mastic			ND				
Layer: Blue Tile			ND				
Layer: Yellow Mastic			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
29	11635680						
Layer: Grey Cementitious Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							

Client Name: Protech Consulting & Engineers Inc.

Report Number: B204703

Date Printed: 04/27/15

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
-----------	------------	---------------	------------------	---------------	------------------	---------------	------------------

Tad Throver

Tad Throver, Laboratory Supervisor, Hayward Laboratory

Note: Limit of Quantification ('LOQ') = 1%. 'Trace' denotes the presence of asbestos below the LOQ. 'ND' = 'None Detected'.

Analytical results and reports are generated by Forensic Analytical Laboratories Inc. (FALI) at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by FALI to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by FALI. The client is solely responsible for the use and interpretation of test results and reports requested from FALI. Forensic Analytical Laboratories Inc. is not able to assess the degree of hazard resulting from materials analyzed. FALI reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.

General Information

Date: 04-23-15
Job ID: Santa Cruz Roundtree SB1022
Ancillary Bldg.
Collected By: ED
Lab: FAST

Analysis Requested

- PCM NIOSH 7400
- TEM
- AHERA
- Level 2
- Bulk Quantitative
- Bulk Qualitative
- PLM BULK - EPA/600/RV116
- Lead
- AA
- TTLC
- STLC
- TCLP
- Mold
- Other _____

Turn Around Time

- Rush
- 12 hours
- 24 hours
- 48 hours
- 3-5 days

Special Instructions


Prior Positive

Filter Type: MCE, 0.8 µm, 25mm MCE, 0.45µm, 25mm MCE, 0.8µm, 37mm Other _____

Sample # Date	Sample Type	Sample Protocol	Location / Activity / Material Description	Time On/Off	LPM	Total Min. Total Vol Fibers/Fields	Results
# 01-03 04	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	D.W.	on _____ off _____	on _____ end _____ Ave _____ Rotor# _____		
			2x4 C.P.	pump# _____			
# 05 06	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	w. P. Mastic	on _____ off _____	on _____ end _____ Ave _____ Rotor# _____		
			Mastic	pump# _____			
# 07 08	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Epoxy	on _____ off _____	on _____ end _____ Ave _____ Rotor# _____		
			Insulation	pump# _____			
# 09-11 12-13	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	D.W.	on _____ off _____	on _____ end _____ Ave _____ Rotor# _____		
			2x4 Gtg. Panel	pump# _____			
# 14 15	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	B.B. Mastic	on _____ off _____	on _____ end _____ Ave _____ Rotor# _____		
				pump# _____			
# 16 17-18	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	12x12 VFT w/m.	on _____ off _____	on _____ end _____ Ave _____ Rotor# _____		
			Mastic	pump# _____			
# 19-20 21-22	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Chalk	on _____ off _____	on _____ end _____ Ave _____ Rotor# _____		
			Jacket	pump# _____			
# 23-27 28	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Fireproofing	on _____ off _____	on _____ end _____ Ave _____ Rotor# _____		
			12x12 VFT w/m	pump# _____			
# 29	<input type="checkbox"/> Post <input type="checkbox"/> Area <input type="checkbox"/> Background <input type="checkbox"/> Personal <input type="checkbox"/> Blank <input type="checkbox"/> Bulk	<input type="checkbox"/> Amb. <input type="checkbox"/> ALS <input type="checkbox"/> Agg.	Stucco	on _____ off _____	on _____ end _____ Ave _____ Rotor# _____		
				pump# _____			

CHAIN OF CUSTODY

Relinquished By: <u>[Signature]</u>	Date/Time	Received By: <u>[Signature]</u>	Date/Time: <u>APR 24 2015</u>
-------------------------------------	-----------	---------------------------------	-------------------------------



**PRELIMINARY STORMWATER
CONTROL PLAN**

**ADDRESSING:
INITIAL BMP SIZING**

For

**THE ROUNDTREE JAIL EXPANSION
100 ROUNDTREE LANE
Watsonville, California 95076**



Prepared by:

**Whitson Engineers
2425 Porter Street, Suite 2
Soquel, California 95073**

Prepared:

**July 14, 2015
Project #3193.00**

WHITSON ENGINEERS

2425 Porter Street • Suite 2 • Soquel, CA 95073
831 464-9363 • Fax 831 464-2316

ROUNTREE REHABILITATION AND RE-ENTRY FACILITY SANTA CRUZ COUNTY AT 100 ROUNTREE LANE WATSONVILLE, CALIFORNIA

Background and Project Description

The detention facility boundary area covers approximately 21.6 acres and is located at 100 Rountree Lane, adjacent to the Buena Vista Landfill, in Watsonville, California. The project site currently developed and contains an existing medium security detention facility that is in use and an existing low security facility that is currently unused. The low security ("X-Building") is proposed to be renovated and expanded. The project consists of the construction of an expanded housing unit at the X-Building, a new visitation building, and an administration building and storage addition attached to the Medium Security building. Also included with the improvements is associate parking and utility improvements, permeable pavement, biotreatment areas, and miscellaneous site improvements. The total site disturbance is estimated as approximately 4.6 acres. The existing impervious coverage is estimated as 19.1% impervious. The proposed improvements will increase the impervious coverage to approximately 21.5% impervious.

The existing site currently drains to a drainage swale located along the east side of the project where it is eventually conveyed to a series of ponds prior to draining to Gallighan Slough. The proposed improvements will continue a similar drainage pattern and will discharge runoff the existing drainage swale after meeting the County's requirements for water quality and retention/detention. The site does not receive run-on from any of the adjacent properties. There were no natural creeks proposed for disturbance that require protection or maintenance. Reduced scale prints of the civil site plans for *Rountree Rehabilitation and Re-entry Facility renovation and Expansion* are include in Appendix C for reference and show the existing and proposed improvements.

On-site Soils

A sewage disposal study was performed by Steve Brooks R.E.H.S. in 1990 that indicates that the site soils below 3' are largely sands. The 9 percolation tests performed by Steve Brooks indicate percolation rates ranging from 2 to 11 in/hr. A design rate of 1 in/hr was used for preliminary drainage calculations. The final design percolation rates at the base of the proposed drainage facilities should be verified as part of the final plans. Groundwater was observed at depths of approximately 30 feet.

Project Requirements

The project has been designed to comply with the County of Santa Cruz Design Criteria, dated June 2014 (CDC). Since the adds or replaces more than 5,000 square feet of impervious area, it falls under the "Large Project" threshold for mitigation requirement referenced in Part 3, Section C,1,c of the CDC. Based on known restrictions in the downstream channel, the County is requiring that the project limit the post-development release to the predevelopment 5-year, 15 minute discharge rate while providing storage for the post-development 10-year storm event and demonstrating that the pre-project 2-year 2-hour runoff rate will not be exceeded for the 2-year storm event. Additionally, the project is required to meet the stormwater water quality standards (two times the 85th percentile event) required in the Central Coast Region Post-Construction Stormwater Management Requirements for Development Projects in the Coast Region (Resolution R3-2013-0032).

Storm Water Treatment Approach

The project consists of six main watersheds, as shown on the Watershed Summary Exhibit provided in Appendix A. Various runoff site design and runoff reduction strategies are proposed as part of the project stormwater management approach. Efforts were made to reduce impervious coverage by implementing pervious pavement, biotreatment areas, and landscape areas. Approximately 14,300 sf of conventional hardscape was replaced with permeable pavement as part of the current redesign, providing a significant reduction in impervious coverage. The site soils are proposed to be compacted to the minimum

standards required by the geotechnical engineer. Compaction beyond these requirements is not proposed. No vegetation clearing or grading is proposed beyond the minimum of what is required to construct the project. All roof runoff is directed to surface drain to biotreatment areas.

Permeable Concrete Pavement

Approximately 14,300 sf of permeable concrete pavement is proposed for several areas to reduce the project's impervious coverage. Roof water and new and replaced hardscape areas may be directed to the permeable pavement for treatment and detention as part of the final design, if practical. However, this is not proposed as part of the current plans. Subdrains may be required based on final geotechnical recommendations and percolation testing results.

Biotreatment BMP

Approximately 6,800 square feet of Biotreatment BMP area is proposed throughout the project to mitigate new or replaced impervious area. The preliminary cross-section consists of a maximum of 6 inches of ponded water over 24 inches of amended topsoil on top of 12 inches of drain rock that surrounds a 4 inch perforated pipe. An orifice is provided in a cap at the base of the perforated pipe to meter the 2-year, 2-hour pre-development discharge rate and a second orifice is provided at a higher elevation to meter the predevelopment 5-year, 15 minute discharge rate. In large storm events, stormwater that does not meter through the orifices will be conveyed to the Stormdrain System through an inlet that is raised 6 inches above the BMP channel bottom. See Appendix B for Biotreatment BMP sizing. The porosity in the amended soil and the drain rock is calculated as 0.26 and 0.40, respectively.

DESIGN CALCULATIONS

The HEC-HMS computer program was used to calculate runoff volumes, perform routing, and determine detention volume requirements. The stage storage relationship for each BMP is displayed in the excel spreadsheets included in Appendix B. The outflow is metered through two orifices that restricts the outflow to the predevelopment 5-year 15 minute discharge rate while providing storage for the post-development 10-year storm event and maintaining the 2-year 2 hour predevelopment runoff rates. A 10-year, 24-hour storm event was routed through each stage storage model to verify that the volume provided by each BMP is sufficient. The rainfall-runoff model developed by the Soil Conservation Service and presented in the TR-55 was used. The model inputs for the 10-year post-development hydrology for this project are presented in Tables 1 and 2, below.

Soil hydrologic parameters (Runoff Curve Numbers) were derived from Table 2-2a of the TR-55. The 10 year 24-hour precipitation was determined from the NOAA Atlas 14, Volume 6, Version 2, for Watsonville, California.

Table 1. 24-Hour Precipitation

10-Year	4.09 in
---------	---------

Table 2. Soil Hydrologic Parameters

Hydrologic Soil Group	Runoff Curve Number
	100-Year Storm
A	40
B	98

Table 3 summarize the project watershed areas.

Table 3: Watershed Area Summary

Watershed	Impervious Area (SF)	Pervious Area (SF)	Total Area (SF)	BMP Area (SF)
A	52,828	47,109	99,937	3,800
B	6,722	10,934	17,656	625
C	1,665	5,382	7,047	165
D	3,594	2,172	5,766	260
E	938	1,377	2,315	65
Total	65,747	66,974	132,721	4,915

*See Appendix A for Watershed Exhibit

Table 4: Storage Volume Summary

BMP	BMP A	BMP B	BMP C	BMP D	BMP E
Required Storage (CF)	2,786	1,427	1,840	300	300
Provided Storage (CF)	2,786	1,500	1,890	300	300

Table 4 summarizes the required and provided storage volumes for each BMP. For the purpose of sizing each BMP, 100 percent of the incidental rainfall is accounted for in the modeling calculations by including the BMP area as impervious area. The BMP's are designed to limit the post-development release to the predevelopment 5-year, 15 minute discharge rate while providing storage for the post-development 10-year storm event and demonstrate that the pre-project 2-year 2-hour runoff rate will not be exceeded for the 2-year storm event. Additionally, water quality calculations were performed to verify that the water quality storage volume required by Section B, 3, b, iii, a (two times the 85th percentile event), of the Central Coast Region Post-Construction Stormwater Management Requirements for Development Projects in the Coast Region (Resolution R3-2013-0032). See Appendix B for calculations. As a precautionary measure, overland escape shall be provided as part of the final design to insure that stormwater will drain out away from structures if the storm drain system were to cease functioning.

Permeable Pavement and Biotreatment BMP Operation and Maintenance Recommendations

The permeable concrete pavement is proposed to be one of the last site improvements constructed in order to minimize opportunities for construction debris to be collected in the pavement. Additionally, the project Storm Water Pollution Prevention Plan will provide guidance regarding the mitigation of potential storm water contaminants expected during construction.

After construction, the permeable concrete pavement and Biotreatment BMP will be inspected on a frequent basis and maintained in order to ensure long term performance. The following inspection and maintenance measures are proposed in maintain functionality of the project BMPs.

Permeable Pavement:

- Accumulated debris and litter shall be routinely removed as a source control measure.
- The permeable concrete pavement will be inspected several times during the first few storms to insure proper infiltration and drainage. After the first year the pavement will be inspected at least once a year.
- Permeable pavements and materials shall be cleaned with a vacuum-type street cleaner. The frequency will depend on the exposure to sediment. However it is anticipated that vacuuming may occur twice a year (before and after the rainy season).
- Hand held pressure washers can be effective for cleaning the void spaces of small areas and shall follow vacuum cleaning.
- Maintenance personnel shall be instructed not to seal or pave with non-porous materials.

- Pervious pavements will not be sanded in the winter to avoid clogging the void spaces

Biotreatment BMPs:

- Proper maintenance includes mowing, weed control, removal of trash and debris, watering during the dry season, and reseeding of non-vegetated areas.
- Remove grass cuttings after mowing grass.
- Vegetation, large shrubs or trees that interfere with landscape swale operation shall be pruned.
- Invasive vegetation contributing up to 25% of vegetation of all species shall be removed and replaced. Fallen leaves and debris from deciduous plant foliage shall be removed.
- Inspect swales at least twice annually for damage to vegetation, erosion, sediment accumulation and ponding water standing longer than 72 hours.
- Debris in quantities that inhibit operation shall be removed routinely (no less than quarterly), or upon discovery. Sediments shall be removed when depths exceed 3 inches.
- Side slopes shall be maintained to prevent erosion that introduces sediment into the swale.
- If a spill occurs and hazardous materials contaminate soils in vegetated swales, the affected areas shall be removed immediately and the appropriate soils and materials replaced as soon as possible.
- Insects and rodents shall not be harbored in the vegetated swales. Pest control measures shall be taken when insects/rodents are found to be present.
- If sprays are considered, then a mosquito larvicide, such as bacillus thurendensis or altoside formulations may be applied only if absolutely necessary, approved by the County, and, applied by an appropriately licensed individual or contractor.

Anticipated On-going Pollutant Generating Activities and Sources

Over the life of the project, there are a number of pollutant generating activities and sources expected. Table 5 below shows the expected pollutant generating activities and sources along with the proposed mitigation measures. A Pollutant Mitigation Exhibit is also included in Appendix D.



Table 5: Expected Pollutants and Mitigations

Pollutant Exhibit Plan Keynote #	Source Pollutants	Mitigation Measure – CASQA BMP Designation
1	Accidental spills or leaks	<ul style="list-style-type: none"> ○ NS-1 Water Conservation Practices ○ SC-11 Spill Prevention, Control, and Cleanup ○ SC-41 Building & Grounds Maintenance ○ SC-10 Non-Stormwater Discharges ○ Clean up spills immediately ○ Keep spill control measures onsite
2	Interior floor drains and elevator drains	<ul style="list-style-type: none"> ○ Interior floor drains and elevator drains shall be plumbed to sanitary sewer. ○ Inspect and maintain drains to prevent blockages and overflow.
3	Parking area maintenance	<ul style="list-style-type: none"> ○ SC-41 Building & Grounds Maintenance ○ SC-70 Road and Street Maintenance
4	Indoor and structural pest control	<ul style="list-style-type: none"> ○ SC-11 Spill Prevention, Control, and Cleanup ○ SC-41 Building and Grounds Maintenance ○ SC-61 Safer Alternative Products ○ Provide Integrated Pest Management information to owners, lessees, and operators
5	Landscape/out door pesticide use	<ul style="list-style-type: none"> ○ SC-11 Spill Prevention, Control, and Cleanup ○ SC-41 Building and Grounds Maintenance ○ SC-60 Housekeeping Practices ○ SC-61 Safer Alternative Products ○ SC-73 Landscape Maintenance ○ Maintain landscaping using minimum or no pesticides ○ Provide Integrated Pest Management information to owners, lessees, and operators
6	Food service operations	<ul style="list-style-type: none"> ○ SC-34 Waste Handling and Disposal ○ As necessary, drains connect to a grease interceptor before discharging to the sanitary sewer
7	Refuse areas	<ul style="list-style-type: none"> ○ SC-34 Waste Handling and Disposal ○ Provide signage stating "Do not dump hazardous materials here", or similar ○ Inspect receptacles regularly; repair or replace leaky receptacles ○ Keep receptacles covered ○ Inspect and pick up litter daily ○ Clean up spills immediately ○ Keep spill control measures onsite
8	Fire sprinkler test water	SC-41 Building and Grounds Maintenance
9	Drain or wash water from boiler drains, condensate drain lines, rooftop equipment, and other sources	SC-10 Non-Stormwater Discharges
10	Unauthorized non-stormwater discharges	<ul style="list-style-type: none"> ○ SC-10 Building and Grounds Maintenance ○ SC-60 Housekeeping Practices ○ SC-61 Safer Alternative Products
11	Building and grounds maintenance	<ul style="list-style-type: none"> ○ SC-41 Building and Grounds Maintenance ○ SC-32 Outdoor Equipment Maintenance ○ SC-60 Housekeeping Practices ○ SC-70 Plaza and Sidewalk Cleaning (includes graffiti removal) ○ SC-73 Landscape Maintenance ○ SC-74 Drainage System Maintenance

Conclusion

The preliminary drainage calculations meet the intent of the current County Design Criteria. All assumptions and calculations shall be verified by the design build team as part of the final design. The location and placement of all biotreatment and permeable pavement BMPs shall be coordinated with the project Geotechnical and Structural Engineer. All control structures and storm drainage pipes shall be sized to convey the 25 year storm flows at a minimum.

APPENDIX A



NOTE: THIS SHEET IS FOR REFERENCE ONLY.
NOT FOR CONSTRUCTION

APPROX. LIMITS OF
DISTURBANCE, TYP.

PROJECT SITE
BOUNDARY
(GROUND
LEASE AREA)

DMIA TO
BYPASS
BMP AREAS

NEW OR REPLACED
IMPERVIOUS
AREA

APPROX. LIMITS OF
DISTURBANCE, TYP.

LEGEND

- DRAINAGE MANAGEMENT AREA (DMA)
- NEW OR REPLACED IMPERVIOUS AREA
- - - PROPERTY BOUNDARY
- - - PROJECT BOUNDARY

WATERSHED SUMMARY


DMA	IMPERVIOUS AREA	TOTAL AREA
A	52,828 SF	99,937 SF
B	6,722 SF	17,656 SF
C	1,665 SF	7,047 SF
D	3,594 SF	5,766 SF
E	938 SF	2,315 SF

BMP SUMMARY

BMP DESCRIPTION	AREA	PROVIDED VOL.	REQ. VOL.
A BIOTREATMENT	3,600 SF	5,320 CF	5,306 CF
B BIOTREATMENT	625 SF	875 CF	663 CF
C BIOTREATMENT	165 SF	231 CF	187 CF
D BIOTREATMENT	260 SF	364 CF	356 CF
E BIOTREATMENT	65 SF	91 CF	91 CF
F&G SELF-TREATING	N/A	N/A	N/A

- NOTES:**
- FOR THE PURPOSE OF THESE CALCULATIONS, THE BIOSWALE SOIL MEDIA HAS A POROSITY OF 0.25 AND THE DRAIN ROCK HAS A VOID RATIO OF 0.4.
 - THE SEWAGE DISPOSAL STUDY PERFORMED BY STEVE BROOKS, R.E.H.S IN 1990 INDICATES THAT THE SITE SOILS BELOW 3' ARE LARGELY SANDS. THE 9 PERCOLATION TESTS INDICATE PERCOLATION RATES RANGING FROM 2 TO 11 IN/HR. A DESIGN RATE OF 2 IN/HR WAS USED FOR THESE CALCULATIONS AND SHOULD BE VERIFIED AS PART OF THE FINAL DESIGN PLANS.


WATERSHED EXHIBIT
SANTA CRUZ COUNTY - ROUNTREE FACILITY
SANTA CRUZ COUNTY, CALIFORNIA



Whitson Engineers
2425 Porter Street | Suite 2 | Soquel, CA 95073 | 831 464-9363 | F 831 464-2316
Civil Engineering ■ Land Surveying ■ Project Management | www.whitsonengineers.com
Project No.: 3193.02

APPENDIX B

COUNTY OF SANTA CRUZ
 DEPARTMENT OF PUBLIC WORKS
 P 60* ISOPLETHS



*P60 DENOTES RAINFALL INTENSITY IN INCHES/HR FOR 60 MINUTE DURATION AND A 100 YEAR STORM SELECT PROPER INTENSITY DURATION CURVE FROM FIGURE SWM-3 AFTER DETERMINING P60 VALUE.

PROJECT: BMP A: Rountree Jail Facility

Calc by: RMT Date: 7/14/2015

Input Parameters

Impervious Area (sf)	52828
Footprint (sf)	3,800
Soil Void Ratio	0.25
Rock Void Ratio	0.4
Ponding Depth (ft)	0.5
Soil Depth (ft)	2
Rock Depth (ft)	1

10yr-5hr Calculations (SWM-24)

Storage Req. (cf)	2710
Release Rate (cfs)	0.412

2yr-2hr Calculations (SWM-17)

Storage Req. (cf)	2639
Release Rate (cfs)	0.130

Required Water Quality Storage Volume (85th Percentile Event)

Total Watershed Area	52828 SF
Impervious Area	13867 SF
Impervious Area Ratio	0.26
Runoff Coefficient	0.20
Required WQV	1505 CF

Stage-Storage Table

Stage (ft)	Storage (cf)	Storage (ac-ft)	Orifice Release
0	0	0.0000	0.000
0.1	152	0.0035	0.024
0.2	304	0.0070	0.033
0.3	456	0.0105	0.041
0.4	608	0.0140	0.047
0.5	760	0.0174	0.053
0.6	912	0.0209	0.058
0.7	1064	0.0244	0.063
0.8	1216	0.0279	0.067
0.9	1368	0.0314	0.071
1	1520	0.0349	0.075
1.1	1672	0.0384	0.078
1.2	1824	0.0419	0.082
1.3	1976	0.0454	0.085
1.4	2128	0.0489	0.088
1.5	2280	0.0524	0.092
1.6	2432	0.0559	0.095
1.7	2584	0.0594	0.098
1.8	2736	0.0629	0.100
1.9	2888	0.0664	0.103
2	3040	0.0699	0.106
2.1	3192	0.0734	0.108
2.2	3344	0.0769	0.111
2.3	3496	0.0804	0.113
2.4	3648	0.0839	0.116
2.5	3800	0.0874	0.118
2.6	3952	0.0909	0.121
2.7	4104	0.0944	0.123
2.8	4256	0.0979	0.125
2.9	4408	0.1014	0.127
3	4560	0.1049	0.240
3.1	4712	0.1084	0.287
3.2	4864	0.1119	0.323
3.3	5016	0.1154	0.353
3.4	5168	0.1189	0.380
3.5	5320	0.1224	0.404

Bottom of Rock
Orifice 1 Elev.

Bottom of Soil

Orifice 2 Elev.
Top of Soil

Max Pond Depth:

10 Year Storm Analysis		Post-Pre 10yr-5yr			
Storm Duration (min)	10-year Intensity (in/hr)	Detention Release Qpre (cfs)	Specified 10-Year Qpost (cfs)	Rate To Storage Volume (cf)	Storage Volume (cf)
1440	0.223	0.058	0.246	-0.186	-20055
1200	0.242	0.063	0.266	-0.165	-14867
960	0.267	0.069	0.294	-0.138	-9918
720	0.303	0.079	0.333	-0.098	-5301
480	0.362	0.094	0.398	-0.033	-1194
360	0.411	0.107	0.452	0.021	554
240	0.491	0.128	0.540	0.109	1957
180	0.557	0.145	0.613	0.182	2450
120	0.666	0.173	0.732	0.301	2710
90	0.755	0.196	0.831	0.400	2699
60	0.903	0.235	0.993	0.562	2529
45	1.024	0.266	1.127	0.696	2349
30	1.224	0.318	1.347	0.916	2061
20	1.463	0.380	1.610	1.179	1768
15	1.660	0.431	1.827	1.396	1570
10	1.984	0.516	2.184	1.752	1314
5	2.691	0.699	2.961	2.530	949
0	0.000	0.000	0.000	0.000	0

Orifice 1 Sizing: (2 Year-2hr Release)

Orifice diameter	1.89 inch
Cd	0.6
Design Flow Rate (Max)	0.130 cfs
Calculated Flow Rate	0.127 cfs
Orifice Area	0.0155316 ft ²

Orifice 2 Sizing: (5 Year-15 Min Release)

Orifice diameter	3.69 inch
Cd	0.6
Design Flow Rate (Max)	0.281 cfs
Calculated Flow Rate	0.277 cfs
Orifice Area	0.0741637 ft ²

SUMMARY:

Storage Required From Routing via HEC-HMS:	5306 CF
Total Storage Provided	5320 CF

PROJECT: BMP A: Rountree Jail Facility

Calc by: RMT


Date: 7/14/2015

RUNOFF DETENTION BY THE MODIFIED RATIONAL METHOD
 Data Entry: PRESS TAB & ENTER DESIGN VALUES SS Ver. 1.0

Site Location P60 Isoleth: 1.35 Fig. SWM-2 in County Design Criteria
 Rational Coefficients Cpre: 0.25 See note # 2
 Cpost: 0.90 See note # 2
 Impervious Area: 52828 ft² See note # 2 and # 4

STRUCTURE DIMENSIONS FOR DETENTION
 2710 ft³ storage volume calculated
 100 % void space assumed
 2710 ft³ excavated volume needed
 Structure Length Width* Depth*
 Ratios 25.00 2.00 2.00
 Dimen. (ft) 75.09 6.01 6.01
 *For pipe, use the square root of the sectional area

Storm Duration (min)	10 - YEAR DESIGN STORM			DETENTION @ 15 MIN.	
	10 - Year Intensity (in/hr)	5 - Yr. Release Qpre (cfs)	10 - Year Qpost (cfs)	Detention Rate To Storage (cfs)	Specified Storage Volume (cf)
1440	0.22	0.058	0.246	-0.186	-20055
1200	0.24	0.063	0.266	-0.165	-14867
960	0.27	0.069	0.294	-0.138	-9918
720	0.30	0.079	0.333	-0.098	-5301
480	0.36	0.084	0.398	-0.033	-1194
360	0.41	0.107	0.452	0.021	554
240	0.49	0.128	0.540	0.109	1957
180	0.56	0.145	0.613	0.182	2450
120	0.67	0.173	0.732	0.301	2710
90	0.76	0.196	0.831	0.400	2699
60	0.90	0.235	0.993	0.562	2529
45	1.02	0.265	1.127	0.696	2349
30	1.22	0.318	1.347	0.916	2061
20	1.46	0.380	1.610	1.179	1768
15	1.66	0.431	1.827	1.396	1570
10	1.98	0.516	2.184	1.752	1314
5	2.69	0.699	2.961	2.530	949



- Notes & Limitations on Use:**
- 1) The modified rational method, and therefore the standard calculations are applicable in watersheds up to 20 acres in size.
 - 2) Required detention volume determinations shall be based on all net new impervious areas, both on and off-site, resulting from the proposed project. Pervious areas shall not be included in detention volume sizing; an exception may be made for incidental pervious areas less than 10% of the total area.
 - 3) Gravel packed detention chambers shall specify on the plans, aggregate that is washed, angular, and uniformly graded (of single size), assuring void space not less than 35%.
 - 4) A map showing boundaries of both regulated impervious areas and actual drainage areas routed to the hydraulic control structure of the detention facility is to be provided, clearly distinguishing between the two areas, and noting the square footage.
 - 5) The EPA defines a class V injection well as any bored, drilled, or driven shaft, or dug hole that is deeper than its widest surface dimension, or an improved sinkhole, or a subsurface fluid distribution system. Such storm water drainage wells are "authorized by rule". For more information on these rules, contact the EPA. A web site link is provided from the County DPW Stormwater Management web page.
 - 6) Refer to the County of Santa Cruz Design Criteria, for complete method criteria.

This method is available from the County Public Works web site in a computerized Excel spreadsheet format to simplify usage. <http://www.dpw.co.santa-cruz.ca.us/drainage.htm>

The spreadsheet formulas and format are copy protected to prevent alteration. Any modified submittals may be rejected, unless the changes made and the author are clearly identified, and the format is recognizably different

RUNOFF RETENTION BY THE STORAGE PERCOLATION METHOD

SS Ver:1.0

Notes & Limitations on Use:

Site Location P60 Isopeith:	1.35	Fig. SWM-2
Rational Coefficients Cpre:	0.25	
Cpost:	0.90	
Impervious Area:	52828	ft ²
Saturated Soil Permeability:	1.00	in/hr

Saturated soil permeability values may be used conservatively from the USDA-NRCS soil survey, or use actual test values. Site selection and design shall give proper consideration to the path for excess flows downstream of the designated retention area. Retention site location on, or immediately above, slopes exceeding 15% will require consulting a geotechnical engineer. Gravel packed structures shall use washed, angular, uniformly graded aggregate providing not less than 35% void space. Refer to the County of Santa Cruz Design Criteria, Stormwater Management - Section H, for complete method criteria.

2 - YEAR DESIGN STORM				RETENTION @ 120 MIN.				STRUCTURE DIMENSIONS FOR RETENTION				DETENTION @ 60 MIN.	
Storm Duration (min)	2 - Year Intensity (in/hr)	Qpre (cfs)	Qpost (cfs)	Retention Rate To Storage (cfs)	Specified Retained Volume (cf)	2639 ft ³ storage volume calculated	% void space assumed	Structure Length	Width*	Depth**	Retention Rate To Storage (cfs)	Specified Detained Volume (cf)	
1440	0.14	0.044	0.157	0.027	-1043	40	25.00	2.00	2.00	2.00	-0.019	-1672	
1200	0.15	0.047	0.170	0.040	92	6598	101.02	8.08	8.08	8.08	-0.006	-448	
960	0.17	0.052	0.188	0.058	1102	2580	ft ² internal surface area				0.011	653	
720	0.19	0.059	0.213	0.083	1940	1806	ft ² effective surface area				0.037	1584	
480	0.23	0.071	0.255	0.125	2512	17.5	hrs estimated structure drainage time				0.078	2254	
360	0.26	0.080	0.289	0.159	2639						0.113	2433	
240	0.31	0.096	0.346	0.215	2586						0.169	2434	
180	0.36	0.109	0.392	0.262	2451						0.216	2329	
120	0.43	0.130	0.469	0.339	2195						0.292	2104	
90	0.48	0.148	0.532	0.402	1993						0.355	1919	
60	0.58	0.177	0.636	0.506	1709						0.459	1653	
45	0.66	0.200	0.721	0.591	1517						0.545	1471	
30	0.78	0.240	0.862	0.732	1269						0.686	1234	
20	0.94	0.286	1.030	0.900	1051						0.854	1025	
15	1.06	0.325	1.169	1.039	916						0.993	893	
10	1.27	0.388	1.397	1.267	750						1.221	733	
5	1.72	0.526	1.895	1.765	527						1.719	516	

* For pipe, use the square root of the sectional area.
 ** If cell values displayed are corrupted, enter zero for depth, then re-enter a positive numeric value within allowed range.

STRUCTURE DIMENSIONS FOR DETENTION
 2434 ft³ storage volume calculated
 100 % void space assumed
 2434 ft³ excavated volume needed
 Structure Length 25.00 Width* 2.00 Depth* 2.00
 Ratios 72.46 5.80 5.80
 Dimen. (ft) 72.46 5.80 5.80

Project: BMP - A

Simulation Run: Run 1 Reservoir: BMP

Start of Run:	01Jan2000, 00:00	Basin Model:	Site
End of Run:	02Jan2000, 23:59	Meteorologic Model:	Met 1
Compute Time:	14Jul2015, 13:54:15	Control Specifications:	Control 1

Volume Units: AC-FT

Computed Results

Peak Inflow :	2.40 (CFS)	Date/Time of Peak Inflow :	01Jan2000, 10:07
Peak Outflow :	0.49 (CFS)	Date/Time of Peak Outflow :	01Jan2000, 10:54
Total Inflow :	0.40136 (AC-FT)	Peak Storage :	0.12182 (AC-FT)
Total Outflow :	0.40136 (AC-FT)	Peak Elevation :	(FT)

Input Parameters	
Impervious Area (sf)	6722
Footprint (sf)	625
Soil Void Ratio	0.25
Rock Void Ratio	0.4
Ponding Depth (ft)	0.5
Soil Depth (ft)	2
Rock Depth (ft)	1

10yr-5hr Calculations (SWM-24)	
Storage Req. (cf)	345
Release Rate (cfs)	0.052

2yr-2hr Calculations (SWM-17)	
Storage Req. (cf)	275
Release Rate (cfs)	0.017

Required Water Quality Storage Volume (85th Percentile Event)	
Total Watershed Area	17656 SF
Impervious Area	6722 SF
Impervious Area Ratio	0.38
Runoff Coefficient	0.27
Required WQV	660 CF

Stage-Storage Table

Stage (ft)	Storage (cf)	Storage (ac-ft)	Orifice Release
0	0	0.0000	0.000
0.1	25	0.0006	0.003
0.2	50	0.0011	0.005
0.3	75	0.0017	0.006
0.4	100	0.0023	0.007
0.5	125	0.0029	0.007
0.6	150	0.0034	0.008
0.7	175	0.0040	0.009
0.8	200	0.0046	0.009
0.9	225	0.0052	0.010
1	250	0.0057	0.010
1.1	266	0.0061	0.011
1.2	281	0.0065	0.011
1.3	297	0.0068	0.012
1.4	313	0.0072	0.012
1.5	328	0.0075	0.013
1.6	344	0.0079	0.013
1.7	359	0.0083	0.013
1.8	375	0.0086	0.014
1.9	391	0.0090	0.014
2	406	0.0093	0.015
2.1	422	0.0097	0.015
2.2	438	0.0100	0.015
2.3	453	0.0104	0.016
2.4	469	0.0108	0.016
2.5	484	0.0111	0.016
2.6	500	0.0115	0.017
2.7	516	0.0118	0.017
2.8	531	0.0122	0.017
2.9	547	0.0126	0.017
3	563	0.0129	0.032
3.1	625	0.0143	0.038
3.2	688	0.0158	0.042
3.3	750	0.0172	0.046
3.4	813	0.0187	0.049
3.5	875	0.0201	0.053

Bottom of Rock
Orifice 1 Elev.

Bottom of Soil

Orifice 2 Elev.
Top of Soil

Max Pond Depth

10 Year Storm Analysis		Post-Pre 10yr-5yr			
Storm Duration (min)	10-year Intensity (in/hr)	Detention Release Qpre (cfs)	Specified 10-Year Qpost (cfs)	Rate To Storage (cfs)	Storage Volume (cf)
1440	0.223	0.007	0.031	-0.024	-2552
1200	0.242	0.008	0.034	-0.021	-1892
960	0.267	0.009	0.037	-0.018	-1262
720	0.303	0.010	0.042	-0.012	-675
480	0.362	0.012	0.051	-0.004	-152
360	0.411	0.014	0.058	0.003	71
240	0.491	0.016	0.069	0.014	249
180	0.557	0.018	0.078	0.023	312
120	0.666	0.022	0.093	0.038	345
90	0.755	0.025	0.106	0.051	343
60	0.903	0.030	0.126	0.072	322
45	1.024	0.034	0.143	0.089	299
30	1.224	0.040	0.171	0.117	262
20	1.463	0.048	0.205	0.150	225
15	1.660	0.055	0.232	0.178	200
10	1.984	0.066	0.278	0.223	167
5	2.691	0.089	0.377	0.322	121
0	0.000	0.000	0.000	0.000	0

Max: 345

Orifice 1 Sizing: (2 Year-2hr Release)

Orifice diameter	0.63 inch (10/16")
Cd	0.6
Design Flow Rate (Max)	0.017 cfs (2 Year-2hr)
Calculated Flow Rate	0.017 cfs
Orifice Area	0.0021305 ft ²

Orifice 2 Sizing: (5 Year-15 Min Release)

Orifice diameter	1.31 inch (1-5/16")
Cd	0.6
Design Flow Rate (Max)	0.036 cfs (Difference between 1.0 and 2 year)
Calculated Flow Rate	0.035 cfs
Orifice Area	0.0093956 ft ²

SUMMARY:

Storage Required From Routing via HEC-HMS:	663 CF
Total Storage Provided	875 CF

PROJECT: **BMP B: Rountree Jail Facility**

Calc by: **RMT**

Date: **7/14/2015**

RUNOFF RETENTION BY THE STORAGE PERCOLATION METHOD

Data Entry: PRESS TAB KEY & ENTER DESIGN VALUES

Notes & Limitations on Use:

SS Ver:1.0

Site Location P60 Isopleth:	1.35	Fig. SWM-2
Rational Coefficients Cpre:	0.25	
Cpost:	0.90	
Impervious Area:	6722	ft ²
Saturated Soil Permeability:	1.00	in/hr

Saturated soil permeability values may be used conservatively from the USDA-NRCS soil survey, or use actual test values.
 Site selection and design shall give proper consideration to the path for excess flows downstream of the designated retention area.
 Retention site location on, or immediately above, slopes exceeding 15% will require consulting a geotechnical engineer.
 Gravel packed structures shall use washed, angular, uniformly graded aggregate providing not less than 35% void space.
 Refer to the County of Santa Cruz Design Criteria, Stormwater Management - Section H, for complete method criteria.

2 - YEAR DESIGN STORM				RETENTION @ 120 MIN.				STRUCTURE DIMENSIONS FOR RETENTION				RETENTION @ 60 MIN.						
Storm Duration (min)	2 - Year Intensity (in/hr)	Qpre (cfs)	Qpost (cfs)	Retention Rate To Storage (cfs)	Specified Retained Volume (cf)	279 ft ³ storage volume calculated	% void space assumed	Structure Length	Structure Width*	Structure Depth*	Retention Rate To Storage (cfs)	Specified Detained Volume (cf)	279 ft ³ storage volume calculated	% void space assumed	Structure Length	Structure Width*	Structure Depth*	
1440	0.14	0.006	0.020	0.003	-459	40	25.00	2.00	2.00	2.00	-0.002	-213	40	25.00	2.00	2.00	2.00	
1200	0.15	0.006	0.022	0.005	-258	698	47.78	3.82	3.82	3.82	-0.001	-57	698	47.78	3.82	3.82	3.82	
960	0.17	0.007	0.024	0.007	-74	577	ft ² internal surface area				0.001	83	577	ft ² internal surface area				
720	0.19	0.008	0.027	0.011	88	404	ft ² effective surface area				0.005	202	404	ft ² effective surface area				
480	0.23	0.009	0.032	0.016	216	8.3	hrs estimated structure drainage time				0.010	287	8.3	hrs estimated structure drainage time				
360	0.26	0.010	0.037	0.020	259						0.014	310						
240	0.31	0.012	0.044	0.027	279						0.022	310						
180	0.36	0.014	0.050	0.033	275						0.027	296						
120	0.43	0.017	0.060	0.043	256						0.037	268						
90	0.48	0.019	0.068	0.051	237						0.045	244						
60	0.58	0.022	0.081	0.064	207						0.058	210						
45	0.66	0.026	0.092	0.075	185						0.069	187						
30	0.78	0.030	0.110	0.093	157						0.087	157						
20	0.94	0.036	0.131	0.115	131						0.109	130						
15	1.06	0.041	0.149	0.132	115						0.126	114						
10	1.27	0.049	0.178	0.161	94						0.155	93						
5	1.72	0.067	0.241	0.225	67						0.219	66						

* For pipe, use the square root of the sectional area.
 * If cell values displayed are corrupted, enter zero for depth, then re-enter a positive numeric value within allowed range.

This method is available from the County Public Works web site in a computerized Excel spreadsheet format to simplify usage. <http://www.dpw.co.santa-cruz.ca.us/drainage.htm>

Project: BMP - B

Simulation Run: Run 1 Reservoir: BMP

Start of Run:	01Jan2000, 00:00	Basin Model:	Site
End of Run:	02Jan2000, 23:59	Meteorologic Model:	Met 1
Compute Time:	14Jul2015, 14:57:34	Control Specifications:	Control 1

Volume Units: AC-FT

Computed Results

Peak Inflow :	0.30 (CFS)	Date/Time of Peak Inflow :	01Jan2000, 10:07
Peak Outflow :	0.05 (CFS)	Date/Time of Peak Outflow :	01Jan2000, 11:01
Total Inflow :	0.05109 (AC-FT)	Peak Storage :	<u>0.01522 (AC-FT)</u> 663 CF
Total Outflow :	0.05109 (AC-FT)	Peak Elevation :	(FT)

PROJECT: BMP B: Rountree Jail Facility

Calc by: RMT


Date: 7/14/2015

RUNOFF DETENTION BY THE MODIFIED RATIONAL METHOD

Data Entry:	PRESS TAB & ENTER DESIGN VALUES	SS Ver: 1.0
Site Location P60 Isoleth:	1.35	Fig. SWM-2 in County Design Criteria
Rational Coefficients Cpre:	0.25	See note # 2
Cpost:	0.90	See note # 2
Impervious Area:	6722	ft ² See note # 2 and # 4

STRUCTURE DIMENSIONS FOR DETENTION			
345	ft ³ storage volume calculated		
100	% void space assumed		
345	ft ³ excavated volume needed		
Structure Ratios	Length	Width*	Depth*
	25.00	2.00	2.00
Dimen. (ft)	37.77	3.02	3.02

Storm Duration (min)	10 - YEAR DESIGN STORM			5 - Yr.		DETENTION @ 15 MIN.	
	10 - Year Intensity (in/hr)	10 - Year Qpost (cfs)	10 - Year Qpre (cfs)	Release (cfs)	Detention Rate To Storage (cfs)	Specified Storage Volume (cf)	
1440	0.22	0.007	0.031	0.007	-0.024	-2552	
1200	0.24	0.008	0.034	0.008	-0.021	-1892	
960	0.27	0.009	0.037	0.009	-0.018	-1262	
720	0.30	0.010	0.042	0.010	-0.012	-675	
480	0.36	0.012	0.051	0.012	-0.004	-152	
360	0.41	0.014	0.058	0.014	0.003	71	
240	0.49	0.016	0.069	0.016	0.014	249	
180	0.56	0.018	0.078	0.018	0.023	312	
120	0.67	0.022	0.093	0.022	0.038	345	
90	0.76	0.025	0.106	0.025	0.051	343	
60	0.90	0.030	0.126	0.030	0.072	322	
45	1.02	0.034	0.143	0.034	0.089	299	
30	1.22	0.040	0.171	0.040	0.117	262	
20	1.46	0.048	0.205	0.048	0.150	225	
15	1.66	0.055	0.232	0.055	0.178	200	
10	1.98	0.066	0.278	0.066	0.223	167	
5	2.69	0.089	0.377	0.089	0.322	121	



Notes & Limitations on Use:

- 1) The modified rational method, and therefore the standard calculations are applicable in watersheds up to 20 acres in size.
- 2) Required detention volume determinations shall be based on all net new impervious areas, both on and off-site, resulting from the proposed project. Pervious areas shall not be included in detention volume sizing; an exception may be made for incidental pervious areas less than 10% of the total area.
- 3) Gravel packed detention chambers shall specify on the plans, aggregate that is washed, angular, and uniformly graded (of single size), assuring void space not less than 35%.
- 4) A map showing boundaries of both regulated impervious areas and actual drainage areas routed to the hydraulic control structure of the detention facility is to be provided, clearly distinguishing between the two areas, and noting the square footage.
- 5) The EPA defines a class V injection well as any bored, drilled, or driven shaft, or dug hole that is deeper than its widest surface dimension, or an improved sinkhole, or a subsurface fluid distribution system. Such storm water drainage wells are "authorized by rule". For more information on these rules, contact the EPA. A web site link is provided from the County DPW Stormwater Management web page.
- 6) Refer to the County of Santa Cruz Design Criteria, for complete method criteria.

This method is available from the County Public Works web site in a computerized Excel spreadsheet format to simplify usage. <http://www.dpw.co.santa-cruz.ca.us/drainage.htm>

The spreadsheet formulas and format are copy protected to prevent alteration. Any modified submittals may be rejected, unless the changes made and the author are clearly identified, and the format is recognizably different

PROJECT: BMP C: Rountree Jail Facility

Calc by: RMT Date: 7/14/2015

Input Parameters

Impervious Area (sf)	1665
Footprint (sf)	165
Soil Void Ratio	0.25
Rock Void Ratio	0.4
Ponding Depth (ft)	0.5
Soil Depth (ft)	2
Rock Depth (ft)	1

10Yr-5hr Calculations (SWM-24)

Storage Req. (cf)	85
Release Rate (cfs)	0.013

2yr-2hr Calculations (SWM-17)

Storage Req. (cf)	59
Release Rate (cfs)	0.004

Required Water Quality Storage Volume (85th Percentile Event)

Total Watershed Area	7047 SF
Impervious Area	1665 SF
Impervious Area Ratio	0.24
Runoff Coefficient	0.19
Required WQV	187 CF

Stage-Storage Table

Stage (ft)	Storage (cf)	Storage (ac-ft)	Orifice Release
0.1	0	0.0000	0.000
0.2	13	0.0002	0.001
0.3	20	0.0005	0.001
0.4	26	0.0006	0.002
0.5	33	0.0008	0.002
0.6	40	0.0009	0.002
0.7	46	0.0011	0.002
0.8	53	0.0012	0.002
0.9	59	0.0014	0.002
1.0	66	0.0015	0.003
1.1	70	0.0017	0.003
1.2	74	0.0018	0.003
1.3	78	0.0019	0.003
1.4	83	0.0020	0.003
1.5	87	0.0021	0.003
1.6	91	0.0022	0.003
1.7	95	0.0023	0.003
1.8	99	0.0024	0.004
1.9	103	0.0025	0.004
2.0	107	0.0026	0.004
2.1	111	0.0027	0.004
2.2	116	0.0027	0.004
2.3	120	0.0028	0.004
2.4	124	0.0028	0.004
2.5	128	0.0029	0.004
2.6	132	0.0030	0.004
2.7	136	0.0031	0.004
2.8	140	0.0032	0.004
2.9	144	0.0033	0.004
3.0	149	0.0034	0.008
3.1	165	0.0038	0.009
3.2	182	0.0042	0.010
3.3	198	0.0045	0.011
3.4	215	0.0049	0.012
3.5	231	0.0053	0.012

Bottom of Rock
Orifice 1 Elev.

Bottom of Soil

Orifice 2 Elev.
Top of Soil

Max Pond Depth

10 Year Storm Analysis		Post-Pre 10Yr-5yr			
Storm Duration (min)	10-year Intensity (in/hr)	Detention Release Cpre (cfs)	Specified 10-Year Cpost (cfs)	Rate To Storage (cfs)	Storage Volume (cf)
1440	0.223	0.002	0.008	-0.006	-632
1200	0.242	0.002	0.008	-0.005	-469
960	0.267	0.002	0.009	-0.004	-313
720	0.303	0.002	0.011	-0.003	-167
480	0.362	0.003	0.013	-0.001	-38
360	0.411	0.003	0.014	0.001	17
240	0.491	0.004	0.017	0.003	62
180	0.557	0.005	0.019	0.006	77
120	0.666	0.005	0.023	0.009	85
90	0.755	0.006	0.026	0.013	85
60	0.903	0.007	0.031	0.018	80
45	1.024	0.008	0.036	0.022	74
30	1.224	0.010	0.042	0.029	65
20	1.463	0.012	0.051	0.037	56
15	1.660	0.014	0.058	0.044	49
10	1.984	0.016	0.069	0.055	41
5	2.691	0.022	0.093	0.080	30
0	0.000	0.000	0.000	0.000	0

Orifice 1 Sizing: (2 Year-2hr Release)

Orifice diameter	0.31 inch
Cd	0.6
Design Flow Rate (Max)	0.004 cfs
Calculated Flow Rate	0.004 cfs
Orifice Area	0.0005326 ft^2

Orifice 2 Sizing: (5 Year-15 Min Release)

Orifice diameter	0.63 inch
Cd	0.6
Design Flow Rate (Max)	0.009 cfs
Calculated Flow Rate	0.008 cfs
Orifice Area	0.0021305 ft^2

SUMMARY:

Storage Required From Routing via HEC-HMS:	167 CF
Total Storage Provided	231 CF


PROJECT: BMP C: Rountree Jail Facility

Calc by: RMT Date: 7/14/2015

RUNOFF DETENTION BY THE MODIFIED RATIONAL METHOD	
Data Entry:	PRESS TAB & ENTER DESIGN VALUES
SS Ver:	1.0
Site Location	P60 Isoleth; 1.35 Fig. SWM-2 in County Design Criteria
Rational Coefficients Cpr:	0.25 See note # 2
Cpost:	0.90 See note # 2
Impervious Area:	1665 ft ² See note # 2 and # 4

STRUCTURE DIMENSIONS FOR DETENTION			
85	ft ³ storage volume calculated		
100	% void space assumed		
85	ft ³ excavated volume needed		
Structure Ratios	Length	Width*	Depth*
	25.00	2.00	2.00
Dimen. (ft)	23.72	1.90	1.90

10 - YEAR DESIGN STORM				DETENTION @ 15 MIN.	
Storm Duration (min)	10 - Year Intensity (in/hr)	5 - Yr. Release Qpre (cfs)	10 - Year Qpost (cfs)	Detention Rate To Storage (cfs)	Specified Storage Volume (cf)
1440	0.22	0.002	0.008	-0.006	-632
1200	0.24	0.002	0.008	-0.005	-469
960	0.27	0.002	0.009	-0.004	-313
720	0.30	0.002	0.011	-0.003	-167
480	0.36	0.003	0.013	-0.001	-38
360	0.41	0.003	0.014	0.001	17
240	0.49	0.004	0.017	0.003	62
180	0.56	0.005	0.019	0.006	77
120	0.67	0.005	0.023	0.009	85
90	0.76	0.006	0.026	0.013	85
60	0.90	0.007	0.031	0.018	80
45	1.02	0.008	0.036	0.022	74
30	1.22	0.010	0.042	0.029	65
20	1.46	0.012	0.051	0.037	56
15	1.66	0.014	0.058	0.044	49
10	1.98	0.016	0.069	0.055	41
5	2.69	0.022	0.093	0.080	30



- Notes & Limitations on Use:**
- 1) The modified rational method, and therefore the standard calculations are applicable in watersheds up to 20 acres in size.
 - 2) Required detention volume determinations shall be based on all net new impervious areas, both on and off-site, resulting from the proposed project. Pervious areas shall not be included in detention volume sizing; an exception may be made for incidental pervious areas less than 10% of the total area.
 - 3) Gravel packed detention chambers shall specify on the plans, aggregate that is washed, angular, and uniformly graded (of single size), assuring void space not less than 35%.
 - 4) A map showing boundaries of both regulated impervious areas and actual drainage areas routed to the hydraulic control structure of the detention facility is to be provided, clearly distinguishing between the two areas, and noting the square footage.
 - 5) The EPA defines a class V injection well as any bored, drilled, or driven shaft, or dug hole that is deeper than its widest surface dimension, or an improved sinkhole, or a subsurface fluid distribution system. Such storm water drainage wells are "authorized by rule". For more information on these rules, contact the EPA. A web site link is provided from the County DPW Stormwater Management web page.
 - 6) Refer to the County of Santa Cruz Design Criteria, for complete method criteria.

This method is available from the County Public Works web site in a computerized Excel spreadsheet format to simplify usage. <http://www.dpw.co.santa-cruz.ca.us/drainage.htm>

The spreadsheet formulas and format are copy protected to prevent alteration. Any modified submittals may be rejected, unless the changes made and the author are clearly identified, and the format is recognizably different

PROJECT: **BMP C: Rountree Jail Facility**

Calc by: **RMT**

Date: **7/14/2015**

RUNOFF RETENTION BY THE STORAGE PERCOLATION METHOD

Data Entry: PRESS TAB KEY & ENTER DESIGN VALUES

Notes & Limitations on Use:

SS Ver:1.0

Site Location P60 Isoleth:	1.35	Fig. SWM-2
Rational Coefficients Cpre:	0.25	
Cpost:	0.90	
Impervious Area:	1665	ft ²
Saturated Soil Permeability:	1.00	in/hr

Saturated soil permeability values may be used conservatively from the USDA-NRCS soil survey, or use actual test values.
 Site selection and design shall give proper consideration to the path for excess flows downstream of the designated retention area.
 Retention site location on, or immediately above, slopes exceeding 15% will require consulting a geotechnical engineer.
 Gravel packed structures shall use washed, angular, uniformly graded aggregate providing not less than 35% void space.
 Refer to the County of Santa Cruz Design Criteria, Stormwater Management - Section H, for complete method criteria.

2 - YEAR DESIGN STORM				RETENTION @ 120 MIN.				STRUCTURE DIMENSIONS FOR RETENTION				DETENTION @ 60 MIN.			
Storm Duration (min)	2 - Year Intensity (in/hr)	Qpre (cfs)	Qpost (cfs)	Retention Rate To Storage (cfs)	Specified Retained Volume (cf)	59 ft ³ storage volume calculated	% void space assumed	Structure Length	Structure Width*	Structure Depth*	Retention Rate To Storage (cfs)	Specified Detained Volume (cf)	205 ft ² internal surface area	143 ft ² effective surface area	4.9 hrs estimated structure drainage time
1440	0.14	0.001	0.005	0.001	-195			25.00	2.00	2.00	-0.001	-53			
1200	0.15	0.001	0.005	0.001	-131			28.47	2.28	2.28	0.000	-14			
960	0.17	0.002	0.006	0.002	-72						0.000	21			
720	0.19	0.002	0.007	0.003	-18						0.001	50			
480	0.23	0.002	0.008	0.004	28						0.002	71			
360	0.26	0.003	0.009	0.005	45						0.004	77			
240	0.31	0.003	0.011	0.007	57						0.005	77			
180	0.36	0.003	0.012	0.008	59						0.007	73			
120	0.43	0.004	0.015	0.011	58						0.009	66			
90	0.48	0.005	0.017	0.013	54						0.011	60			
60	0.58	0.006	0.020	0.016	49						0.014	52			
45	0.66	0.006	0.023	0.019	44						0.017	46			
30	0.78	0.008	0.027	0.023	38						0.022	39			
20	0.94	0.009	0.032	0.028	32						0.027	32			
15	1.06	0.010	0.037	0.033	28						0.031	28			
10	1.27	0.012	0.044	0.040	23						0.038	23			
5	1.72	0.017	0.060	0.056	16						0.054	16			

* For pipe, use the square root of the sectional area.
 * If cell values displayed are corrupted, enter zero for depth, then re-enter a positive numeric value within allowed range.

This method is available from the County Public Works web site in a computerized Excel spreadsheet format to simplify usage. <http://www.dpw.co.santa-cruz.ca.us/drainage.htm>

Input Parameters

Impervious Area (sf)	3594
Footprint (sf)	260
Soil Void Ratio	0.25
Rock Void Ratio	0.4
Ponding Depth (ft)	0.5
Soil Depth (ft)	2
Rock Depth (ft)	1

10yr-5hr Calculations (SWM-24)

Storage Req. (cf)	184
Release Rate (cfs)	0.028

2yr-2hr Calculations (SWM-17)

Storage Req. (cf)	139
Release Rate (cfs)	0.009

Required Water Quality Storage Volume (85th Percentile Event)

Impervious Area	5766 SF
Impervious Area Ratio	3594 SF
Runoff Coefficient	0.62
Required WQV	0.43
	342 CF

Stage Storage Table

Stage (ft)	Storage (cf)	Storage (ac-ft)	Orifice Release
0	0	0.0000	0.000
0.1	10	0.0002	0.002
0.2	21	0.0005	0.003
0.3	31	0.0007	0.003
0.4	42	0.0010	0.003
0.5	52	0.0012	0.004
0.6	62	0.0014	0.004
0.7	73	0.0017	0.004
0.8	83	0.0019	0.004
0.9	94	0.0021	0.005
1	104	0.0024	0.005
1.1	111	0.0025	0.005
1.2	117	0.0027	0.006
1.3	124	0.0028	0.006
1.4	130	0.0030	0.006
1.5	137	0.0031	0.006
1.6	143	0.0033	0.006
1.7	150	0.0034	0.007
1.8	156	0.0036	0.007
1.9	163	0.0037	0.007
2	169	0.0039	0.007
2.1	176	0.0040	0.007
2.2	182	0.0042	0.007
2.3	189	0.0043	0.008
2.4	195	0.0045	0.008
2.5	202	0.0046	0.008
2.6	208	0.0048	0.008
2.7	215	0.0049	0.008
2.8	221	0.0051	0.008
2.9	228	0.0052	0.009
3	234	0.0054	0.016
3.1	260	0.0060	0.019
3.2	286	0.0066	0.021
3.3	312	0.0072	0.023
3.4	338	0.0078	0.025
3.5	364	0.0084	0.026

Bottom of Rock
Orifice 1 Elev.

Bottom of Soil

Orifice 2 Elev.
Top of Soil

Max Pond Depth

10 Year Storm Analysis

Storm Duration (min)	10-year Intensity (in/hr)	Detention Release Qpre (cfs)	Specified Qpost (cfs)	Rate To Storage (cfs)	Storage Volume (cf)
1440	0.223	0.004	0.017	-0.013	-1364
1200	0.242	0.004	0.018	-0.011	-1011
960	0.267	0.005	0.020	-0.009	-675
720	0.303	0.005	0.023	-0.007	-361
480	0.362	0.006	0.027	-0.002	-81
360	0.411	0.007	0.031	0.001	38
240	0.491	0.009	0.037	0.007	133
180	0.557	0.010	0.042	0.012	167
120	0.666	0.012	0.050	0.020	184
90	0.755	0.013	0.057	0.027	184
60	0.903	0.016	0.068	0.038	172
45	1.024	0.018	0.077	0.047	160
30	1.224	0.022	0.092	0.062	140
20	1.463	0.026	0.110	0.080	120
15	1.660	0.029	0.124	0.095	107
10	1.984	0.035	0.149	0.119	89
5	2.691	0.048	0.201	0.172	65
0	0.000	0.000	0.000	0.000	0

Max: 184

Orifice 1 Sizing: (2 Year-2hr Release)

Orifice diameter	0.44 inch	(7/16")
Cd	0.6	
Design Flow Rate (Max)	0.009 cfs	(2 Year-2hr)
Calculated Flow Rate	0.009 cfs	
Orifice Area	0.001044 ft ²	

Orifice 2 Sizing: (5 Year-15 Min Release)

Orifice diameter	0.94 inch	(15/16")
Cd	0.6	
Design Flow Rate (Max)	0.019 cfs	(Difference between 10 and 2 year)
Calculated Flow Rate	0.018 cfs	
Orifice Area	0.0047937 ft ²	

SUMMARY:

Storage Required From Routing via HEC-HMS:	356 CF
Total Storage Provided	364 CF

PROJECT: BMP D: Rountree Jail Facility

Calc by: RMT

Date: 7/14/2015

RUNOFF DETENTION BY THE MODIFIED RATIONAL METHOD

Data Entry: PRESS TAB & ENTER DESIGN VALUES SS Ver. 1.0

Site Location P60 Isoleth: 1.35 Fig. SWM-2 in County Design Criteria
 Rational Coefficients Cpre: 0.25 See note # 2
 Cpost: 0.90 See note # 2
 Impervious Area: 3594 ft² See note # 2 and # 4


STRUCTURE DIMENSIONS FOR DETENTION

184 ft³ storage volume calculated
 100 % void space assumed
 184 ft³ excavated volume needed

Structure Length	Width*	Depth*
25.00	2.00	2.00
Dimen. (ft)	30.65	2.45

*For pipe, use the square root of the sectional area

Storm Duration (min)	10 - YEAR DESIGN STORM			5 - Yr.		DETENTION @ 15 MIN.	
	10 - Year Intensity (in/hr)	10 - Year Qpost (cfs)	Release Qpre (cfs)	Qpre (cfs)	Detention Rate To Storage (cfs)	Specified Storage Volume (cf)	
1440	0.22	0.004	0.017	0.004	-0.013	-1364	
1200	0.24	0.004	0.018	0.004	-0.011	-1011	
960	0.27	0.005	0.020	0.005	-0.009	-675	
720	0.30	0.005	0.023	0.005	-0.007	-361	
480	0.36	0.006	0.027	0.006	-0.002	-81	
360	0.41	0.007	0.031	0.007	0.001	38	
240	0.49	0.009	0.037	0.009	0.007	133	
180	0.56	0.010	0.042	0.010	0.012	167	
120	0.67	0.012	0.050	0.012	0.020	184	
90	0.76	0.013	0.057	0.013	0.027	184	
60	0.90	0.016	0.068	0.016	0.038	172	
45	1.02	0.018	0.077	0.018	0.047	160	
30	1.22	0.022	0.092	0.022	0.062	140	
20	1.46	0.026	0.110	0.026	0.080	120	
15	1.66	0.029	0.124	0.029	0.095	107	
10	1.98	0.035	0.149	0.035	0.119	89	
5	2.69	0.048	0.201	0.048	0.172	65	



- Notes & Limitations on Use:**
- 1) The modified rational method, and therefore the standard calculations are applicable in watersheds up to 20 acres in size.
 - 2) Required detention volume determinations shall be based on all net new impervious areas, both on and off-site, resulting from the proposed project. Pervious areas shall not be included in detention volume sizing; an exception may be made for incidental pervious areas less than 10% of the total area.
 - 3) Gravel packed detention chambers shall specify on the plans, aggregate that is washed, angular, and uniformly graded (of single size), assuring void space not less than 35%.
 - 4) A map showing boundaries of both regulated impervious areas and actual drainage areas routed to the hydraulic control structure of the detention facility is to be provided, clearly distinguishing between the two areas, and noting the square footage.
 - 5) The EPA defines a class V injection well as any bored, drilled, or driven shaft, or dug hole that is deeper than its widest surface dimension, or an improved sinkhole, or a subsurface fluid distribution system. Such storm water drainage wells are "authorized by rule". For more information on these rules, contact the EPA. A web site link is provided from the County DPW Stormwater Management web page.
 - 6) Refer to the County of Santa Cruz Design Criteria, for complete method criteria.

This method is available from the County Public Works web site in a computerized Excel spreadsheet format to simplify usage. <http://www.dpw.co.santa-cruz.ca.us/drainage.htm>

The spreadsheet formulas and format are copy protected to prevent alteration. Any modified submittals may be rejected, unless the changes made and the author are clearly identified, and the format is recognizably different

PROJECT: **BMP D: Rountree Jail Facility**

Calc by: **RMT**

Date: **7/14/2015**

RUNOFF RETENTION BY THE STORAGE PERCOLATION METHOD

Data Entry: PRESS TAB KEY & ENTER DESIGN VALUES

SS Ver:1.0

Site Location P60 Isoleth: 1.35 Fig. SWM-2
 Rational Coefficients Cpre: 0.25
 Cpost: 0.90
 Impervious Area: 3594 ft²
 Saturated Soil Permeability: 1.00 in/hr

Saturated soil permeability values may be used conservatively from the USDA-NRCS soil survey, or use actual test values.
 Site selection and design shall give proper consideration to the path for excess flows downstream of the designated retention area.
 Retention site location on, or immediately above, slopes exceeding 15% will require consulting a geotechnical engineer.
 Gravel packed structures shall use washed, angular, uniformly graded aggregate providing not less than 35% void space.
 Refer to the County of Santa Cruz Design Criteria, Stormwater Management - Section H, for complete method criteria.

Notes & Limitations on Use:

2 - YEAR DESIGN STORM			
Storm Duration (min)	2 - Year Intensity (in/hr)	Qpre (cfs)	Qpost (cfs)
1440	0.14	0.003	0.011
1200	0.15	0.003	0.012
960	0.17	0.004	0.013
720	0.19	0.004	0.015
480	0.23	0.005	0.017
360	0.26	0.005	0.020
240	0.31	0.007	0.024
180	0.36	0.007	0.027
120	0.43	0.009	0.032
90	0.48	0.010	0.036
60	0.58	0.012	0.043
45	0.66	0.014	0.049
30	0.78	0.016	0.059
20	0.94	0.019	0.070
15	1.06	0.022	0.080
10	1.27	0.026	0.095
5	1.72	0.036	0.129

RETENTION @ 120 MIN.	
Retention Rate To Storage (cfs)	Specified Retained Volume (cf)
0.002	-316
0.003	-197
0.004	-86
0.006	12
0.008	93
0.011	122
0.015	138
0.018	139
0.023	132
0.027	123
0.034	108
0.040	97
0.050	83
0.061	69
0.071	61
0.086	50
0.120	36

STRUCTURE DIMENSIONS FOR RETENTION			
Structure	Length	Width*	Depth**
139	25.00	2.00	2.00
40	37.89	3.03	3.03
348			
Ratios	25.00	2.00	2.00
Dimen. (ft)	37.89	3.03	3.03
363			
254			
6.6			

ft³ storage volume calculated
 % void space assumed
 ft³ excavated volume needed
 ft² internal surface area
 ft² effective surface area
 hrs estimated structure drainage time

* For pipe, use the square root of the sectional area.
 ** If cell values displayed are corrupted, enter zero for depth, then re-enter a positive numeric value within allowed range.

STRUCTURE DIMENSIONS FOR DETENTION			
Structure	Length	Width*	Depth*
166	25.00	2.00	2.00
100	29.58	2.37	2.37
166			
Ratios	25.00	2.00	2.00
Dimen. (ft)	29.58	2.37	2.37

ft³ storage volume calculated
 % void space assumed
 ft³ excavated volume needed

DETENTION @ 60 MIN.	
Detention Rate To Storage (cfs)	Specified Detained Volume (cf)
-0.001	-114
0.000	-31
0.001	44
0.002	108
0.005	153
0.008	166
0.012	166
0.015	158
0.020	143
0.024	131
0.031	112
0.037	100
0.047	84
0.058	70
0.068	61
0.083	50
0.117	35

This method is available from the County Public Works web site in a computerized Excel spreadsheet format to simplify usage. <http://www.dpw.co.santa-cruz.ca.us/drainage.htm>

Project: BMP - D
Simulation Run: Run 1 Reservoir: BMP

Start of Run:	01Jan2000, 00:00	Basin Model:	Site
End of Run:	02Jan2000, 23:59	Meteorologic Model:	Met 1
Compute Time:	14Jul2015, 15:32:33	Control Specifications:	Control 1

Volume Units: AC-FT

Computed Results

Peak Inflow :	0.16 (CFS)	Date/Time of Peak Inflow :	01Jan2000, 10:07
Peak Outflow :	0.03 (CFS)	Date/Time of Peak Outflow :	01Jan2000, 10:56
Total Inflow :	0.02683 (AC-FT)	Peak Storage :	0.00817 (AC-FT) 356 CF
Total Outflow :	0.02683 (AC-FT)	Peak Elevation :	(FT)

Project: BMP - C

Simulation Run: Run 1 Reservoir: BMP

Start of Run:	01Jan2000, 00:00	Basin Model:	Site
End of Run:	02Jan2000, 23:59	Meteorologic Model:	Met 1
Compute Time:	14Jul2015, 15:21:34	Control Specifications:	Control 1

Volume Units: AC-FT

Computed Results

Peak Inflow :	0.07 (CFS)	Date/Time of Peak Inflow :	01Jan2000, 10:07
Peak Outflow :	0.01 (CFS)	Date/Time of Peak Outflow :	01Jan2000, 11:05
Total Inflow :	0.01303 (AC-FT)	Peak Storage :	0.00383 (AC-FT) 167 CF
Total Outflow :	0.01303 (AC-FT)	Peak Elevation :	(FT)

Input Parameters

Impervious Area (sf)	938
Footprint (sf)	65
Soil Void Ratio	0.25
Rock Void Ratio	0.4
Ponding Depth (ft)	0.5
Soil Depth (ft)	2
Rock Depth (ft)	1

10yr-5hr Calculations (SWM-24)

Storage Req. (cf)	48
Release Rate (cfs)	0.007

2yr-2hr Calculations (SWM-17)

Storage Req. (cf)	31
Release Rate (cfs)	0.002

Required Water Quality Storage Volume

(85th Percentile Event)	2315 SF
Total Watershed Area	938 SF
Impervious Area	0.41
Runoff Coefficient	0.28
Required WQV	91 CF

Stage-Storage Table

Stage (ft)	Storage (cf)	Storage (ac-ft)	Orifice Release
0	0	0.0000	0.000
0.1	3	0.0001	0.000
0.2	5	0.0001	0.000
0.3	8	0.0002	0.001
0.4	10	0.0002	0.001
0.5	13	0.0003	0.001
0.6	16	0.0004	0.001
0.7	18	0.0004	0.001
0.8	21	0.0005	0.001
0.9	23	0.0005	0.001
1	26	0.0006	0.001
1.1	28	0.0006	0.001
1.2	29	0.0007	0.001
1.3	31	0.0007	0.001
1.4	33	0.0007	0.001
1.5	34	0.0008	0.001
1.6	36	0.0008	0.001
1.7	37	0.0009	0.001
1.8	39	0.0009	0.001
1.9	41	0.0009	0.001
2	42	0.0010	0.001
2.1	44	0.0010	0.001
2.2	46	0.0010	0.001
2.3	47	0.0011	0.001
2.4	49	0.0011	0.001
2.5	50	0.0012	0.001
2.6	52	0.0012	0.001
2.7	54	0.0012	0.002
2.8	55	0.0013	0.002
2.9	57	0.0013	0.002
3	59	0.0013	0.004
3.1	65	0.0015	0.005
3.2	72	0.0016	0.005
3.3	78	0.0018	0.006
3.4	85	0.0019	0.006
3.5	91	0.0021	0.007

Bottom of Rock
Orifice 1 Elev.

Bottom of Soil

Orifice 2 Elev.
Top of Soil

Max Pond Depth

10 Year Storm Analysis				Post-Pre 10yr-5yr	
Storm Duration (min)	10-Year Intensity (in/hr)	Detention Release Qpr (cfs)	Specified 10-Year Qpost (cfs)	Rate To Storage (cfs)	Storage Volume (cf)
1440	0.223	0.001	0.004	-0.003	-356
1200	0.242	0.001	0.005	-0.003	-264
960	0.267	0.001	0.005	-0.002	-176
720	0.303	0.001	0.006	-0.002	-94
480	0.362	0.002	0.007	-0.001	-21
360	0.411	0.002	0.008	0.000	10
240	0.491	0.002	0.010	0.002	35
180	0.557	0.003	0.011	0.003	44
120	0.666	0.003	0.013	0.005	48
90	0.755	0.003	0.015	0.007	48
60	0.903	0.004	0.018	0.010	45
45	1.024	0.005	0.020	0.012	42
30	1.224	0.006	0.024	0.016	37
20	1.463	0.007	0.029	0.021	31
15	1.660	0.008	0.032	0.025	28
10	1.984	0.009	0.039	0.031	23
5	2.691	0.012	0.053	0.045	17
0	0.000	0.000	0.000	0.000	0

Max: 48

Orifice 1 Sizing: (2 Year-2hr Release)

Orifice diameter	0.19 inch (3/16")
Cd	0.6
Design Flow Rate (Max)	0.002 cfs
Calculated Flow Rate	0.002 cfs
Orifice Area	0.0001917 ft ²

Orifice 2 Sizing: (5 Year-15 Min Release)

Orifice diameter	0.50 inch (1/2")
Cd	0.6
Design Flow Rate (Max)	0.005 cfs
Calculated Flow Rate	0.005 cfs
Orifice Area	0.0013635 ft ²

SUMMARY:

Storage Required From Routing via HEC-HMS:	65 CF
Total Storage Provided	91 CF

PROJECT: BMP D: Rountree Jail Facility

Calc by: RMT

Date: 7/14/2015

RUNOFF DETENTION BY THE MODIFIED RATIONAL METHOD

Data Entry: PRESS TAB & ENTER DESIGN VALUES SS Ver. 1.0


Site Location #60 Isoleth:	1.35	Fig. SWM-2 in County Design Criteria
Rational Coefficients Cpre:	0.25	See note # 2
Cpost:	0.90	See note # 2
Impervious Area:	938	ft ²
		See note # 2 and # 4

STRUCTURE DIMENSIONS FOR DETENTION

48	ft ³ storage volume calculated		
100	% void space assumed		
48	ft ³ excavated volume needed		
Structure Ratios	Length	Width*	Depth*
	25.00	2.00	2.00
Dimen. (ft)	19.59	1.57	1.57

*For pipe, use the square root of the sectional area

Storm Duration (min)	10 - YEAR DESIGN STORM			DETENTION @ 15 MIN.	
	10 - Year Intensity (in/hr)	5 - Yr. Release Qpre (cfs)	10 - Year Qpost (cfs)	Detention Rate To Storage (cfs)	Specified Storage Volume (cf)
1440	0.22	0.001	0.004	-0.003	-356
1200	0.24	0.001	0.005	-0.003	-264
960	0.27	0.001	0.005	-0.002	-176
720	0.30	0.001	0.006	-0.002	-94
480	0.36	0.002	0.007	-0.001	-21
360	0.41	0.002	0.008	0.000	10
240	0.49	0.002	0.010	0.002	35
180	0.56	0.003	0.011	0.003	44
120	0.67	0.003	0.013	0.005	48
90	0.76	0.003	0.015	0.007	48
60	0.90	0.004	0.018	0.010	45
45	1.02	0.005	0.020	0.012	42
30	1.22	0.006	0.024	0.016	37
20	1.46	0.007	0.029	0.021	31
15	1.66	0.008	0.032	0.025	28
10	1.98	0.009	0.039	0.031	23
5	2.69	0.012	0.053	0.045	17



Notes & Limitations on Use:

- 1) The modified rational method, and therefore the standard calculations are applicable in watersheds up to 20 acres in size.
- 2) Required detention volume determinations shall be based on all net new impervious areas, both on and off-site, resulting from the proposed project. Pervious areas shall not be included in detention volume sizing; an exception may be made for incidental pervious areas less than 10% of the total area.
- 3) Gravel packed detention chambers shall specify on the plans, aggregate that is washed, angular, and uniformly graded (of single size), assuring void space not less than 35%.
- 4) A map showing boundaries of both regulated impervious areas and actual drainage areas routed to the hydraulic control structure of the detention facility is to be provided, clearly distinguishing between the two areas, and noting the square footage.
- 5) The EPA defines a class V injection well as any bored, drilled, or driven shaft, or dug hole that is deeper than its widest surface dimension, or an improved sinkhole, or a subsurface fluid distribution system. Such storm water drainage wells are "authorized by rule". For more information on these rules, contact the EPA. A web site link is provided from the County DPW Stormwater Management web page.
- 6) Refer to the County of Santa Cruz Design Criteria, for complete method criteria.

This method is available from the County Public Works web site in a computerized Excel spreadsheet format to simplify usage. <http://www.dpw.co.santa-cruz.ca.us/drainage.htm>

The spreadsheet formulas and format are copy protected to prevent alteration. Any modified submittals may be rejected, unless the changes made and the author are clearly identified, and the format is recognizably different

PROJECT: **BMP D: Rountree Jail Facility**

Calc by: **RMT**

Date: **7/14/2015**

SS Ver:1.0

RUNOFF RETENTION BY THE STORAGE PERCOLATION METHOD

Notes & Limitations on Use:

Data Entry: PRESS TAB KEY & ENTER DESIGN VALUES

Site Location P60 Isopeith:	1.35	Fig. SWM-2
Rational Coefficients Cpre:	0.25	
Cpost:	0.90	
Impervious Area:	938	ft ²
Saturated Soil Permeability:	1.00	in/hr

Saturated soil permeability values may be used conservatively from the USDA-NRCS soil survey, or use actual test values. Site selection and design shall give proper consideration to the path for excess flows downstream of the designated retention area. Retention site location on, or immediately above, slopes exceeding 15% will require consulting a geotechnical engineer. Gravel packed structures shall use washed, angular, uniformly graded aggregate providing not less than 35% void space. Refer to the County of Santa Cruz Design Criteria, Stormwater Management - Section H, for complete method criteria.

2 - YEAR DESIGN STORM				RETENTION @ 120 MIN.			STRUCTURE DIMENSIONS FOR RETENTION			DETENTION @ 60 MIN.			
Storm Duration (min)	2 - Year Intensity (in/hr)	Qpre (cfs)	Qpost (cfs)	Retention Rate To Storage (cfs)	Specified Retained Volume (cf)	ft ³ storage volume calculated	% void space assumed	ft ³ excavated volume needed	Structure Length	Width*	Depth**	Detention Rate To Storage (cfs)	Specified Detained Volume (cf)
1440	0.14	0.001	0.003	0.000	-132	31	40	77	25.00	2.00	2.00	0.000	-30
1200	0.15	0.001	0.003	0.001	-93	40	40	77	22.91	1.83	1.83	0.000	-8
960	0.17	0.001	0.003	0.001	-55	77	133	133	ft ² internal surface area			0.000	12
720	0.19	0.001	0.004	0.001	-21	93	93	93	ft ² effective surface area			0.001	28
480	0.23	0.001	0.005	0.002	8	4.0	4.0	4.0	hrs estimated structure drainage time			0.001	40
360	0.26	0.001	0.005	0.003	20							0.002	43
240	0.31	0.002	0.006	0.004	29							0.003	43
180	0.36	0.002	0.007	0.005	31							0.004	41
120	0.43	0.002	0.008	0.006	31							0.005	37
90	0.48	0.003	0.009	0.007	29							0.006	34
60	0.58	0.003	0.011	0.009	27							0.008	29
45	0.66	0.004	0.013	0.010	24							0.010	26
30	0.78	0.004	0.015	0.013	21							0.012	22
20	0.94	0.005	0.018	0.016	18							0.015	18
15	1.06	0.006	0.021	0.018	16							0.018	16
10	1.27	0.007	0.025	0.023	13							0.022	13
5	1.72	0.009	0.034	0.031	9							0.031	9

* For pipe, use the square root of the sectional area.
 * If cell values displayed are corrupted, enter zero for depth, then re-enter a positive numeric value within allowed range.

This method is available from the County Public Works web site in a computerized Excel spreadsheet format to simplify usage. <http://www.dpw.co.santa-cruz.ca.us/drainage.htm>

Project: BMP - E

Simulation Run: Run 1 Reservoir: BMP

Start of Run:	01Jan2000, 00:00	Basin Model:	Site
End of Run:	02Jan2000, 23:59	Meteorologic Model:	Met 1
Compute Time:	14Jul2015, 15:37:21	Control Specifications:	Control 1

Volume Units: AC-FT

Computed Results

Peak Inflow :	0.04 (CFS)	Date/Time of Peak Inflow :	01Jan2000, 10:07
Peak Outflow :	0.01 (CFS)	Date/Time of Peak Outflow :	01Jan2000, 10:47
Total Inflow :	0.00718 (AC-FT)	Peak Storage :	0.00148 (AC-FT) 65 CF
Total Outflow :	0.00718 (AC-FT)	Peak Elevation :	(FT)

APPENDIX C



CGL COMPANIES
2485 HATFIELD PARK DR., SUITE 300
SACRAMENTO, CA 95833



100% CRITERIA DOCUMENTS


**SANTA CRUZ COUNTY
ROUNTREE
REHABILITATION AND
RE-ENTRY FACILITY**

**100 ROUNTREE LANE
WASTONVILLE, CA**

**SCHEMATIC
GRADING,
DRAINAGE &
UTILITY PLAN**

PROJECT NUMBER: 40223
DATE: 7/16/2013

C1.1
SCALE: 1" = 30'



- GRADING KEY NOTES**
1. NEW PROPOSED
 2. EXISTING
 3. EXISTING PAVING LOT, SEE ARCHITECTURE PLANS
 4. NEW CONCRETE CURB AND GUTTER
 5. RELOCATE OR REPLACE EXISTING SOM
 6. NEW FENCE, SEE ARCHITECTURE PLANS
 7. NEW PRECAST CONCRETE WALKING TRACK
 8. NEW GRASS PAPER SEPTIC TANK ACCESS DRIVEWAY
 9. NEW POST INDICATOR MARKS
 10. NEW FENCE TO EXISTING WALKING TRACK
 11. EXISTING WALKING TRACK
 12. EXISTING WALKING TRACK
 13. EXISTING WALKING TRACK
 14. EXISTING WALKING TRACK
 15. EXISTING WALKING TRACK
 16. EXISTING WALKING TRACK
 17. EXISTING WALKING TRACK
 18. EXISTING WALKING TRACK
 19. EXISTING WALKING TRACK
 20. EXISTING WALKING TRACK
 21. EXISTING WALKING TRACK
 22. EXISTING WALKING TRACK
 23. EXISTING WALKING TRACK
 24. EXISTING WALKING TRACK
 25. EXISTING WALKING TRACK
 26. EXISTING WALKING TRACK
 27. EXISTING WALKING TRACK
 28. EXISTING WALKING TRACK
 29. EXISTING WALKING TRACK
 30. EXISTING WALKING TRACK
 31. EXISTING WALKING TRACK
 32. EXISTING WALKING TRACK
 33. EXISTING WALKING TRACK
 34. EXISTING WALKING TRACK
 35. EXISTING WALKING TRACK
 36. EXISTING WALKING TRACK
 37. EXISTING WALKING TRACK
 38. EXISTING WALKING TRACK
 39. EXISTING WALKING TRACK
 40. EXISTING WALKING TRACK
 41. EXISTING WALKING TRACK
 42. EXISTING WALKING TRACK
 43. EXISTING WALKING TRACK
 44. EXISTING WALKING TRACK
 45. EXISTING WALKING TRACK
 46. EXISTING WALKING TRACK
 47. EXISTING WALKING TRACK
 48. EXISTING WALKING TRACK
 49. EXISTING WALKING TRACK
 50. EXISTING WALKING TRACK
 51. EXISTING WALKING TRACK
 52. EXISTING WALKING TRACK
 53. EXISTING WALKING TRACK
 54. EXISTING WALKING TRACK
 55. EXISTING WALKING TRACK
 56. EXISTING WALKING TRACK
 57. EXISTING WALKING TRACK
 58. EXISTING WALKING TRACK
 59. EXISTING WALKING TRACK
 60. EXISTING WALKING TRACK
 61. EXISTING WALKING TRACK
 62. EXISTING WALKING TRACK
 63. EXISTING WALKING TRACK
 64. EXISTING WALKING TRACK
 65. EXISTING WALKING TRACK
 66. EXISTING WALKING TRACK
 67. EXISTING WALKING TRACK
 68. EXISTING WALKING TRACK
 69. EXISTING WALKING TRACK
 70. EXISTING WALKING TRACK
 71. EXISTING WALKING TRACK
 72. EXISTING WALKING TRACK
 73. EXISTING WALKING TRACK
 74. EXISTING WALKING TRACK
 75. EXISTING WALKING TRACK
 76. EXISTING WALKING TRACK
 77. EXISTING WALKING TRACK
 78. EXISTING WALKING TRACK
 79. EXISTING WALKING TRACK
 80. EXISTING WALKING TRACK
 81. EXISTING WALKING TRACK
 82. EXISTING WALKING TRACK
 83. EXISTING WALKING TRACK
 84. EXISTING WALKING TRACK
 85. EXISTING WALKING TRACK
 86. EXISTING WALKING TRACK
 87. EXISTING WALKING TRACK
 88. EXISTING WALKING TRACK
 89. EXISTING WALKING TRACK
 90. EXISTING WALKING TRACK
 91. EXISTING WALKING TRACK
 92. EXISTING WALKING TRACK
 93. EXISTING WALKING TRACK
 94. EXISTING WALKING TRACK
 95. EXISTING WALKING TRACK
 96. EXISTING WALKING TRACK
 97. EXISTING WALKING TRACK
 98. EXISTING WALKING TRACK
 99. EXISTING WALKING TRACK
 100. EXISTING WALKING TRACK

NOTE:
STOCK FILE EXISTING BRICK REMOVED AS PART
OF THE PROJECT, AS DIRECTED BY THE OWNER




NOT FOR CONSTRUCTION

PROPOSED WALKING TRACK
WALKING TRACK

APPROXIMATE WALKING TRACK
WALKING TRACK

APPROXIMATE WALKING TRACK
WALKING TRACK



CGL COMPANIES
248 MATOMAS PARK DR., SUITE 300
SACRAMENTO, CA 95833



WHITSON ENGINEERS
1407 YORK STREET, SUITE 200
SACRAMENTO, CA 95833
REGISTERED PROFESSIONAL ENGINEER
NO. 10000
CIVIL
3/18/03

100% CRITERIA DOCUMENTS

SANTA CRUZ COUNTY
ROUNTREE
REHABILITATION AND
RE-ENTRY FACILITY

100 ROUNTREE LANE
WASTONVILLE, CA

TEMPORARY
WATER
POLLUTION
CONTROL PLAN

PROJECT NUMBER
40222
DATE
7/15/2015

C2.1
SCALE
1" = 60'

- APPROPRIATE CALTRANS OR COUNTY BMP THE CONSTRUCTION SHALL PROVIDE A SLOPE PREVENTION AND RESPONSE PLAN INCLUDING ALL IMPROVEMENT PRODUCTS THAT WILL BE AVAILABLE AT THE PROJECT SITE DURING THE COURSE OF CONSTRUCTION ACTIVITIES.
1. THE CONSTRUCTION SHALL PROVIDE A SLOPE PREVENTION AND RESPONSE PLAN INCLUDING ALL IMPROVEMENT PRODUCTS THAT WILL BE AVAILABLE AT THE PROJECT SITE DURING THE COURSE OF CONSTRUCTION ACTIVITIES.
 2. SOIL EROSION CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE CONSTRUCTION PERIOD.
 3. TOTAL DISTURBANCE AREA: 5.6 ACRES.
 4. THIS PROJECT WILL INCURE A POINT FROM THE REGIONAL WATER QUALITY CONTROL BOARD.
 5. THE CONTRACTOR SHALL SUBMIT A SLOPE PREVENTION AND RESPONSE PLAN TO THE COUNTY AND REGIONAL WATER QUALITY CONTROL BOARD FOR APPROVAL.
 6. EROSION IS TO BE CONTROLLED AT ALL TIMES THROUGH PROPER MEASURES SHOWN ARE TO BE IMPLEMENTED AT A MINIMUM BEGINNING OCTOBER 15TH AND APRIL 15TH. THE AVOIDANCE OF SITE EROSION CONTROL MEASURES IS TO PREVENT EROSION AND TO PREVENT EROSION FROM LEAVING THE SITE ON EXISTING ANY WEATHERING OR RECEIVING RAIN. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SEE THAT ANY ADDITIONAL MEASURES NECESSARY TO CONTROL SITE EROSION AND PREVENT SEDIMENT TRANSPORT OFF-SITE ARE IMPLEMENTED.
 7. UNNECESSARY DRIVING AND DISTURBANCE OF SOIL SHALL BE AVOIDED (SEE 16-17).
 8. RAINFALL FROM THE CONSTRUCTION SITE MUST NOT BE ALLOWED TO FLOW OVER ANY FILL SLOPES.
 9. ALL EXCAVATED MATERIAL NOT SUITABLE FOR FILL OR OTHER USE ON-SITE SHALL BE REMOVED TO AN APPROVED DISPOSAL SITE.
 10. FOR ON-SITE CONSTRUCTION & STAGING AREAS SITE HOUSEKEEPING, MATERIALS MANAGEMENT, & EQUIPMENT MANAGEMENT SHALL BE CONSISTENT WITH THE REQUIREMENTS OF THE

11. APPROPRIATE CALTRANS OR COUNTY BMP THE CONSTRUCTION SHALL PROVIDE A SLOPE PREVENTION AND RESPONSE PLAN INCLUDING ALL IMPROVEMENT PRODUCTS THAT WILL BE AVAILABLE AT THE PROJECT SITE DURING THE COURSE OF CONSTRUCTION ACTIVITIES.
12. SOIL EROSION CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE CONSTRUCTION PERIOD.
13. TOTAL DISTURBANCE AREA: 5.6 ACRES.
14. THIS PROJECT WILL INCURE A POINT FROM THE REGIONAL WATER QUALITY CONTROL BOARD.
15. THE CONTRACTOR SHALL SUBMIT A SLOPE PREVENTION AND RESPONSE PLAN TO THE COUNTY AND REGIONAL WATER QUALITY CONTROL BOARD FOR APPROVAL.
16. EROSION IS TO BE CONTROLLED AT ALL TIMES THROUGH PROPER MEASURES SHOWN ARE TO BE IMPLEMENTED AT A MINIMUM BEGINNING OCTOBER 15TH AND APRIL 15TH. THE AVOIDANCE OF SITE EROSION CONTROL MEASURES IS TO PREVENT EROSION AND TO PREVENT EROSION FROM LEAVING THE SITE ON EXISTING ANY WEATHERING OR RECEIVING RAIN. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SEE THAT ANY ADDITIONAL MEASURES NECESSARY TO CONTROL SITE EROSION AND PREVENT SEDIMENT TRANSPORT OFF-SITE ARE IMPLEMENTED.
17. UNNECESSARY DRIVING AND DISTURBANCE OF SOIL SHALL BE AVOIDED (SEE 16-17).
18. RAINFALL FROM THE CONSTRUCTION SITE MUST NOT BE ALLOWED TO FLOW OVER ANY FILL SLOPES.
19. ALL EXCAVATED MATERIAL NOT SUITABLE FOR FILL OR OTHER USE ON-SITE SHALL BE REMOVED TO AN APPROVED DISPOSAL SITE.
20. FOR ON-SITE CONSTRUCTION & STAGING AREAS SITE HOUSEKEEPING, MATERIALS MANAGEMENT, & EQUIPMENT MANAGEMENT SHALL BE CONSISTENT WITH THE REQUIREMENTS OF THE

BMP NOTES:
TRANS BARRIERS SHALL BE IN PLACE ON SITE AS DESCRIBED IN THE BMP PLAN SHEET UNLESS OTHERWISE DIRECTED BY THE PROJECT PLANS. CALTRANS BMP PLAN SHEETS CAN BE FOUND AT THE FOLLOWING WEBSITE: WWW.CALTRANS.GOV/CONSTRUCTION/STANDARD/BARRIERS/INDEX.HTML

SS-1	SCHEDULING	NS-7	PORTABLE WATER/IRRIGATION
SS-2	CONSTRUCTION SCHEDULING	NS-8	VEHICLE AND EQUIPMENT MAINTENANCE
SS-3	CONSTRUCTION SCHEDULING	NS-9	VEHICLE AND EQUIPMENT MAINTENANCE
SS-4	CONSTRUCTION SCHEDULING	NS-10	VEHICLE AND EQUIPMENT MAINTENANCE
SS-5	CONSTRUCTION SCHEDULING	NS-11	VEHICLE AND EQUIPMENT MAINTENANCE
SS-6	CONSTRUCTION SCHEDULING	NS-12	VEHICLE AND EQUIPMENT MAINTENANCE
SS-7	CONSTRUCTION SCHEDULING	NS-13	VEHICLE AND EQUIPMENT MAINTENANCE
SS-8	CONSTRUCTION SCHEDULING	NS-14	VEHICLE AND EQUIPMENT MAINTENANCE
SS-9	CONSTRUCTION SCHEDULING	NS-15	VEHICLE AND EQUIPMENT MAINTENANCE
SS-10	CONSTRUCTION SCHEDULING	NS-16	VEHICLE AND EQUIPMENT MAINTENANCE
SS-11	CONSTRUCTION SCHEDULING	NS-17	VEHICLE AND EQUIPMENT MAINTENANCE
SS-12	CONSTRUCTION SCHEDULING	NS-18	VEHICLE AND EQUIPMENT MAINTENANCE
SS-13	CONSTRUCTION SCHEDULING	NS-19	VEHICLE AND EQUIPMENT MAINTENANCE
SS-14	CONSTRUCTION SCHEDULING	NS-20	VEHICLE AND EQUIPMENT MAINTENANCE
SS-15	CONSTRUCTION SCHEDULING	NS-21	VEHICLE AND EQUIPMENT MAINTENANCE
SS-16	CONSTRUCTION SCHEDULING	NS-22	VEHICLE AND EQUIPMENT MAINTENANCE
SS-17	CONSTRUCTION SCHEDULING	NS-23	VEHICLE AND EQUIPMENT MAINTENANCE
SS-18	CONSTRUCTION SCHEDULING	NS-24	VEHICLE AND EQUIPMENT MAINTENANCE
SS-19	CONSTRUCTION SCHEDULING	NS-25	VEHICLE AND EQUIPMENT MAINTENANCE
SS-20	CONSTRUCTION SCHEDULING	NS-26	VEHICLE AND EQUIPMENT MAINTENANCE
SS-21	CONSTRUCTION SCHEDULING	NS-27	VEHICLE AND EQUIPMENT MAINTENANCE
SS-22	CONSTRUCTION SCHEDULING	NS-28	VEHICLE AND EQUIPMENT MAINTENANCE
SS-23	CONSTRUCTION SCHEDULING	NS-29	VEHICLE AND EQUIPMENT MAINTENANCE
SS-24	CONSTRUCTION SCHEDULING	NS-30	VEHICLE AND EQUIPMENT MAINTENANCE
SS-25	CONSTRUCTION SCHEDULING	NS-31	VEHICLE AND EQUIPMENT MAINTENANCE
SS-26	CONSTRUCTION SCHEDULING	NS-32	VEHICLE AND EQUIPMENT MAINTENANCE
SS-27	CONSTRUCTION SCHEDULING	NS-33	VEHICLE AND EQUIPMENT MAINTENANCE
SS-28	CONSTRUCTION SCHEDULING	NS-34	VEHICLE AND EQUIPMENT MAINTENANCE
SS-29	CONSTRUCTION SCHEDULING	NS-35	VEHICLE AND EQUIPMENT MAINTENANCE
SS-30	CONSTRUCTION SCHEDULING	NS-36	VEHICLE AND EQUIPMENT MAINTENANCE
SS-31	CONSTRUCTION SCHEDULING	NS-37	VEHICLE AND EQUIPMENT MAINTENANCE
SS-32	CONSTRUCTION SCHEDULING	NS-38	VEHICLE AND EQUIPMENT MAINTENANCE
SS-33	CONSTRUCTION SCHEDULING	NS-39	VEHICLE AND EQUIPMENT MAINTENANCE
SS-34	CONSTRUCTION SCHEDULING	NS-40	VEHICLE AND EQUIPMENT MAINTENANCE
SS-35	CONSTRUCTION SCHEDULING	NS-41	VEHICLE AND EQUIPMENT MAINTENANCE
SS-36	CONSTRUCTION SCHEDULING	NS-42	VEHICLE AND EQUIPMENT MAINTENANCE
SS-37	CONSTRUCTION SCHEDULING	NS-43	VEHICLE AND EQUIPMENT MAINTENANCE
SS-38	CONSTRUCTION SCHEDULING	NS-44	VEHICLE AND EQUIPMENT MAINTENANCE
SS-39	CONSTRUCTION SCHEDULING	NS-45	VEHICLE AND EQUIPMENT MAINTENANCE
SS-40	CONSTRUCTION SCHEDULING	NS-46	VEHICLE AND EQUIPMENT MAINTENANCE
SS-41	CONSTRUCTION SCHEDULING	NS-47	VEHICLE AND EQUIPMENT MAINTENANCE
SS-42	CONSTRUCTION SCHEDULING	NS-48	VEHICLE AND EQUIPMENT MAINTENANCE
SS-43	CONSTRUCTION SCHEDULING	NS-49	VEHICLE AND EQUIPMENT MAINTENANCE
SS-44	CONSTRUCTION SCHEDULING	NS-50	VEHICLE AND EQUIPMENT MAINTENANCE
SS-45	CONSTRUCTION SCHEDULING	NS-51	VEHICLE AND EQUIPMENT MAINTENANCE
SS-46	CONSTRUCTION SCHEDULING	NS-52	VEHICLE AND EQUIPMENT MAINTENANCE
SS-47	CONSTRUCTION SCHEDULING	NS-53	VEHICLE AND EQUIPMENT MAINTENANCE
SS-48	CONSTRUCTION SCHEDULING	NS-54	VEHICLE AND EQUIPMENT MAINTENANCE
SS-49	CONSTRUCTION SCHEDULING	NS-55	VEHICLE AND EQUIPMENT MAINTENANCE
SS-50	CONSTRUCTION SCHEDULING	NS-56	VEHICLE AND EQUIPMENT MAINTENANCE
SS-51	CONSTRUCTION SCHEDULING	NS-57	VEHICLE AND EQUIPMENT MAINTENANCE
SS-52	CONSTRUCTION SCHEDULING	NS-58	VEHICLE AND EQUIPMENT MAINTENANCE
SS-53	CONSTRUCTION SCHEDULING	NS-59	VEHICLE AND EQUIPMENT MAINTENANCE
SS-54	CONSTRUCTION SCHEDULING	NS-60	VEHICLE AND EQUIPMENT MAINTENANCE
SS-55	CONSTRUCTION SCHEDULING	NS-61	VEHICLE AND EQUIPMENT MAINTENANCE
SS-56	CONSTRUCTION SCHEDULING	NS-62	VEHICLE AND EQUIPMENT MAINTENANCE
SS-57	CONSTRUCTION SCHEDULING	NS-63	VEHICLE AND EQUIPMENT MAINTENANCE
SS-58	CONSTRUCTION SCHEDULING	NS-64	VEHICLE AND EQUIPMENT MAINTENANCE
SS-59	CONSTRUCTION SCHEDULING	NS-65	VEHICLE AND EQUIPMENT MAINTENANCE
SS-60	CONSTRUCTION SCHEDULING	NS-66	VEHICLE AND EQUIPMENT MAINTENANCE
SS-61	CONSTRUCTION SCHEDULING	NS-67	VEHICLE AND EQUIPMENT MAINTENANCE
SS-62	CONSTRUCTION SCHEDULING	NS-68	VEHICLE AND EQUIPMENT MAINTENANCE
SS-63	CONSTRUCTION SCHEDULING	NS-69	VEHICLE AND EQUIPMENT MAINTENANCE
SS-64	CONSTRUCTION SCHEDULING	NS-70	VEHICLE AND EQUIPMENT MAINTENANCE
SS-65	CONSTRUCTION SCHEDULING	NS-71	VEHICLE AND EQUIPMENT MAINTENANCE
SS-66	CONSTRUCTION SCHEDULING	NS-72	VEHICLE AND EQUIPMENT MAINTENANCE
SS-67	CONSTRUCTION SCHEDULING	NS-73	VEHICLE AND EQUIPMENT MAINTENANCE
SS-68	CONSTRUCTION SCHEDULING	NS-74	VEHICLE AND EQUIPMENT MAINTENANCE
SS-69	CONSTRUCTION SCHEDULING	NS-75	VEHICLE AND EQUIPMENT MAINTENANCE
SS-70	CONSTRUCTION SCHEDULING	NS-76	VEHICLE AND EQUIPMENT MAINTENANCE
SS-71	CONSTRUCTION SCHEDULING	NS-77	VEHICLE AND EQUIPMENT MAINTENANCE
SS-72	CONSTRUCTION SCHEDULING	NS-78	VEHICLE AND EQUIPMENT MAINTENANCE
SS-73	CONSTRUCTION SCHEDULING	NS-79	VEHICLE AND EQUIPMENT MAINTENANCE
SS-74	CONSTRUCTION SCHEDULING	NS-80	VEHICLE AND EQUIPMENT MAINTENANCE
SS-75	CONSTRUCTION SCHEDULING	NS-81	VEHICLE AND EQUIPMENT MAINTENANCE
SS-76	CONSTRUCTION SCHEDULING	NS-82	VEHICLE AND EQUIPMENT MAINTENANCE
SS-77	CONSTRUCTION SCHEDULING	NS-83	VEHICLE AND EQUIPMENT MAINTENANCE
SS-78	CONSTRUCTION SCHEDULING	NS-84	VEHICLE AND EQUIPMENT MAINTENANCE
SS-79	CONSTRUCTION SCHEDULING	NS-85	VEHICLE AND EQUIPMENT MAINTENANCE
SS-80	CONSTRUCTION SCHEDULING	NS-86	VEHICLE AND EQUIPMENT MAINTENANCE
SS-81	CONSTRUCTION SCHEDULING	NS-87	VEHICLE AND EQUIPMENT MAINTENANCE
SS-82	CONSTRUCTION SCHEDULING	NS-88	VEHICLE AND EQUIPMENT MAINTENANCE
SS-83	CONSTRUCTION SCHEDULING	NS-89	VEHICLE AND EQUIPMENT MAINTENANCE
SS-84	CONSTRUCTION SCHEDULING	NS-90	VEHICLE AND EQUIPMENT MAINTENANCE
SS-85	CONSTRUCTION SCHEDULING	NS-91	VEHICLE AND EQUIPMENT MAINTENANCE
SS-86	CONSTRUCTION SCHEDULING	NS-92	VEHICLE AND EQUIPMENT MAINTENANCE
SS-87	CONSTRUCTION SCHEDULING	NS-93	VEHICLE AND EQUIPMENT MAINTENANCE
SS-88	CONSTRUCTION SCHEDULING	NS-94	VEHICLE AND EQUIPMENT MAINTENANCE
SS-89	CONSTRUCTION SCHEDULING	NS-95	VEHICLE AND EQUIPMENT MAINTENANCE
SS-90	CONSTRUCTION SCHEDULING	NS-96	VEHICLE AND EQUIPMENT MAINTENANCE
SS-91	CONSTRUCTION SCHEDULING	NS-97	VEHICLE AND EQUIPMENT MAINTENANCE
SS-92	CONSTRUCTION SCHEDULING	NS-98	VEHICLE AND EQUIPMENT MAINTENANCE
SS-93	CONSTRUCTION SCHEDULING	NS-99	VEHICLE AND EQUIPMENT MAINTENANCE
SS-94	CONSTRUCTION SCHEDULING	NS-100	VEHICLE AND EQUIPMENT MAINTENANCE

POST-CONSTRUCTION INSPECTION AND MAINTENANCE REQUIREMENTS

EROSION CONTROL:

1. STORM DRAIN INLETS AND JUNCTION BOXES SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
2. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
3. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
4. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
5. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
6. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
7. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
8. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
9. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
10. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
11. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
12. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
13. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
14. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
15. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
16. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
17. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
18. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
19. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
20. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.


1. STORM DRAIN INLETS AND JUNCTION BOXES SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
2. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
3. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
4. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
5. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
6. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
7. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
8. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
9. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
10. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
11. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
12. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
13. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
14. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
15. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
16. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
17. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
18. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
19. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.
20. CULVERTS SHALL BE INSPECTED ANNUALLY PRIOR TO OCTOBER 1ST. THEY SHALL ALSO BE INSPECTED WHEN IT IS DETERMINED THAT THE SYSTEM HAS NOT BEEN MAINTAINED PROPERLY.


NOT FOR CONSTRUCTION

- EROSION CONTROL MEASURES**
1. THIS PLAN SHALL BE USED IN CONJUNCTION WITH THE PROJECT STORM WATER POLLUTION PREVENTION PLAN (SWPPP) AND NUMBERED MEASURES SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE CONSTRUCTION PERIOD.
 2. TOTAL DISTURBANCE AREA: 5.6 ACRES.
 3. THIS PROJECT WILL INCURE A POINT FROM THE REGIONAL WATER QUALITY CONTROL BOARD.
 4. THE CONTRACTOR SHALL SUBMIT A SLOPE PREVENTION AND RESPONSE PLAN TO THE COUNTY AND REGIONAL WATER QUALITY CONTROL BOARD FOR APPROVAL.
 5. EROSION IS TO BE CONTROLLED AT ALL TIMES THROUGH PROPER MEASURES SHOWN ARE TO BE IMPLEMENTED AT A MINIMUM BEGINNING OCTOBER 15TH AND APRIL 15TH. THE AVOIDANCE OF SITE EROSION CONTROL MEASURES IS TO PREVENT EROSION AND TO PREVENT EROSION FROM LEAVING THE SITE ON EXISTING ANY WEATHERING OR RECEIVING RAIN. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SEE THAT ANY ADDITIONAL MEASURES NECESSARY TO CONTROL SITE EROSION AND PREVENT SEDIMENT TRANSPORT OFF-SITE ARE IMPLEMENTED.
 6. UNNECESSARY DRIVING AND DISTURBANCE OF SOIL SHALL BE AVOIDED (SEE 16-17).
 7. RAINFALL FROM THE CONSTRUCTION SITE MUST NOT BE ALLOWED TO FLOW OVER ANY FILL SLOPES.
 8. ALL EXCAVATED MATERIAL NOT SUITABLE FOR FILL OR OTHER USE ON-SITE SHALL BE REMOVED TO AN APPROVED DISPOSAL SITE.
 9. FOR ON-SITE CONSTRUCTION & STAGING AREAS SITE HOUSEKEEPING, MATERIALS MANAGEMENT, & EQUIPMENT MANAGEMENT SHALL BE CONSISTENT WITH THE REQUIREMENTS OF THE

LEGEND

SYMBOL	CALTRANS BMP #	DESCRIPTION	SYMBOL	CALTRANS BMP #	DESCRIPTION
[Symbol]	SS-9	EARTH DICES, DRAINAGE SWALES AND LINED DITCHES	[Symbol]	SS-2, SS-4	SOIL STABILIZATION (PROPOSED ON ALL DISTURBED SOILS)
[Symbol]	SS-1, SS-6, SS-8	LINEAR SEDIMENT BARRIER, FIBER ROLLS, SILT FENCE, OR COMPOST SOCK (CONTRACTOR'S OPTION)	[Symbol]	SS-3, SS-5, SS-7, SS-10	TEMPORARY STABILIZATION PER CIVIL PLAN
[Symbol]	SS-1	TS1, T60 SILT FENCE	[Symbol]	TS8	STABILIZED CONSTRUCTION ENTRANCE/EXIT ON THE WASH
[Symbol]	SS-7	STREET SWEEPING	[Symbol]	TM-1	MATERIAL STORAGE AND WASTE MANAGEMENT AREA
[Symbol]	SS-10	INLET PROTECTION	[Symbol]	TM-3	TEMPORARY STOOPLES
[Symbol]	TM-6	CONCRETE WASTE MANAGEMENT (WASHOUT) AREA	[Symbol]	TM-9	SANITARY FACILITIES
[Symbol]	TM-8	TS1, T62, T64	[Symbol]	DIR	DIRECTION OF DRAINAGE





WE WHITSON ENGINEERS

2425 Porter Street • Suite 2 • Soquel, California 95073
831 464-9363 • Fax 831 464-2316

Job No.: 3193.03

MEMORANDUM

DATE: August 24, 2015

TO: Michael Lynch, AIA
CGL Companies

FROM: Rodney Trujillo, P.E. *RT*

Cc: Cameron Glass – CGL Companies
Tom Russel – Moss & Associates

SUBJECT: Rountree Jail Facility
Septic System Condition

The X-building sewage effluent drains to an existing onsite septic system. Preliminary Sewage Disposal System Plan prepared by Steve Brooks R.E.H.S Consultant ("record drawings"), date unknown, show a 6" sewer lateral from the building that connects to a diversion manhole. The diversion manhole distributes effluent to two rows of septic tanks with a 21,000 gallon total capacity before draining to a 2,000 gallon pump tank. A single pump forces effluent to existing leach fields that are located at the northwest corner of the site.

The previous use for the X-building housed 162 inmates at full capacity. The proposed use for the rehabilitation project reduces the number of beds from 162 to 64 beds. The occupancy reduction results in a substantial effluent generation reduction for the facility. Therefore, expansion of the existing septic system for the new use is not proposed.

The septic system lines and leach fields were inspected and videoed by Mr. Rooter. Based on my conversation with Albert of Mr. Rooter the system is in serviceable condition but they recommend that one leach field should be cleaned by "HydroScrubbing" in conjunction with treatment with natural enzymes.

Based on conversations with Pat Delia of the County General Services Department who performs maintenance on the septic system, it is also recommended that the existing diversion valve be replaced and the single effluent pump be replaced with a duplex pump with alarm and pump controller.